
SECTION 5
SPECIFICATIONS

SECTION 011100 - SUMMARY OF WORK

PART 1 - GENERAL

1.1 LOCATION OF THE PROJECT

- A. The project is located along Wheeling Creek in the from Alice Ave to Homewood Ave in the Valleyview Neighborhood of Wheeling.

1.2 PROJECT DESCRIPTION

- A. The project includes the installation and replacement of failing lines of a combined sanitary sewer, replacement of combined sewer overflows and, and sanitary sewer lining installation to aid in reducing combined sewer overflows into Wheeling Creek.

1.3 SPECIFICATIONS

- A. In general, these Specifications describe the work to be performed by the various trades, other than work specifically excluded. It shall be the responsibility of the Contractor and Subcontractors to perform all work incidental to their trade, whether or not specific mention is made of each item, unless such incidentals are included under another Item.
- B. It is advised that the Contractor and all Subcontractors familiarize themselves with the contents of the complete Specifications, particularly for the trades preceding, following, related or adjacent to their work.

END OF SECTION 011100

SECTION 011419 – USE OF SITE

PART 1 - GENERAL

1.1 GENERAL

- A. The Contractor will be allowed the use of as much of the site designated for the improvements as is necessary for his operation.

1.2 USE OF STREETS

- A. During the progress of the work, the Contractor shall make ample provisions for both vehicle and pedestrian traffic on any public street and shall indemnify and save harmless the Owner from any expense whatsoever due to their operations over said streets. The Contractor shall also provide free access to all the fire hydrants, water, and gas valves located along the line of his work. Gutters and waterways must be kept open or other provisions made for the removal of storm water. Street intersections may be blocked only one-half at a time, and the Contractor shall lay and maintain temporary driveways, bridges and crossings, such as in the opinion of the Engineer are necessary to reasonably accommodate the public.
- B. In the event of the Contractor's failure to comply with these provisions, the Owner may cause the same to be done, and may deduct the cost of such work from any monies due the Contractor under this Agreement, but the performance of such work by the Owner at its instance shall serve in no way to release the Contractor from his general or particular liability for the safety of the public or the work.
- C. The Contractor shall repair at no cost to the Owner, all existing roads, parking areas, grassed areas that are damaged due to the execution of his work. The Contractor shall remove daily all mud, soil and debris that may be tracked onto existing streets, drives, or walks by his equipment or that of subcontractors or suppliers.

1.3 CLOSING STREETS TO TRAFFIC

The Contractor may with the approval of the Engineer, close streets, or parts of streets, to vehicular traffic. The streets are to remain closed as long as the construction work or the condition of the finished work requires or as determined by the Engineer. The Engineer shall be the judge of how many streets or parts of streets it is necessary for the Contractor to close at any time, and may refuse to permit the closing of additional streets to traffic until the majority of the work on the closed streets is completed and they are opened to traffic.

1.4 RIGHTS-OF-WAY

- A. Whenever it is required to perform work within the limits of public or private property or in rights-of-way, such work shall be done in conformity with all agreements between the Owner and the owners of such. Care shall be taken to avoid injury to the premises entered, which premises shall be left in a neat and orderly condition by the removal of

rubbish and the grading of surplus materials, and the restoration of said public or private property to the same general conditions as pertained at the time of entry for work to be performed under this contract.

- B. The Contractor shall not (except after consent from the proper parties) enter or occupy with men, tools or equipment, any land outside the rights-of-way or property of the Owner.
- C. When the Contractor performs construction within 10 ft. of a right-of-way or easement line, he shall place tall stakes properly identified at points of change in width or direction of the right-of-way or easement line and at points along the line so that at least two stakes can be seen distinctly from any point on the line.

1.5 EASEMENTS

- A. Where the work is to be constructed upon easements, such easements will be secured by the Owner without cost to the Contractor. The Contractor shall not enter upon or occupy any private property outside of the limits of the easements furnished.
- B. Care shall be taken to avoid injury to the premises entered, which premises shall be left in a neat and orderly condition by the removal of rubbish and the grading of surplus materials, and the restoration of said public or private property to the same general conditions as pertained at the time of entry for work to be performed under this contract.

1.6 PROTECTING EXISTING BUILDINGS, STRUCTURES AND ROADWAYS

- A. The Contractor shall, at his own expense, shore up and protect any buildings, roadways, utilities or other public or private structures which may be encountered or endangered in the prosecution of the work, and that may not be otherwise provided for, and he shall repair and make good any damages caused to any such property by reason of his operations. All existing fences removed due to the prosecution of the work shall be replaced by the Contractor. No extra payment will be made for said work or material, but the cost of this work must be included in the price stipulated for the work to be done under this contract.

1.7 SITE FACILITIES

- A. The Contractor shall furnish and place sufficient quantities of portable toilet facilities at locations convenient for use by the Contractor's personnel, Subcontractors, the Engineer, and the Owner.

1.8 RESTORATION

- A. The contractor shall restore all areas per the plans and specifications and if not specified, at least to the condition existing prior to the start of work.

END OF SECTION 011419

SECTION 012513 – PRODUCT SUBSTITUTION PROCEDURES

PART 1 - GENERAL

1.1 MATERIALS AND EQUIPMENT

- A. In the specifications and on the Engineer's drawings, are specified and shown certain pieces of equipment and materials deemed most suitable for the service anticipated. This is not done to eliminate other equipment and materials equally as good and efficient. The Contractor shall prepare his bid on the particular materials and equipment specified. Following the award of the contract, should the Contractor desire to use other equipment and materials, he shall submit to the Owner a written request for such change and state the advantage to the Owner and the savings or additional cost involved by the proposed substitution. The determination as to whether or not such change will be permitted rests with the Owner and the Engineer.
- B. Each major item of equipment shall be inspected by a manufacturer's representative during installation and upon completion of the work. The Contractor shall supply the Engineer with a certificate of such inspection.

END OF SECTION 012513

SECTION 013119 - PROJECT MEETINGS

PART 1 - GENERAL

1.1 PRECONSTRUCTION CONFERENCE

- A. Prior to the Contractor beginning any work on the project, the Owner will schedule and hold a preconstruction conference to discuss all aspects of the Project.
- B. The Contractor shall be present and be prepared to comment in detail on all aspects of his work.
- C. The Contractor shall submit a progress schedule prior to the conference and be prepared to present at the preconstruction conference a proposed construction progress schedule, erosion control plan, quality control program, concrete mix designs, asphalt mix designs (JMF), etc. Approval of each by the Engineer is required prior to the start of any Work.
- D. Included in the construction progress schedule shall be an implementation sequence of the proposed erosion control efforts required by the contract.

1.2 PROGRESS MEETINGS

- A. Progress meetings will be held generally monthly or as needed at a location to be determined by the Owner on a regularly scheduled day mutually convenient to the Owner, Contractor, and Engineer. The Contractors Superintendent and authorized representative shall attend all progress meetings.
- B. The Contractor shall provide a written update of the construction progress schedule, and a list of any claims at every progress meeting and be prepared to comment in detail on all aspects of his work.

END OF SECTION 013119

SECTION 013216 – CONSTRUCTION PROGRESS SCHEDULE

PART 1 - GENERAL

1.1 PROGRESS SCHEDULE

- A. Immediately after signing the Contract, the General Construction Contractor shall prepare a graphic progress schedule in accordance with General Conditions 2.05, indicating the work to be executed during each month and the rate of expected progress to secure completion on the agreed-upon completion date. The progress schedule shall be submitted and approved in accordance with General Conditions 2.07 by the Engineer and Owner prior to starting Work on the site. Copies of such graphic progress charts, upon which has been indicated the actual progress, shall be furnished to the Engineer with each requisition for payment.

- B. Should the rate of progress fall materially behind the scheduled rate of progress, and unless the delay is authorized by the Engineer, each offending Contractor shall furnish additional labor, work overtime, or take other necessary means required for completion of the work on the scheduled date. No additional compensation beyond the set Contract price shall be paid for action taken or overtime expense incurred in maintaining scheduled progress.

END OF SECTION 013216

SECTION 013323 - SHOP DRAWINGS, PRODUCT DATA AND SAMPLES

PART 1 - GENERAL

1.1 GENERAL

- A. The Contractor shall submit detailed drawings, acceptable catalog data, specifications and material certifications for all equipment and materials specified or required for the proper completion of the work.
- B. The intent of these items is to demonstrate compliance with the design concept of the work and to provide the detailed information necessary for the fabrication, assembly and installation of the work specified. It is not intended that every detail of all parts of manufactured equipment be submitted, however sufficient detail will be required to ascertain compliance with the specifications and establish the quality of the equipment proposed.

Shop Drawings shall be sufficiently clear and complete to enable the Engineer/Architect and Owner to determine that items proposed to be furnished conform to the specifications and that items delivered to the site are actually those that have been reviewed.

- C. It is emphasized that the Engineer/Architect's review of Contractor's submitted data is for general conformance to the contract drawings and specifications but subject to the detailed requirements of drawings and specifications. Although the Engineer/Architect may review submitted data in detail, such review is an effort to discover errors and omissions in Contractor's drawings. The Engineer/Architect's review shall in no way relieve the Contractor of his obligation to properly coordinate the work and to Engineer/Architect the details of the work in such manner that the purposes and intent of the contract will be achieved. Such review by the Engineer/Architect shall not be construed as placing on him or on the Owner any responsibility for the accuracy and for proper fit, functioning or performance of any phase of the work included in the contract.
- D. Shop Drawings shall be submitted in proper sequence and with due regard to the time required for checking, transmittal and review so as to cause no delay in the work. The Contractor's failure to transmit appropriate submittals to the Engineer/Architect sufficiently in advance of the work shall not be grounds for time extension.
- E. The Contractor shall submit Shop Drawings for all fabricated work and for all manufactured items required to be furnished in the Contract in accordance with the General Provisions and as specified herein. Shop Drawings shall be submitted in sufficient time to allow at least twenty-one (21) calendar days after receipt of the Shop Drawings from the Contractor for checking and processing by the Engineer/Architect.
- F. It is the responsibility of each Prime Contractor to furnish to all other Prime Contractors and especially the General Construction Contractor reviewed Shop Drawings for guidance in interfacing the various trades; i.e., sleeves, inserts, anchor bolts, terminations, and space requirements.

- G. No work shall be performed requiring Shop Drawings until same have been reviewed by Engineer/Architect.
- H. Accepted and reviewed Shop Drawings shall not be construed as approval of changes from Contract plan and specification requirements.
- I. The Engineer/Architect will review the first and second Shop Drawing item submittals at no cost to the Contractor. Review of the third submittal and any subsequent submittal will be at the Contractor's expense. Payment will be deducted from the Contract amount at a rate of 2.8 times direct labor cost plus expenses.

1.2 SUBMITTAL PROCEDURE

- A. All required submissions shall be made to the Engineer/Architect by the Contractor only. Any data prepared by subcontractors and suppliers and all correspondence originating with subcontractors, suppliers, etc., shall be submitted through the Contractor.
- B. Contractor shall review and approve all Shop Drawings prior to submission. Contractor's approval shall constitute a representation to Owner and Engineer/Architect that Contractor has either determined and verified all quantities, dimensions, field construction criteria, materials, catalog numbers, and similar data or assumes full responsibility for doing so, and that Contractor has reviewed or coordinated each Shop Drawing or sample with the requirements of the work and the Contract Documents.
- C. Submittal Preparation: Mark each submittal with a permanent label or page for identification. Provide the following information on the label for proper processing and recording of action taken:
 - 1. Location
 - 2. Project Name
 - 3. Contract
 - 4. Name and Address of Engineer/Architect
 - 5. Name and Address of Contractor
 - 6. Name and Address of Subcontractor
 - 7. Name and Address of Supplier
 - 8. Name of Manufacturer
 - 9. Number and Title of appropriate Specification Section
 - 10. Drawing Number and Detail References, as appropriate.
 - 11. Submittal Sequence or Log Reference Number.
 - a. Provide a space on the label for the Contractor's review and approval markings and a space for the Engineer/Architect's "Action Stamp".
- D. Each Shop Drawing, sample and product data submitted by the Contractor shall have affixed to it the following Certification Statement including the Contractor's Company name and signed by the Contractor:

Certification Statement: By this submittal, I hereby represent that I have determined and verified all field measurements, field construction criteria, materials, dimensions, catalog numbers and similar data and I have checked and coordinated each item with other applicable approved shop drawings and all Contract requirements.

Signature

Date

Company

- E. Shop Drawings shall be submitted in not less than six (6) copies to the Engineer/Architect at the address specified at the Preconstruction Conference. Electronic submittals maybe permitted at the discretion of the Engineer.
- F. At the time of each submission, Contractor shall in writing identify any deviations that the Shop Drawings or samples may have from the requirements of the Contract Documents.
- G. Drawings shall be clean, legible and shall show necessary working dimensions, arrangement, material finish, erection data, and like information needed to define what is to be furnished and to establish its suitability for the intended use. Specifications may be required for equipment or materials to establish any characteristics of performance where such are pertinent. Suitable catalog data sheets showing all options and marked with complete model numbers may, in certain instances, be sufficient to define the articles which it is proposed to furnish.
- H. For product which require submittal of samples, furnish samples so as not to delay fabrication, allowing the Engineer reasonable time for the consideration of the samples submitted. Properly label samples, indicating the material or product represented, its place of origin, the names of the vendor and Contractor and the name of the project for which it is intended. Ship samples prepaid. Accompany samples with pertinent data required to judge the quality and acceptability of the sample, such as certified test records and, where required for proper evaluation, certified chemical analyses.

1.3 REVIEW PROCEDURE

- A. Engineer/Architect will review with reasonable promptness all properly submitted Shop Drawings. Such review shall be only for conformance with the design concept of the Project and for compliance with the information given in the plans and specifications and shall not extend to means, methods, sequences, techniques or procedures of construction or to safety precautions or programs incident thereto.
- B. The review of a separate item as such will not constitute the review of the assembly in which the item functions. The Contractor shall submit entire systems as a package.
- C. All Shop Drawings submitted for review shall be stamped with the Engineer/Architect's action and associated comments.

- D. Except for submittals for record, information or similar purposes, where action and return is required or requested, the Engineer/Architect will review each submittal, mark to indicate action taken, and return accordingly. Compliance with specified characteristics is the Contractor's responsibility.

Action Stamp: The Engineer/Architect will stamp each submittal with a uniform, self-explanatory action stamp. The stamp will be appropriately marked, as follows, to indicate the action taken:

1. If Shop Drawings are found to be in general compliance, such review will be indicated by marking the first statement.
 2. If only minor notes in reasonable number are needed, the Engineer/Architect will make same on all copies and mark the second statement. Shop Drawings so marked need not be resubmitted.
 3. If the submitted Shop Drawings are incomplete or inadequate, the Engineer/Architect will mark the third statement, request such additional information as required, and explain the reasons for revision. The Contractor shall be responsible for revisions, and/or providing needed information, without undue delay, until such Shop Drawings are acceptable. Shop Drawings marked with No. 3 shall be completed resubmitted.
 4. If the submitted Shop Drawings are not in accordance with the Contract Documents, the Engineer/Architect will mark the fourth statement. The Contractor will be responsible to submit a new offering conforming to specific products specified herein and/or as directed per review citations.
- E. No submittal requiring a Change Order for either value or substitution or both, will be returned until the Change Order is approved or otherwise directed by the Owner.

APPLICATION FOR USE OF SUBSTITUTE ITEM

TO: _____

PROJECT: _____

SPECIFIED ITEM:

Page	Paragraph	Description
A.		The undersigned requests consideration of the following as a substitute item in accordance with Article 6.05 of the General Conditions.
B.		Change in Contract Price (indicate + or -) \$ _____
C.		Attached data includes product description, specifications, drawings, photographs, references, past problems and remedies, and performance and test data adequate for evaluation of the request; applicable portions of the data are clearly identified. For consideration of the attached data as SHOP DRAWINGS, submittal shall be in accordance with requirements of Section 013323.
D.		Attached data also includes a description of changes to the Contract Documents that the proposed substitution will require for its proper installation.

The undersigned certifies that the following paragraphs, unless modified by attachments are correct:

1. The proposed substitute does not affect dimensions shown on Drawings.
2. The undersigned will pay for changes to the building design, including engineering design, detailing, and construction costs caused by the requested substitution.
3. The proposed substitution will have no adverse affect on other contractors, the construction schedule, or specified warranty requirements. (If proposed substitution affects construction schedule, indicate below using + or -)

_____ CONSECUTIVE CALENDAR DAYS

4. Maintenance and service parts will be locally available for the proposed substitution.

The undersigned further states that the function, appearance, and quality of the proposed substitution are equivalent or superior to the specified item, and agrees to reimburse the OWNER for the charges of the ENGINEER for evaluating this proposed substitute item.

E. Signature:

Firm:

Address:

Telephone:

Date:

Attachments:

For use by ENGINEER:

_____ Accepted as evidenced by affixed SHOP DRAWING REVIEW stamp.

_____ Accepted as evidenced by included CHANGE ORDER.

_____ Not accepted as submitted. See Remarks.

_____ Acceptance requires completion of submittal as required for SHOP DRAWINGS.

_____ Not accepted. Do not resubmit.

By:

Date:

Remarks:

APPLICATION FOR USE OF "OR-EQUAL" ITEM

TO: _____

PROJECT: _____

SPECIFIED ITEM:

Page	Paragraph	Description
------	-----------	-------------

A. The undersigned requests consideration of the following as an "or-equal" item in accordance with Article 6.05 of the General Conditions.

B. Change in Contract Price (indicate + or -) \$ _____

C. Attached data includes product description, specifications, drawings, photographs, references, past problems and remedies, and performance and test data adequate for evaluation of the request; applicable portions of the data are clearly identified. For consideration of the attached data as SHOP DRAWINGS, submittal shall be in accordance with requirements of Section 013323.

D. Signature:

Firm: _____

Address: _____

Telephone: _____ Date: _____

Attachments: _____

For use by ENGINEER:

_____ Accepted as evidenced by affixed SHOP DRAWING REVIEW stamp.

_____ Accepted as evidenced by included CHANGE ORDER.

_____ Not accepted as submitted. See Remarks.

_____ Acceptance requires completion of submittal as required for SHOP DRAWINGS.

_____ Not accepted. Do not resubmit.

By: _____ Date: _____

Remarks: _____

END OF SECTION 013323

SECTION 013543 - ENVIRONMENTAL PROTECTION

PART 1 - GENERAL

1.1 UNNECESSARY NOISE, DUST AND ODORS

- A. The Contractor's performance of this contract shall be conducted so as to eliminate all unnecessary noise, dust and odors.

1.2 SEWAGE, SURFACE AND FLOOD FLOWS

- A. The Contractor shall take whatever action is necessary to provide all necessary tools, equipment and machinery to adequately handle all sewage, surface flows and flood flows which may be encountered during the performance of the work. The entire cost of and liability for handling such flows is the responsibility of the Contractor and shall be included in the price for the appropriate item.

1.3 WORK IN FREEZING WEATHER

- A. Written permission from the Engineer shall be obtained before any work is performed which, in the judgment of the Engineer, may be affected by frost, cold, or snow. When work is performed under such conditions, the Contractor shall provide facilities for heating the materials and for protecting the finished work.

1.4 POLLUTION CONTROL

- A. It shall be the responsibility of the Contractor to prevent or limit pollution of air and water resulting from his operations.
- B. The Contractor shall perform work required to prevent soil from eroding or otherwise entering onto all paved areas and into natural watercourses, ditches, and public sewer systems. This work shall conform to all local ordinances and/or regulations.
- C. The Contractor shall perform work required to prevent dust attributable to his operations from entering the atmosphere. Dust on unsurfaced streets or parking areas and any remaining dust on surfaced streets shall be controlled with water and/or calcium chloride dust palliative as needed.
- D. Any material removed from sanitary or storm sewers shall be disposed in accordance with all applicable regulations.

END OF SECTION 013543

SECTION 015100 - TEMPORARY POWER SERVICE

PART 1 - GENERAL

1.1 ELECTRICAL POWER

- A. The Contractor shall furnish at his own expense all electrical power which may be required for the project. All temporary lines shall be furnished and installed by the Contractor at his own expense in a manner which meets the approval of the Engineer, and shall be removed by the Contractor at the completion of the construction.

END OF SECTION 015100

SECTION 015136 - TEMPORARY WATER

PART 1 - GENERAL

1.1 WATER

- A. Water needed for work shall be included in contractors bid ancillary to other bid items. Surface water withdrawal from Wheeling Creek and Ohio River is allowed and acceptable. Withdrawal from Wheeling Water utility requires a temporary meter. Contractor will be billed for water used based on City of Wheeling water rates on a monthly basis.

END OF SECTION 015136

SECTION 015526 - TEMPORARY TRAFFIC CONTROL DEVICES

PART 1 - GENERAL

1.1 BARRICADES, SIGNS AND LIGHTS

- A. The Contractor shall employ watchmen on the work when and as necessary. The Contractor shall erect and maintain such strong and suitable barriers and such lights as will effectively prevent the occurrence of any accident to health, limb or property. Lights shall be maintained between the hours of one-half (1/2) hour after sunset and one-half (1/2) hour before sunrise.
- B. No manhole, trench, excavation will be left open awaiting connection or removal at a later date by the Contractor's forces or others but shall be temporarily backfilled and resurfaced if applicable with a temporary pavement passable to traffic at no additional cost to the Owner.
- C. In addition to other safety requirements, a minimum of four (4) foot high fence will be incorporated around any shaft or manhole or other excavation left open at the end of a day's work.

1.2 MAINTENANCE OF TRAFFIC

- A. The Contractor is required to provide maintenance of traffic in conformance with the West Virginia Department of Transportation Manual on Temporary Traffic Control for Streets and Highways.
- B. The Contractor is also responsible for maintaining local access to all residences and businesses along the route of the construction and to provide whatever temporary materials are necessary to provide a safe, adequate drive surface.

END OF SECTION 015526

SECTION 016600 - PRODUCT HANDLING AND PROTECTION

PART 1 - GENERAL

1.1 DELIVERY AND STORAGE OF MATERIALS

- A. The Contractor shall be responsible for delivery and storage of all materials.
- B. The Contractor shall coordinate with the Engineer on the arrangement for storing construction materials and equipment. Deliveries of all construction materials and equipment should be made at suitable times.
- C. The Contractor shall store all materials required for the performance of this contract at sites designated by the Engineer or Owner.
- D. All stockpiles shall be neat, compact, completely safe, and barricaded with warning lights if necessary.
- E. Precautions shall be taken so that no shade trees, shrubs, flowers, sidewalks, driveways or other facilities will be damaged by the storage of materials. The Contractor shall be responsible for the restoration of all stockpile sites to their original condition.
- F. Materials, tools and machinery shall not be piled or placed against shade trees, unless they shall be amply protected against injury therefrom. All materials, tools, machinery, etc. stored upon public thoroughfares must be provided with red lights at night time so as to warn the traffic of such obstruction.
- G. Materials shall be so stored as to assure the preservation of their quality and fitness for the work. Stored materials, even though approved before storage, shall again be inspected prior to their use in the work. Stored materials shall be located so as to facilitate their prompt inspection. Approved portions of the construction site may be used for storage purposes and for the placing of the Contractor's plant and equipment, but any additional space required therefore must be provided by the Contractor at his expense. Private property shall not be used for storage purposes without written permission of the property owner or lessee, and copies of such written permission shall be furnished the Engineer. All storage sites shall be restored to their original condition by the Contractor at his expense.

END OF SECTION 016600

SECTION 017800 - FINAL COMPLIANCE AND SUBMITTALS

PART 1 - GENERAL

- 1.1 The following forms and related sign-offs shall be documented in accordance with provisions of the contract. These forms shall be completed by the Contractor and approved by the Owner before final retainer is approved for release. Forms for Items A to D will be attached to the Contractor's executed copy of the contract.
- A. Certificate of Substantial Completion (To be submitted at time of Substantial Completion).
 - B. Contractor's Certification of Completion.
 - C. Consent of Surety Company for Final Payment.
 - D. Affidavit of Final Acceptance Date and Correction Period.
 - E. Record Drawing and Documents.

END OF SECTION 017800

SECTION 017821 - CLEANING AND PROTECTION

PART 1 - GENERAL

1.1 GENERAL

- A. On or before the completion date for the Work, the Contractor shall tear down and remove all temporary structures built by him, all construction plant used by him, and shall repair and replace all parts of existing embankments, fences or other structures which were removed or injured by his operations or by the employees of the Contractor. The Contractor shall thoroughly clean out all buildings, sewers, drains, pipes, manholes, inlets and miscellaneous and appurtenant structures, and shall remove all rubbish leaving the grounds in a neat and satisfactory condition.
- B. As circumstances require and when ordered by the Engineer, the Contractor shall clean the road, driveway, and/or sidewalk on which construction activity under this contract has resulted in dirt or any other foreign material being deposited with an automatic self-contained mechanical sweeper with integral water spray, vacuum and on-board or supplementary containment.
- C. Failure to comply with this requirement when ordered by the Engineer or his representative, may serve as cause for the Engineer to stop the work and to withhold any monies due the Contractor until such order has been complied with to the satisfaction of the Engineer.
- D. As the Work progresses, and as may be directed, the Contractor shall remove from the site and dispose of debris and waste material resulting from his work. Particular attention shall be given to minimizing any fire and safety hazard from form materials or from other combustibles as may be used in connection with the work, which should be removed daily.
- E. The Contractor shall wash all windows and other glass surfaces, leaving all areas free from putty marks, paint, etc.
- F. During and after installation, the Contractor shall furnish and maintain satisfactory protection to all equipment against injury by weather, flooding or breakage thereby permitting all work to be left in a new condition at the completion of the contract.

END OF SECTION 017821

SECTION 330130.03 - SEWER FLOW CONTROL

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division-1 Specifications, apply to work of this Section.

1.2 DESCRIPTION OF WORK

- A. The intent of this work is to control the flow in the sewer to enable the successful inspection, rehabilitation or replacement of the pipe.
- B. Depth of flow shall not exceed that shown below for the respective pipe sizes when performing television inspection, joint testing and/or sealing.

Pipe Diameter Maximum Depth of Flow

1.	6" - 10" Pipe	-	25% of pipe diameter
2.	12" - 24" Pipe	-	33% of pipe diameter
3.	27" & up Pipe	-	40% of pipe diameter

- C. Flow shall be controlled or bypassed from sewer sections being lined or replaced. The methods used shall be in accordance with the work being performed.

1.3 QUALITY ASSURANCE

- A. When flow in a sewer line is plugged, blocked, or bypassed; sufficient precautions must be taken to protect the sewer lines from damage that might result from sewer surcharging. Further, precautions must be taken to insure that sewer flow control operations do not cause flooding or damage to public or private property being served by the sewers involved.

1.4 SUBMITTALS

- A. The Contractor shall submit a written request for Sewer Flow Control, specify the method and equipment to be used, and receive approval from the Owner prior to performing the work.
- B. For bypass pumping, submit shop drawings in accordance with the General Requirements showing pumps, piping layout plan and dimensions, schedule of pipe fittings and specials, materials and class for each size and type of pipe, joint details, and any special provisions required for assembly. Provide a wet weather operation plan which describes what procedures will be followed when flow exceeds pumping capacity.

PART 2 - PRODUCTS

2.1 EQUIPMENT

- A. Sewer plugs shall be so designed that all or any portion of the sewage can be quickly released.
- B. Pumping and bypassing:
- C. Pumps bypass pipe, fittings, and joining methods shall be suitable and of a type normally used for raw sanitary sewage.
 - 1. The bypass system shall be of sufficient capacity to handle existing peak dry weather flow plus additional flow that may occur during a rainstorm unless otherwise provided for by an approved wet weather operation plan.
 - 2. If pumping is required on a 24-hour basis, engines shall be equipped in a manner to keep noise to a minimum.
 - 3. Bypass piping to be furnished and installed shall include, but not limited to all pipe, fittings, specials, bends, beveled pipe, adapters, bulkheads, stoppers, plugs, joint restraints, joints and jointing materials, and pipe supports. Bypass piping shall be rated to twice the system operating pressure.
- D. Hydrocleaning equipment shall be equipped with high-velocity nozzles capable of pulling flow away from the pipe section being televised. The equipment shall carry its own water tank, auxiliary engines, pumps and hydraulically driven hose reel.

PART 3 - EXECUTION

3.1 FIELD QUALITY CONTROL

- A. The Contractor shall continuously supervise the level of water in the upstream and downstream sewers to ensure that harmful surcharging does not occur. The Contractor shall be responsible for any damage to the system and/or to public or private property resulting from improper execution of flow control measures.

3.2 PLUGGING OR BLOCKING

- A. A sewer line plug shall be inserted into the line upstream of the section being worked. During TV inspection, testing and sealing operations, flow shall be reduced to within the limits specified above. After the work has been completed, flow shall be restored to normal.

3.3 PUMPING AND BYPASSING

- A. When pumping and bypassing is required, the Contractor shall supply and install the pumps, conduits, and other equipment to divert the flow around the section in which work is to be performed. Under no circumstances will the discharge of raw sewage to other than sanitary sewers be allowed.
- B. The Contractor shall be responsible for furnishing the necessary labor and supervision to set up and operate the pumping and bypassing system.
- C. The proposed bypassing system shall be set up to allow traffic flow to local residents and businesses.
- D. Locate facilities where they will serve the Project adequately and result in minimum interference with performance of the Work. Relocate and modify facilities as required.
- E. Make connections to all existing force mains being bypassed.
- F. Install temporary bypass piping with restrained joints at horizontal and vertical changes in direction.
- G. Provide granular material for bedding and encasement of temporary piping when buried below pavement.
- H. Field test bypass piping and obtain approval from the Engineer prior to placing bypass system in service.
- I. Do not remove pumping and bypass system until it is no longer needed and can be replaced by authorized use of completed permanent facilities.

3.4 HYDRAULIC FLOW CONTROL

- A. This method shall be used for sewer televising only. The Contractor shall position the high-velocity nozzle no less than five (5) feet ahead of the television camera. Pressures shall be just sufficient to reduce the flow level in front of the camera to the specified depth. The jet nozzle shall be reeled in at the same rate as the forward movement of the television camera to maintain the separation distance.

END OF SECTION 330130.03

SECTION 330130.72 - CURED-IN-PLACE PIPE LINING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division-1 Specification sections, apply to work of this section.
- B. Other documents which shall be considered part of and included in these specifications
 - 1. ASTM D 543 - Test Method of Resistance of Plastics to Chemical Reagents
 - 2. ASTM D 638 - Test Method for Tensile Properties of Plastics
 - 3. ASTM D 790 - Test Methods for Flexural Properties of Unreinforced and Reinforced Plastics and Electrical Insulating Materials
 - 4. ASTM E 132 - Test Method for Poisson's Ratio at Room Temperature
 - 5. ASTM F1216 - Practice for Rehabilitation of Existing Pipelines and Conduits by the Inversion and Curing of a Resin-Impregnated Tube
 - 6. ASTM F1743 - Standard Practice for Rehabilitation of Existing Pipelines and Conduits by Pulled-in-Place Installation of Cured-in-Place Thermosetting Resin Pipe (CIPP)

1.2 DESCRIPTION OF WORK

- A. The intent of cured-in-place pipe (CIPP) is to rehabilitate sewer lines by installing a flexible polyester felt tube saturated with a thermosetting resin into the existing pipe. When cured and complete, the installed pipe should extend the full length of the pipe section being rehabilitated and shall provide a structurally sound, continuous, tight-fitting, watertight pipe within a pipe. Deficiencies which will be corrected by the finished product include:
 - 1. Cracked and broken pipe caused by poor construction, unstable soil, earth movement, infiltration, roots, destructive loadings, cleaning tool damage, etc.
 - 2. Corrosion of pipe caused by acid attack above the flow line.
 - 3. Erosion of pipe caused by abrasion below the flow level.
 - 4. Degradation of brick pipe caused by loss of masonry.
 - 5. Infiltration of groundwater and soil through leaking pipe joints and structural defects.
 - 6. Exfiltration of transported fluid through leaking pipe joints and structural defects.
 - 7. Inflow of surface water and infiltration of groundwater through unused or illegal connections.

1.3 QUALITY ASSURANCE

- A. In addition to requirements of these specifications, comply with manufacturer's instructions and recommendations for work.

- B. Installer's Qualifications: Firms with at least 5 successfully completed projects having installed an aggregate total of 10,000 linear feet of the submitted manufacturer's cured-in-place liner.

1.4 SUBMITTALS

- A. Submit the latest edition and any revisions thereto of the manufacturer's technical data and installation instructions.
- B. Submit Material Safety Data Sheet(s) for the resins, any other chemical additives, and any other chemicals used in the CIPP system.
- C. Submit certified copies of all test reports on the properties of the proposed resin materials prior to their use. Tests shall be performed by an approved independent testing laboratory or other approved source.
- D. Submit design calculations for the CIPP material thickness for each section of the pipe to be rehabilitated.

PART 2 - PRODUCTS

2.1 GENERAL

- A. All equipment and material shall be of a type that has been generally been in use for a period of five (5) years. Work performed with experimental equipment or material will not be permitted without prior written consent of the Owner.
- B. Products acceptable for cured-in-place pipe.
 - 1. Eco-Liner Epoxy/Felt
 - 2. Inliner
 - 3. Insituform
 - 4. Masterliner
 - 5. National Liner
 - 6. Spinello Liner

2.2 MATERIALS

- A. All materials used in the installation of CIPP shall be equal to or exceed the manufacturer's standards.
 - 1. Resin: The thermosetting resin shall be specifically blended for use with the CIPP process.
 - 2. Tubing: The felt tubing shall be fabricated from material and suitable mechanical strengtheners as recommended by the manufacturer for each specific installation. The tubing shall be properly sized to the actual diameter of the sewer pipe and to the length of the sewer section to be rehabilitated. The Contractor shall be responsible for sizing the liner through field verification of the actual pipe diameter and length.

The uncured tubing shall be designed to withstand the insertion stresses, and to be able to negotiate pipe joint offsets, gaps, and angular changes up to and including forty-five degrees (45°).

3. The nominal specified thickness for each pipe section shall be designated in the Proposal section or Specific Project Requirements section of the specifications or as shown on the plans. The cured material thickness tolerance shall be plus or minus twenty-five percent ($\pm 25\%$) of the specified thickness. The thickness of any inner and/or outer membrane shall not be included.
4. Where specific thicknesses are not provided the following values shall be used to calculate a minimum value.
 - a. All pipe shall be considered fully deteriorated.
 - b. All pipe shall be subjected to soil loads of 120 pounds per cubic foot.
 - c. All pipe shall be subject to AASHTO HS-20 highway loading.
 - d. The water table shall be assumed to be five (5) feet below the ground surface.
 - e. All pipe shall be assumed to have five percent (5%) ovality.
5. The cured pipe material shall conform to the minimum structural standards as listed below. Evidence shall be presented to demonstrate that the long-term modulus of elasticity of the cured product is no less than fifty percent (50%) of the herein specified Modulus of Elasticity (Short-term).

<u>Cured Pipe Material Test</u>	<u>Test Method</u>	<u>Minimum Value</u>
a. Chemical Resistance	ASTM D 543	< allowed loss
b. Tensile Strength	ASTM D 638	3,000 psi
c. Flexural Strength	ASTM D 790	4,500 psi
d. Flexural Modulus of Elasticity	ASTM D 790	250,000 psi
e. Poisson's Ratio	ASTM E 132	0.3

6. Any material failing to meet any of the structural standards of this specification may be rejected or may be cause for changing the material thickness if approved by the Engineer.

PART 3 - EXECUTION

3.1 PREPARATORY PROCEDURES

- A. The Contractor shall notify all homeowners on the manhole section to be lined forty-eight (48) hours in advance of the work to be done. The Contractor shall inform the homeowner of precautions necessary to prevent backup of sewage into the house. Notification shall include language that the work may extend beyond normal permitted working hours, if necessary to reinstate service laterals.
- B. The following preparatory procedures shall be adhered to unless otherwise approved by the Engineer:

1. Cleaning of Sewer Line: Prior to any pipe installation in a designated section of sewer, the Contractor shall clean the sewer line as specified under Sewer Line Cleaning.
2. Inspection of Sewer Line: In accordance with the Television Inspection requirements, the Contractor shall televise the pipe with experienced personnel specially trained in locating breaks, obstacles, and service connections. The interior of the sewer line shall be carefully inspected to determine the location and extent of any structural failures. The location of any conditions which may prevent proper installation of the CIPP shall be noted so that such conditions can be corrected.
3. Connections: While televising the mainline sewer, the Contractor shall accurately measure and record the locations and positions of service connections using a fiberglass or other tape approved by the Engineer. Additionally, the Contractor shall utilize the pan and tilt capabilities of the televising equipment to determine which connections are live (active) and which are not in use.
4. Bypassing Sewage: The Contractor shall bypass the sewage around the section or sections of sewer line that are to be rehabilitated. The bypass shall be made by plugging an existing upstream manhole and pumping the sewage into a downstream manhole or adjacent system. The pump and bypass lines shall be of adequate capacity and size to handle the flow. All bypassing of flow shall be performed as specified under Sewer Flow Control.
5. Line Obstructions: It shall be the responsibility of the Contractor to clear the line of obstructions such as solids, dropped joints, protruding service connections, or collapsed pipe that will prevent installation. If the obstruction(s) could have been removed by bucket machines or by using conventional cleaning methods, no compensation will be granted.
 - a. Internal repairs are protruding service connections, dropped portions of pipe which can be removed or pushed back in place, and other obstructions which cannot be cleared using conventional cleaning methods, but which can be cleared from within the pipe. Such internal repairs shall be approved in writing by the Engineer prior to the commencement of the work and shall be considered as a pay item.
 - b. Point repairs are obstructions that cannot be removed by either conventional sewer cleaning equipment or by internal equipment. The Contractor shall make an excavation to expose and remove or repair the obstruction. Such excavation shall be approved in writing by the Engineer prior to the commencement of the work, shall be performed as specified under Point Repairs, and shall be considered as a pay item.
6. Pre-Insertion Television Inspection: The Contractor shall televise and record the sewer pipe immediately before installing CIPP. This televising is to assure that the pipe is clean and existing pipe conditions are acceptable for lining. Should additional cleaning be required, it shall be provided at no additional cost to the Owner. The cost of this televising shall be included in the cost of CIPP.

3.2 INSTALLATION PROCEDURES

- A. General: The Contractor shall designate a location where the uncured resin in original containers and the fiber felt tube will be impregnated prior to installation. The Contractor shall provide for the Owner's inspection of the materials and impregnation procedure. A resin/catalyst system compatible with the requirements of this method shall be used. The quantities of the liquid thermosetting material shall be sufficient to provide the thickness specified herein. When a proprietary lining technique is used and the licensor's procedures for proper installation differ from these specifications, the licensor's procedures shall govern.
- B. Handling: The Contractor shall exercise care during transportation, storage and handling of the liner system to ensure that it will not be torn, cut, or otherwise damaged. The tube shall be impregnated with resin not more than twenty-four (24) hours before the proposed time of installation. Prior to insertion, the tube shall be stored and transported to the site in a refrigerated truck. The insertion shall take place no later than thirty (30) minutes after the catalyst is placed into the resin mix.
- C. Insertion: The impregnated fiber felt tube shall be inserted through an existing manhole, through the pipe to be rehabilitated, to the designated rehabilitation location. The tube shall be inserted in accordance with the manufacturer's instructions.
- D. Inflation: The inflation/expansion pressure shall be sufficient to hold it tight to the pipe wall, to produce dimples at side connections and flared ends at manhole walls. Care shall be taken not to over stress the felt tube at the elevated curing temperatures, which may cause damage or failure prior to cure.
- E. Curing: After insertion and inflation/expansion is completed, the Contractor shall supply a suitable heat source. The equipment shall be capable of delivering heat throughout the section to raise the curing medium temperature above the recommended minimum value. This minimum temperature shall be determined by the resin/catalyst system employed. The temperature shall be maintained within the manufacturer's recommended limits for the duration of the cure period. The cure period shall be of a duration recommended by the resin manufacturer, as modified for the installation process.
- F. Cool down: The Contractor shall cool the hardened pipe to a temperature below 100°F before relieving the pressure in the liner. Care shall be taken in the release of the pressure so that a vacuum will not be developed that could damage the newly installed pipe.
- G. Sealing Pipe Ends: The Contractor shall seal both ends of the CIPP in accordance with the manufacturer's recommendations for the field conditions. If, due to broken or misaligned sewer pipe at manhole walls, the installed pipe fails to make a tight seal, the Contractor shall apply a sealant at that point. The sealant shall be of a resin mixture compatible with that used in the CIPP process. The end shall be sealed for a distance of at least (1) pipe diameter inside the host pipe.
- H. Testing: After the installation procedures have been performed and curing is complete, but before any service connections are reinstated, the Contractor shall conduct a leakage test on the sewer line to determine if it is watertight.

1. For water cured liners, the test shall be conducted by using the existing hydrostatic head provided by the standpipe. The test time shall be fifteen (15) minutes, during which time no makeup water shall be added to the standpipe. If at the end of the test period, no significant water loss is observed in the standpipe, the watertightness of the cured-in-place pipe will be considered satisfactory.
 2. For air or steam cured liners, the test shall be conducted by removing the bladder and plugging both ends of the cured pipe. The pipe shall then be pressurized with air to a test pressure of one-half (1/2) psi per vertical foot of pipe depth (not exceeding a test pressure of ten (10) psi). The air flow shall be stopped. If the required pressure can be developed and if the pressure decays by less than one (1) psi within four (4) minutes, the watertightness of the liner pipe will be considered satisfactory.
- I. Service Connection Reinstatement: After testing, the Contractor shall reinstate the existing live service connections. This shall generally be done without excavation, from the interior of the pipe by means of a television camera and a remotely controlled cutting device. The work shall be performed by experienced operators so that no blind holes are made in the CIPP. The openings of the existing live service connections shall be cut to not less than ninety percent (90%) of their original size. All cuts shall be free of burrs, frayed edges, or any restriction preventing free flow of the sewage. Excessive cuts, wrong holes, or trial cuts shall not be made and must be repaired at no cost to the Owner to the full satisfaction of the Engineer.

3.3 FINAL ACCEPTANCE

- A. Finish: The finished pipe shall be continuous over the entire length of sewer run between two manholes and be free from significant defects.
1. Any defects which will affect, the intended use, integrity or strength of the pipe shall be repaired, at the Contractor's expense, in a manner mutually agreed by the Owner and the Contractor.
- B. Inspection: After the work is completed, the Contractor shall provide the Owner with a videotape showing both the before and after conditions, including the reinstated service connections.
- C. Testing: Sufficient portions of the trimmings of each end of a CIPP section shall be marked as to location and given to the Engineer for measurements of thickness and testing of structural properties.
- D. Cleanup: After the installation work has been completed and all testing acceptable, the Contractor shall clean up the entire project area. All excess material and debris not incorporated into the permanent installation shall be disposed of by the Contractor.
- E. Warranty: During the warranty period, any defects which affect the integrity or strength of the pipe shall be repaired at the Contractor's expense in a manner mutually agreed by the Owner and the Contractor.

END OF SECTION 330130.72