



CITY OF FOREST PARK
KENN ROAD CORRIDOR IMPROVEMENTS
CITY OF FOREST PARK, HAMILTON COUNTY, OHIO

DATE: 4/18/24
 PROJECT: 230225

Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure
KENN ROAD				
1	251	* PARTIAL DEPTH PAVEMENT REPAIR	210	SY
2	253	* PAVEMENT REPAIR, AS PER PLAN	210	SY
3	254	PAVEMENT PLANING, ASPHALT CONCRETE (2.5")	8,884	SY
4	441	STRESS ABSORBING MEMBRANE (SAMI) TYPE 1	8,884	SY
5	407	TACK COAT, TRACKLESS - SURFACE COURSE (0.06 GALLON/SY)	533	GAL
6	441	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, PG64-22, (449) (1")	285	CY
7	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG 64-22, (449) (1.5")	400	CY
8	SPL	ASPHALT CONCRETE, MISC,; ASPHALT REJUVENATING AGENT	8,884	SY
9	608	5" CONCRETE WALK	872	SF
10	608	ADA CURB RAMP	11	EA
11	609	COMBINATION CURB AND GUTTER, TYPE 2	2,661	LF
12	611	CATCH BASIN RECONSTRUCTION	4	EA
13	611	STORM MANHOLE ADJUSTMENT TO GRADE	7	EA
14	611	SANITARY MANHOLE ADJUSTMENT TO GRADE	9	EA
15	611	* DOWNSPOUT CONDUIT, MISC. : PVC SCH 40 PIPE, 3"	1	LF
16	644	EDGE LINE, 4" SOLID WHITE	2305	LF

* Denotes Contingency Item

Proposal Items List - Not a Bid Form



CITY OF FOREST PARK
KENN ROAD CORRIDOR IMPROVEMENTS
CITY OF FOREST PARK, HAMILTON COUNTY, OHIO

DATE: 4/18/24
 PROJECT: 230225

Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure
17	644	CENTERLINE, 4" DOUBLE SOLID YELLOW	2370	LF
18	644	CHANNELIZING LINE, 8" WHITE	85	LF
19	644	STOP LINE, 24" WHITE	54	LF
20	644	CROSSWALK LINE, 12" WHITE	562	LF
21	644	LANE ARROW, 96" WHITE	3	EA
22	644	COMBO LANE ARROW, 144" WHITE	1	EA
22	644	WORD ON PAVEMENT, 96"	2	EA
23	644	GORE STRIPING, 24" YELLOW	56	LF
24	614	MAINTAINING TRAFFIC	1	LS
23	452	* 6" NON-REINFORCED CONCRETE PAVEMENT (APRONS & SIDEWALK)	1	SF
24	632	DETECTOR LOOP	1	EA
23	632	LOOP DETECTOR TIE-IN	1	EA
24	SPL	METRO SIGNAGE (INCLUDES REMOVAL OF EXISTING)	2	EA
25	SPL	TRASH RECEPTICAL, SEE DETAIL	2	EA
26	SPL	BENCH, SEE DETAIL	2	EA

* Denotes Contingency Item