



THE CITY OF PAINESVILLE WATER TREATMENT PLANT CHLORINE BUILDING

9565 HEADLANDS ROAD, MENTOR, OH
LAKE COUNTY, OHIO

OCTOBER 2024



LOCATION MAP
NOT TO SCALE

APPROVALS

DOUG LEWIS CITY MANAGER DATE

ORIN MCMONIGLE WASTEWATER SUPERINTENDANT DATE

OFFICIALS

CITY MANAGER DOUG LEWIS
 FINANCIAL DIRECTOR BILL PARKINSON
 CHIEF OF POLICE DAN WATERMAN
 FIRE CHIEF TOM HUMMEL

CITY COUNCIL

JIM FODOR PRESIDENT
 CHRISTINE SHOOP WARD 1
 MARIO RODRIGUEZ WARD 2
 NICK AUGUSTINE WARD 3
 PAUL W. HACH II WARD 4
 DERRICK ABNEY COUNCIL AT LARGE
 LORI DINALLO COUNCIL AT LARGE



NO	REVISION	DATE

SCALE: AS SHOWN
 DATE: 10/30/2024
 DESIGNED BY: VMP
 DRAWN BY: VMP
 CHECKED BY: ADT


PROJECT NO:	
232515	
DRAWING NAME	
G-01	
SHEET	OF
1	17

OHIO811
 Before You Dig
 1-800-362-2764
 CALL TWO WORKING DAYS BEFORE YOU DIG
 (NON MEMBERS MUST BE CALLED DIRECTLY)

1. THE SURVEY SHOWN ON THESE PLANS WAS OBSERVED IN THE FIELD FOR CONSTRUCTION PURPOSES ONLY AND MAY NOT BE SUITABLE FOR PROPERTY LINE SURVEYS OR ANY OTHER PURPOSE.
2. UNDERGROUND BUILDING SERVICE UTILITY LINES ARE NOT SHOWN ON THE PLANS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING, MAINTAINING AND REPLACING AS NECESSARY TO ENSURE CONTINUAL SERVICE TO BUILDINGS.
3. THE CONTRACTOR IS RESPONSIBLE TO CALL OHIO UTILITIES PROTECTION SERVICE @ 1-800-362-2764, THREE WORKING DAYS PRIOR TO CONSTRUCTION.



ENGINEER'S PROJECT No. 232515



DANIEL E. BARR
 P.E. No. 64544
 DATE 10/30/2024

GENERAL SYMBOLOGY NOTES:

- THIS IS A STANDARD SHEET SHOWING COMMONLY USED SYMBOLOGY.
- ALL SYMBOLS ARE NOT NECESSARILY USED ON THIS PROJECT.
- SCREENING OR SHADING OF WORK IS USED TO INDICATE EXISTING COMPONENTS OR TO DE-EMPHASIZE NEW IMPROVEMENTS SO AS TO HIGHLIGHT SPECIFIC TRADE WORK. REFER TO CONTEXT OF EACH SHEET FOR USAGE.
- SYMBOLOGY OR DIAGRAMMATICAL LEGENDS MAY BE SHOWN ON INDIVIDUAL SHEETS FOR SCHEDULES, DIAGRAMS, DETAILS, SCHEMATICS OR EQUIPMENT.

DRAWING CODED NOTE TYPES:

- CT CONTRACTUAL NOTES ARE DEPICTED WITH A HEXAGON, SQUARE, CIRCLE OR TRIANGLE. ALL OTHER EXISTING WRITTEN CALLOUTS SHOWN ON THE REUSED SCANNED PLANS FROM PREVIOUS CONTRACT DRAWINGS. (BACKGROUND IMAGES). SECTIONS & DETAILS ARE FOR EXISTING CONDITIONS AND REFERENCE ONLY. MANY OF THOSE NOTES FROM THE SCANNED DRAWINGS PERTAIN TO PREVIOUS WORK DONE. THESE BACKGROUND IMAGES ARE SHOWN IN GRAY.

SERIES:

- GENERAL - G SERIES
- SITE IMPROVEMENTS - C SERIES
- STRUCTURAL - S SERIES
- ARCHITECTURAL - A SERIES
- PROCESS - D SERIES
- MECHANICAL - M SERIES (PLUMBING & HVAC)
- ELECTRICAL - E SERIES
- STANDARD DETAILS - SD SERIES

VALVE OPERATOR ID:

- CH = CHAIN
- EM = ELECTRIC MOTOR
- ES = EXTENSION STEM
- FB = FLOOR BOX
- FS = FLOOR STAND
- GE = GEAR
- HC = HYDRAULIC CYLINDER
- HW = HANDWHEEL
- LE = LEVER
- LW = "L" WRENCH
- ON = OPERATING NUT
- PC = PNEUMATIC CYLINDER
- PD = PNEUMATIC DIAPHRAGM
- TW = "T" WRENCH
- VB = VALVE BOX

PIPE MATERIAL ID:

- BR = BRASS
- BS = BLACK STEEL
- BZ = BRONZE
- CI = GRAY CAST IRON
- CU = COPPER
- CS = CAST IRON
- CT = CARBON STEEL TUBING
- DIP = DUCTILE IRON PIPE
- DR = DIAMETER RATIO
- FRP = FIBERGLASS REINFORCED PLASTIC
- GS = GALVANIZED STEEL
- HDPE = HIGH-DENSITY POLYETHYLENE PIPE
- PVC = POLYVINYL CHLORIDE PIPE
- SS = STAINLESS STEEL
- STL = STEEL PIPE
- SDR = STANDARD DIAMETER RATIO
- SCH = SCHEDULE

PIPE END JOINT ID:

- BE = BELL
- CM = COMPRESSION
- FL = FLANGED
- GR = GROOVED
- LU = LUG
- MJ = MECHANICAL JOINT
- NPT = NATIONAL PIPE THREAD
- RJ = RESTRAINED JOINT
- PE = PLAIN END
- S = SOLDERED
- SJ = SLIP JOINT (PUSH ON)
- SW = SOLVENT WELDED
- TH = THREADED
- W = WELDED

GATE ABBREVIATIONS:

- BG - BULKHEAD GATE
- SG - SLIDE GATE
- SP - STOP PLATE
- SL - STOP LOG
- ALUM - ALUMINUM
- SS - STAINLESS STEEL
- CI - CAST IRON
- POLY - POLYMER
- B/C - BOTTOM OF CHANNEL
- T/C - TOP OF CHANNEL
- A - HEIGHT
- B - WIDTH

VALVE ID:

- AC = AIR CHECK VALVE
- AN = ANGLE VALVE
- AR = AIR RELEASE VALVE
- AV = AIR & VACUUM VALVE
- BA = BALL VALVE
- BFLY = BUTTERFLY VALVE
- BK = BACKPRESSURE VALVE
- BP = BACKFLOW PREVENTER
- CV = CHECK VALVE
- CO = CONE VALVE
- GV = GATE VALVE
- GL = GLOBE VALVE
- KG = KNIFE GATE VALVE
- KN = KNIFE VALVE
- MV = MUD VALVE
- PD = PLUG DRAIN VALVE
- PF = PRESSURE RELIEF
- PG = PRESSURE REGULATOR
- PI = PINCH VALVE
- PV = PLUG VALVE
- PRV = PRESSURE REDUCING VALVE
- PT = PRESSURE TEMPERATURE RELIEF
- RF = RATE-OF-FLOW CONTROLLER
- SV = SOLENOID VALVE
- SU = SURGE VALVE
- TE = TELESCOPING VALVE
- TM = TEMPERATURE CONTROL VALVE


EQUIPMENT ID:

- AC = AIR COMPRESSOR
- AER = AERATOR
- B = BLOWER
- BFP = BELT FILTER PRESS
- CLS = CLASSIFIER
- C = COMMUNITOR
- CMP = COMPACTOR
- CFD = CHEMICAL FEEDER
- CNV = CONVEYOR
- CNT = CENTRIFUGE
- CC = CALIBRATION CYLINDER
- CFD = CHEMICAL FEEDER
- CP = CONTROL PANEL
- CR = CRANE
- D = DECANTER
- DR = DRIVE
- DFL = DISC FILTER
- F = FAN
- FL = FILTER
- FM = FLOW METER
- GBT = GRAVITY BELT THICKENER
- GR = GRINDER
- GEN = GENERATOR
- HB = HOSE BIB
- M = MOTOR
- MX = MIXER
- P = PUMP
- PS = PUMP STATION
- SMP = SAMPLER
- SCR = SCREEN


OTHER:

- ADDL = ADDITIONAL
- AGG = AGGREGATE
- ALUM. = ALUMINUM
- BTWN = BETWEEN
- CL = C/WINTERLINE
- CLR = CLEAR
- CONC = CONCRETE
- CONT = CONTINUOUS
- DWL = DOWEL(S)
- EF = EACH FACE
- EL = ELEVATION
- EMBED = EMBEDMENT
- EW = EACH WAY
- EX = EXISTING
- FF = FINISH FLOOR
- FND = FOUNDATION
- HORIZ = HORIZONTAL
- HP = HIGH POINT
- LP = LOW POINT
- MAX = MAXIMUM
- MFR = MANUFACTURER
- MIN = MINIMUM
- REF = REFERENCE
- REINF = REINFORCING
- STRC = STRUCTURE
- T/ = TOP OF
- TYP = TYPICAL
- UNO = UNLESS NOTED OTHERWISE
- VERT = VERTICAL

PLAN VIEW SECTION CUT CONVENTIONS:



SECTION LABEL




CODED NOTES:



PLAN REVISIONS:




REFERENCE DIMENSION:




REFERENCE DIMENSIONS ARE GIVEN AS INFORMATION OF EXPECTED DESIGN. THEY ARE CALCULATED DIMENSIONS THAT MAY VARY AND ARE INTENDED TO BE FIELD VERIFIED.


MISC PIPE SYMBOLOGY



VALVE SYMBOLS




WALL CASTINGS



NOTE:

WALL CASTINGS REQUIRING BELL ENDS IN LIEU OF MJ SHALL BE NOTED AS "B". ALL FLANGED (F) AND MECHANICAL JOINT (MJ) FLUSH WITH WALL (SEE DRAWINGS) ARE TO BE DRILLED AND TAPPED FOR STUDS.

Sheet List Table		
Sheet Number	Sheet Title	Drawing Name
GENERAL		
1	COVER SHEET	G-01
2	LEGENDS AND ABBREVIATIONS	G-02
CHLORINE FEED BUILDING: CIVIL		
3	SITE PLAN	C-01
CHLORINE FEED BUILDING: STRUCTURAL		
4	FOUNDATION PLAN	S-01
5	ROOF PLAN	S-02
CHLORINE FEED BUILDING: ARCHITECTURAL		
6	FLOOR PLAN	A-01
7	ELEVATIONS	A-02
8	SECTIONS, DETAILS, AND SCHEDULES	A-03
9	WALL SECTIONS	A-04
CHLORINE FEED BUILDING: MECHANICAL		
10	MECHANICAL PLANS AND SCHEDULES	M-01
STANDARD DETAILS: STRUCTURAL		
11	GENERAL NOTES	SD-01
12	GENERAL NOTES	SD-02
13	GENERAL NOTES	SD-03
14	SECTIONS AND TYPICAL DETAILS	SD-04
15	SECTIONS AND TYPICAL DETAILS	SD-05
16	SECTIONS AND TYPICAL DETAILS	SD-06
17	SECTIONS AND TYPICAL DETAILS	SD-07




DATE	REVISION	NO	AS SHOWN	DATE:	DESIGNED BY:	DRAWN BY:	CHECKED BY:
				10/30/2024	VMP	VMP	ADT

THE CITY OF PAINESVILLE
 WATER TREATMENT PLANT
 CHLORINE BUILDING
 LAKE COUNTY
 MENTOR, OHIO
GENERAL
 LEGENDS AND ABBREVIATIONS

PROJECT NO:	
232515	
DRAWING NAME	
G-02	
SHEET	OF
2	17



NOTES:
1. REFER TO ARCHITECTURAL PLANS FOR BUILDING LOCATION.



T consultants
engineers • architects • planners
a verdantas company


NO	REVISION	DATE

SCALE: AS SHOWN	DESIGNED BY: AGD	CHECKED BY: ADT
DATE: 10/30/2024	DRAWN BY: AGD	

THE CITY OF PAINESVILLE
WATER TREATMENT PLANT
CHLORINE BUILDING
LAKE COUNTY MENTOR, OHIO

GENERAL
SITE PLAN


PROJECT NO:	232515
DRAWING NAME	C-01
SHEET	OF
3	17



- PRECAST ROOF PLAN NOTES:**
- SEE SHEETS S0.01, S0.02, AND S0.03 FOR GENERAL STRUCTURAL NOTES.
 - ROOF CONSTRUCTION** - 8" HOLLOW CORE PLANK. SEE HOLLOW CORE PLANK SCHEDULE ON THIS SHEET FOR LIVE AND DEAD LOADS.
 - COORDINATE LOCATION AND SIZE OF ALL ROOF PENETRATIONS AND OPENINGS WITH ARCHITECTURAL, MECHANICAL, ELECTRICAL AND PLUMBING DRAWINGS.
 - L-X INDICATES MISC. ANGLE LINTEL, SEE GENERAL NOTES FOR SIZES BASED ON OPENING SIZE.
 - MPX.X INDICATES MASONRY PIER, SEE DETAILS ON S1.01.
 - SEE ARCHITECTURAL AND MECHANICAL DRAWINGS FOR ROOF TOP EQUIPMENT WEIGHTS AND LOCATIONS NOT INDICATED.
 - SEE ARCHITECTURAL DRAWINGS FOR ALL MEASUREMENTS NOT SHOWN. ALL DIMENSIONS SHALL CONFORM TO THE ARCHITECTURAL DRAWINGS.
 - THE CONTRACTOR SHALL BE RESPONSIBLE FOR FIELD VERIFYING THE EXISTING CONDITIONS AND FOR THE PROPER FIT AND CLEARANCE IN THE FIELD OF ANY MATERIAL THAT IS FABRICATED FROM THESE DRAWINGS. IF THE CONTRACTOR DISCOVERS ANY EXISTING CONDITIONS THAT ARE NOT AS REPRESENTED ON THESE DRAWINGS, THE EOR SHALL BE CONTACTED IMMEDIATELY TO EVALUATE THE STRUCTURAL SIGNIFICANCE OF THE DEVIATION.
 - CONCRETE MASONRY WALLS SHALL BE 8" WIDE AND REINFORCED VERTICALLY WITH (1) #5 BAR AT 32" ON CENTER, SEE GENERAL NOTES FOR MORE INFORMATION. CONCRETE MASONRY WALLS SHALL BE CENTERED ON FOOTING UNLESS NOTED OTHERWISE.

- ROOF FRAMING PLAN CODED NOTES:**
- EXISTING STEEL COLUMN TO REMAIN.

PRECAST PLANK LOADS				
PLANK	DEAD LD	2" TOPPING	TOT D. LD	LIVE LD
8" PLANK	56 PSF	N.A.	56 PSF	SEE DESIGN LOADS IN GENERAL NOTES






NO	REVISION	DATE

SCALE: AS SHOWN
 DATE: 10/30/2024
 DESIGNED BY: BF
 DRAWN BY: BW
 CHECKED BY: BF

THE CITY OF PAINESVILLE
 WATER TREATMENT PLANT
 CHLORINE BUILDING
 MENTOR, OHIO
 LAKE COUNTY
 CHLORINE FEED BUILDING
 ROOF PLAN

PROJECT NO:	232515
DRAWING NAME	S-02
SHEET	5
OF	17



CHLORINE FEED BUILDING

CODE DATA:
GOVERNING CODES:
2024 OHIO BUILDING CODE (2021 IBC W/ STATE AMENDMENTS)
2024 OHIO PLUMBING CODE (2021 IPC W/ STATE AMENDMENTS)
2024 OHIO MECHANICAL CODE (2021 IMC W/ STATE AMENDMENTS)
2017 OHIO FIRE CODE (2015 IFC W/ STATE AMENDMENTS)
2017 OHIO ENERGY CODE (2012 IECC W/ STATE AMENDMENTS)

PROJECT DATA:
OCCUPANCY GROUP: H-3
CONSTRUCTION TYPE: IIB, UNPROTECTED, SPRINKLED
ALLOWABLE HEIGHT: 55'-0"
ACTUAL HEIGHT: 13'-6"
ALLOWABLE NUMBER OF STORIES: 2
ACTUAL NUMBER OF STORIES: 1
ALLOWABLE AREA: 15,500 S.F.
ACTUAL AREA: 649 S.F.
3 HOUR FIRE BARRIER
BRICK: MIN 5.5" (TABLE 721.1(2))
CMU: MIN 5.3" (TABLE 721.1(2))




THIS BUILDING IS NOT REGULARLY OCCUPIED. SYSTEMS ARE PROVIDED FOR REMOTE MONITORING. ANY TEMPORARY OCCUPANCY WILL BE LIMITED TO MAINTENANCE OF EQUIPMENT AND PERIODIC TESTING ONLY.

DEMOLITION NOTES:

1. REMOVE EXISTING ASPHALT AS SHOWN ON PLAN
2. EXISTING LOADING DOCK STAIRS TO BE REMOVED
3. EXISTING 3" EMBEDDED RAIL SYSTEM TO BE REMOVED
4. EXISTING RACK STORAGE TO BE REMOVED
5. EXISTING MANHOLES TO REMAIN
6. EXISTING STEEL COLUMNS TO REMAIN

CODED NOTES:

- 1 WATER HEATER TANK - NOT INCLUDED IN CONTRACT
- 2 EMERGENCY EYE WASH STATION - NOT INCLUDED IN CONTRACT
- 3 DAY TANK WITH SCALE - NOT INCLUDED IN CONTRACT
- 4 EXHAUST FAN - FUTURE PHASE
- 5 TRANSFER PUMPS - NOT INCLUDED IN CONTRACT
- 6 DUPLEX PERISTALTIC PUMP SKID - NOT INCLUDED IN CONTRACT
- 7 CHEMICAL CONTAINMENT PALLET - NOT INCLUDED IN CONTRACT




NO	REVISION	DATE


SCALE: AS SHOWN	DATE: 10/30/2024	DESIGNED BY: ADT	DRAWN BY: VMP	CHECKED BY: ADT
-----------------	------------------	------------------	---------------	-----------------

THE CITY OF PAINESVILLE
WATER TREATMENT PLANT
CHLORINE FEED BUILDING
MENTOR, OHIO
LAKE COUNTY
CHLORINE FEED BUILDING
FLOOR PLAN


PROJECT NO:	232515
DRAWING NAME	A-01
SHEET	OF
6	17




T consultants
 engineers • architects • planners
 a verdantas company




WEST ELEVATION
 SCALE: 1/4" = 1'-0"




EAST ELEVATION
 SCALE: 1/4" = 1'-0"



NORTH ELEVATION
 SCALE: 1/4" = 1'-0"



SOUTH ELEVATION
 SCALE: 1/4" = 1'-0"



WEST ELEVATION
 SCALE: 1/8" = 1'-0"

NO	DATE	REVISION

SCALE: AS SHOWN	DATE: 10/30/2024	DESIGNED BY: ADT	DRAWN BY: VMP	CHECKED BY: ADT
-----------------	------------------	------------------	---------------	-----------------

THE CITY OF PAINESVILLE
 WATER TREATMENT PLANT
 CHLORINE BUILDING
 MENTOR, OHIO
 LAKE COUNTY
 CHLORINE FEED BUILDING
 ELEVATIONS

PROJECT NO:	232515
DRAWING NAME	A-02
SHEET	7
OF	17

HVAC EQUIPMENT SCHEDULE					
SYMBOL	QUANT.	AREA SERVED	DESCRIPTION	ACCESSORIES	ELECTRICAL REQUIREMENTS
MAU-1	1	CHEMICAL FEED BUILDING	GREENHECK #DGX-P116-H12-D1-3 MAKEUP AIR UNIT OUTDOOR, HORIZONTAL CONFIG., DIRECT-FIRED HEAT, NATURAL GAS, PACKAGED DX INTEGRAL COOLING, R-454B REFRIGERANT, RIGHT HAND ACCESS AND CONNECTIONS, TOP DISCHARGE, DIRECT-DRIVE, MIXED FLOW FAN WITH VARIABLE FREQUENCY DRIVE(VFD), SECTIONS: INTAKE LOUVERS, FILTERS, GAS BURNER, DX COOLING, FAN. APPROX. DIMENSIONS: 159"L x 33"W x 39"H, APPROX. WEIGHT: 1,500#±. 800 CFM @ 0.50" E.S.P., 1.18" TOTAL S.P., 1,140 RPM, 0.28 BHP, 1/2 HP MOTOR, HEAT: 90 MBH INPUT, 83 MBH OUTPUT, 95°F ΔT AT 92% EFF., 7" BURNER OPERATING PRESSURE, 30:1 TURNDOWN RATIO. COOLING: 41 MBH TC, 22 MBH SC, 89.4/76.3 EAT, 61.9/61.8 LAT, 15.5 EER. FAN: 57 Lwa, 46 dBA, 3.5 SONES.	SEE SPEC. #237423 FOR ADDITIONAL INFO. DOUBLE WALL CONSTRUCTION (1" INSULATION) FAN AND HEAT SECTIONS HINGED ACCESS DOORS MOTORIZED OUTLET DAMPER, WITH END SWITCH PERMATECTOR COATING: ENTIRE UNIT AND ALL ACCESSORIES LOUVERED INLET HOOD WITH ALUMINUM MESH V-BANK FILTER SECTION WITH: 2" THICK, PLEATED, MERV-13 DISP. FILTERS CUSTOM REMOTE CONTROL PANEL, NEMA 4X DISCHARGE AIR TEMPERATURE CONTROLS, WITH ROOM OVERRIDE THERMOSTAT FREEZE PROTECTION HEATING INLET AIR SENSOR COOLING INLET AIR SENSOR DIRTY FILTER SENSOR/SWITCH EXHAUST FAN STARTER: 208V/1, 1/4 HP (EF-1) AUXILIARY CONTACTS: SUPPLY FAN STATUS, EXHAUST FAN INTERLOCK, EMERGENCY STOP. FM COMPLIANT GAS TRAIN, WITH HIGH/LOW GAS PRESSURE SWITCHES FLAME FAILURE ALARM LIGHT TEFC MOTOR, PREMIUM EFFICIENCY 12" ROOF CURB EMERGENCY STOP - SEE NOTE 2.	208/3/60 21.4 MCA 30A MOCP
EF-1 (N.I.C.)					

NOTES:


- CHARACTERISTICS (RPM, HP, IMPELLERØ, PRESSURE DROP) SHALL NOT VARY BY MORE THAN 10% OF SPEC'D UNITS. SOUND VALUES SHALL NOT EXCEED THE VALUES INDICATED.
- CONTRACTOR TO PROVIDE A MANUAL EMERGENCY SHUTOFF TO DE-ENERGIZE MAU-1 AND EF-1 EXHAUST FAN. EMERGENCY SHUTOFF TO BE MODEL #HVAC-120 AS MANUFACTURED BY PILLA ELECTRICAL PRODUCTS, INC., OR EQUAL. SHUTOFF TO BE 120-VOLT, RED PUSH BUTTON TYPE, PULL RESET, METALLIC NEMA 4, 4X, 12 ENCLOSURE, WITH LABEL TO READ: "VENTILATION SYSTEM EMERGENCY SHUTOFF". PROVIDE WITH #PILCLHCOV1 CLEAR HINGED COVER.

SEQUENCE OF OPERATION

- MAU-1 MAKEUP AIR UNIT:**
VENTILATION SHALL BE CONTINUOUS, 24 HOURS/DAY, 365 DAYS/YEAR.
MAU-1 SHALL BE A HEATING AND COOLING UNIT.
MAU-1 SHALL BE INTERLOCKED, CONTINGENT UPON THE OPERATION OF EF-1 EXHAUST FAN.
VENTILATION SYSTEM PROVIDES ~ 7.3 AIR CHANGES PER HOUR, AND 1.4 CFM/SF (MINIMUM OF 1.0 CFM/SF REQUIRED BY THE OHIO MECHANICAL CODE).
MAU-1 SHALL BE PROVIDED WITH A REMOTE CONTROL PANEL.
FAN SHALL BE SET TO RUN CONTINUOUSLY.
CONTROL MODES SHALL INCLUDE A HEAT-COOL-AUTO SWITCH. TEMPERATURE CONTROL SHALL BE DISCHARGE AIR WITH A ROOM OVERRIDE THERMOSTAT. IN THE HEAT POSITION, THE UNIT SHALL BE HEATING ONLY. IN THE COOL POSITION, THE UNIT SHALL BE COOLING ONLY. IN THE AUTO POSITION, THE UNIT CAN FUNCTION IN HEATING OR COOLING MODES.
SPACE TEMPERATURE SETTINGS TO BE ~65°F HEATING AND ~75°F COOLING, BOTH ADJUSTABLE.


SYSTEM SHALL INCLUDE AN EMERGENCY STOP BUTTON (SEE PLANS FOR LOCATION) TO SHUT DOWN MAU-1 AND EF-1, PER THE OHIO MECHANICAL CODE FOR HAZARDOUS MATERIAL STORAGE.

SEE ELECTRICAL DRAWINGS FOR INTERLOCK WIRING, MONITORING, AND ALARM PROVISIONS. AN ALARM SIGNAL SHALL BE INITIATED SHOULD MAU-1 OR EF-1 NOT BE OPERATING (CURRENT SENSING RELAY, ETC).
- EF-1 EXHAUST FAN:**
VENTILATION SHALL BE CONTINUOUS, 24 HOURS/DAY, 365 DAYS/YEAR.
MAU-1 MAKEUP AIR UNIT SHALL BE INTERLOCKED WITH EF-1, AS DESCRIBED ABOVE.



CODED NOTES:

- MAKEUP AIR UNIT TO BE MOUNTED ON 12"H ROOF CURB, ON CONCRETE LOADING DOCK LEVEL.



consultants
engineers • architects • planners
a verdantas company

NO	DATE	REVISION
AS SHOWN	10/30/2024	
DESIGNED BY:	JRM	
DRAWN BY:	JRM	
CHECKED BY:	JRM	

THE CITY OF PAINESVILLE
WATER TREATMENT PLANT
CHLORINE BUILDING
LAKE COUNTY
MENTOR, OHIO
MECHANICAL
MECHANICAL PLANS AND SCHEDULES

PROJECT NO:	232515
DRAWING NAME	M-01
SHEET	10
OF	17

GOVERNING CODES AND STANDARDS:

Table listing governing codes and standards including OBC, IBC, ASCE 7, ACI 318, PCI, ACI 301, ACI 305R, ACI 306R, ACI SP-66, ACI 350.1, ACI 530, ACI 530.1, and ADM1.

DESIGN LOADS:

Table of design loads including live loads (uniform and concentrated), snow loads, wind loads, and frost depth.

FOUNDATIONS:

- 1. FOUNDATION DESIGN IS BASED ON RECOMMENDATIONS IN THE GEOTECHNICAL REPORT NO. 232515. PREPARED BY CT CONSULTANTS, DATED SEPTEMBER 26, 2024. CONTRACTOR SHALL REVIEW GEOTECHNICAL REPORT PRIOR TO CONSTRUCTION.
2. FOUNDATIONS ARE DESIGNED TO BE SUPPORTED ON HELICAL PILES (DELEGATED DESIGN). SEE GEOTECHNICAL REPORT FOR SOIL PROFILE, PROPERTIES AND DESIGN PARAMETERS.
...
13. DO NOT PLACE FILL OR CONCRETE ON FROZEN GROUND.

CAST-IN-PLACE CONCRETE AND REINFORCEMENT:

- 1. ALL CONCRETE WORK SHALL BE IN ACCORDANCE WITH ACI 318.
2. CONCRETE SHALL HAVE THE FOLLOWING 28-DAY COMPRESSIVE STRENGTHS:
...
7. CONTRACTOR SHALL KEEP A COPY OF "FIELD REFERENCE MANUAL: STANDARD SPECIFICATIONS FOR STRUCTURAL CONCRETE ACI 301 WITH SELECTED ACI REFERENCES", (ACI PUBLICATION SP-15) AT THE PROJECT FIELD OFFICE.
8. ALL REINFORCING DETAILS SHALL CONFORM TO THE ACI DETAILING MANUAL, SP-66, UNLESS DETAILED OTHERWISE ON THE STRUCTURAL DRAWINGS.

- 9. SUBMIT FOR APPROVAL CONCRETE MIX DESIGN AND CERTIFICATION OF CONCRETE MATERIALS CONFORMING TO THE FOLLOWING EXPOSURE CATEGORIES:

Table showing concrete mix design categories: Footings, Interior Slab-on-Grade, Piers, Walls, Exterior Slabs, with sub-categories for Freeze and Thawing, Sulfate, and Corrosion Protection.

- 10. THE CONTRACTOR SHALL EMPLOY A TESTING LABORATORY APPROVED BY THE ENGINEER/ARCHITECT TO PERFORM THE TESTING SPECIFIED PER PARAGRAPH 1.6.4 OF ACI 301. THE TESTING LABORATORY SHALL MEET THE REQUIREMENTS OF ASTM E329. TESTING SHALL BE MADE BY AN ACI CONCRETE FIELD-TESTING TECHNICIAN GRADE 1 OR APPROVED EQUIVALENT. A TECHNICIAN GRADE 1 SHALL BE PRESENT DURING ALL CONCRETE PLACEMENT.

- 11. SUBMIT SHOP DRAWINGS FOR REVIEW. THESE DRAWINGS SHALL SHOW ALL CONCRETE MEMBER DIMENSIONS AND DOWELS FOR MASONRY WALLS.
12. PROVIDE DOWELS FROM FOUNDATIONS TO MATCH PIER AND WALL VERTICAL REINFORCING. WHERE SHOWN, PROVIDE DOWELS OUT OF WALLS TO MATCH SLAB REINFORCING.
...
23. PITCH CONCRETE SLABS TO FLOOR DRAINS SHOWN ON MECHANICAL OR ARCHITECTURAL DRAWINGS.
24. CONCRETE PROTECTION (CLEAR COVER) FOR REINFORCEMENT BARS SHALL BE AS FOLLOWS UNLESS NOTED OTHERWISE:

PRECAST CONCRETE:

- 1. ALL PRECAST MEMBERS SHALL BE DESIGNED AND FABRICATED IN ACCORDANCE WITH ACI 318, "BUILDING CODE REQUIREMENTS FOR STRUCTURAL CONCRETE"; ACI 301, "SPECIFICATIONS FOR STRUCTURAL CONCRETE"; PCI 116-13, "MANUAL FOR QUALITY CONTROL FOR PLANTS AND PRODUCTION OF PRECAST PRESTRESSED PRODUCTS"; AND PCI 135-00, "TOLERANCE MANUAL FOR PRECAST AND PRESTRESSED CONCRETE CONSTRUCTION"; AND "THE PCI DESIGN HANDBOOK."
2. THE MANUFACTURER OF THE PRECAST CONCRETE MEMBERS SHALL BE CERTIFIED BY THE "PRECAST CONCRETE INSTITUTE"(PCI) BY THE BID DATE. THE CERTIFICATION GROUP SHALL BE GROUP "C" FOR STRUCTURAL MEMBERS.
...
11. ALL PRECAST MEMBERS TO RECEIVE TOPPING SHALL HAVE AN INTENTIONALLY ROUGHENED SURFACE WITH A MINIMUM AMPLITUDE OF 1/4 INCH.

- 12. ELASTOMERIC MATERIALS OF A STRUCTURAL (NON-COMMERCIAL) GRADE CONFORMING TO THE REQUIREMENTS OF SECTION 18, DIVISION 2, OF THE AASHTO STANDARD SPECIFICATIONS FOR HIGHWAY BRIDGES 17TH EDITION HAVING A MINIMUM DURROMETER HARDNESS OF 70 SHOULD BE USED UNDER BEARING SURFACES OF PRECAST FLOOR AND ROOF PLANKS. ALL MATERIAL SHALL BE NEW WITH NO RECLAIMED MATERIAL INCORPORATED IN THE FINISHED BEARING PAD.

- 13. PRECAST INSTALLER SHALL SET UNITS LEVEL AND SQUARE, KEEPING UNITS TIGHT AND IN PROPER ALIGNMENT WITH SUPPORTS. MAXIMUM DIFFERENTIAL CAMBER BETWEEN ADJACENT ELEMENTS SHALL NOT EXCEED 1/4" PER 10'-0" OF LENGTH BUT NOT GREATER THAN 3/4". CONTRACTOR SHALL TAKE ALL MEASURES NECESSARY TO CONFORM TO THESE TOLERANCES INCLUDING, BUT NOT LIMITED TO THE ADJUSTMENT OF BEARING HEIGHTS.

- 14. PRECAST CONCRETE SLABS AND TEES SHALL HAVE A MINIMUM BEARING SURFACE OF 3" ON ALL SUPPORTING ELEMENTS, UNLESS NOTED OTHERWISE.

- 15. PRECAST INSTALLER SHALL WELD MEMBERS TO SUPPORTS, AS SHOWN ON THE DRAWINGS. ALL WELDS SHALL BE PERFORMED IN ACCORDANCE WITH AWS D1.1.

- 16. PRECAST MANUFACTURER SHALL PROVIDE STANDARD SHEAR CONNECTORS IN THE FLANGES OF PRECAST TEES AS SHOWN ON DETAILS. FIELD WELD AS INDICATED IN ACCORDANCE WITH AWS D1.1 SECTION 7.

- 17. REINFORCING STEEL THAT MAY BE SHOWN IN DETAILS IS FOR IN-PLACE CONDITION. ALL INSERTS, BRACES, STRONGBACKS AND OTHER REQUIRED ACCESSORIES SHALL BE FURNISHED AND INSTALLED BY THE CONTRACTOR, AND SHALL BE LOCATED IN ACCORDANCE WITH THE RECOMMENDATIONS OF RICHMOND BULLETIN NO. 8, "PRODUCTS FOR PRECAST/PRESTRESSED CONCRETE CONSTRUCTION." THE CONTRACTOR IS ALSO RESPONSIBLE FOR PROVIDING SPECIAL REINFORCING ELEMENTS THAT MAY BE REQUIRED TO PREVENT FLEXURAL CRACKS FROM OCCURRING IN THE PANELS DURING LIFTING AND HANDLING OPERATIONS.

- 18. THE CONTRACTOR SHALL GROUT PRECAST MEMBERS AS OUTLINED BELOW:
a. BETWEEN SLAB EDGES: FILL GROUT KEYS FULL AND STRIKE OFF FLUSH WITH TOP SURFACE. REMOVE ANY GROUT WHICH SEEPS THROUGH TO UNDERSIDE OF UNITS BEFORE IT HARDENS. CLEAN EXCESS FROM FACES AND FLOORS BELOW.
b. AT SLAB ENDS: WHERE END GROUTING IS SHOWN ON THE DRAWINGS, PROVIDE SUITABLE END CAP OR DAM IN VOIDS.

- 19. PRECAST MANUFACTURER/DESIGNER AND CONTRACTOR SHALL COORDINATE WITH OTHER TRADES IN PERMITTING THE INSERTION OF ANCHORS, HANGERS, ELECTRICAL OUTLETS, ETC.

- 20. PRECAST MANUFACTURER AND GENERAL TRADES CONTRACTOR SHALL COORDINATE SIZE AND LOCATION OF ALL HOLES AND OPENINGS REQUIRED THROUGH THE HOLLOW CORE SLABS WITH THE TRADES REQUIRING THE OPENINGS.

- 21. NOT ALL HOLES AND OPENINGS ARE SHOWN ON THE STRUCTURAL DRAWINGS. THOSE WHICH ARE SHOWN SHALL BE CAST-IN OR CUT-IN BY THE MANUFACTURER. ALL OPENINGS LARGER THAN ONE SLAB WIDTH ARE TO BE FRAMED WITH CONCRETE OR STRUCTURAL STEEL HEADERS, DESIGNED AND PROVIDED BY THE MANUFACTURER. ADJACENT UNITS SHALL BE DESIGNED TO SUPPORT THE ADDITIONAL LOAD.

- 22. OPENINGS NOT SHOWN ON THE STRUCTURAL DRAWINGS SHALL BE FIELD CUT BY THE GENERAL TRADES CONTRACTOR AT THE EXPENSE OF THE TRADE REQUIRING THE OPENING. THE MANUFACTURER, HOWEVER, IS RESPONSIBLE FOR DESIGNING THE AFFECTED HOLLOW CORE PLANKS TO ACCOMMODATE THESE OPENINGS BY PROVIDING NECESSARY ADDITIONAL REINFORCING IN UNIT WITH OPENING AND IN ADJACENT UNITS. FIELD CUT HOLES MAY BE DRILLED OR CUT AND TRIMMED WITH A CHISEL. CUT OUTLINE OF HOLE THROUGH LOWER PORTION OF SLAB FROM UNDERSIDE, AFTER WHICH THE TOPSIDE MAY BE REMOVED FROM ABOVE. DO NOT CUT PRESTRESSING STRANDS WITHOUT APPROVAL OF THE MANUFACTURER AND THE ARCHITECT.

- 23. ALL PRECAST FLOOR MEMBERS SHALL BE DESIGNED FOR A FIRE RATING OF 2 HOURS, UNLESS NOTED OTHERWISE ON THE ARCHITECTURAL DRAWINGS. THE SPECIFIED UNIFORM SLAB THICKNESS DURING CONCRETE PLACEMENT SHALL BE MAINTAINED IN ORDER TO ACHIEVE THIS FIRE RATING.

CONCRETE MASONRY:

- 1. MASONRY IS SUPPORTED IN THE COMPLETED CONSTRUCTION. THE CONTRACTOR IS SOLELY RESPONSIBLE FOR SUPPORTING THE MASONRY DURING CONSTRUCTION IN CONFORMANCE WITH LOCAL, STATE AND NATIONAL LAWS AND AS REQUIRED.
2. MASONRY CONSTRUCTION AND MATERIAL SHALL CONFORM TO ALL REQUIREMENTS OF "SPECIFICATIONS FOR MASONRY STRUCTURES" (ACI 530.1/ASCE 6) EXCEPT AS MODIFIED IN THE SPECIFICATIONS AND BELOW. A COPY OF ACI 530.1/ASCE 6 SHALL BE ON THE JOB SITE AT ALL TIMES THAT MASONRY WORK IS BEING PERFORMED.
3. SUBMIT FOR REVIEW, PRIOR TO CONSTRUCTION, SHOP DRAWINGS SHOWING A PLAN AND ELEVATION VIEW OF ALL CMU WALL, AND A PLAN THAT SHOWS ALL DOWELS REQUIRED FOR VERTICAL CMU REINFORCING THAT EXTEND OUT OF CONCRETE. SHOW WALL THICKNESS, AND DIMENSION WALL LENGTH AND LOCATION. SHOWING TOP ELEVATIONS OF WALLS, BOND BEAMS AND GROUT POURS, SHOW LOCATION OF CONTROL JOINT LOCATIONS, SOLID UNITS, CELLS TO BE GROUT FILLED, OPENING, LINTEL, JOINT REINFORCEMENT, REINFORCING BAR AND EMBEDMENT.
4. SUBMIT FOR REVIEW, PRIOR TO CONSTRUCTION, DOCUMENTATION FOR THE BLOCK, MORTAR, GROUT, ADMIXTURES, REINFORCING, BAR POSITIONER AND OTHER ACCESSORIES PROPOSED FOR USE. SUBMIT A WRITTEN DESCRIPTION OF THE METHOD OF REINFORCEMENT AND GROUT, AND OF GROUT CONSOLIDATION.

- 5. CONCRETE MASONRY UNITS SHALL CONFORM TO ASTM C90, NORMAL WEIGHT.
6. CONCRETE MASONRY UNITS WHICH CONTAIN VERTICAL REINFORCEMENT SHALL BE TWO CORE UNITS AND WITH CORES AND WEBS VERTICALLY ALIGNED.
7. MORTAR FOR CONCRETE MASONRY UNITS SHALL BE NON-AIR ENTRAINED PORTLAND CEMENT-LIME CONFORMING TO ASTM C270, TYPE S. CEMENT IN MORTAR SHALL BE LOW-ALKALI AND NON-STAINING. TYPE N MORTAR AND MASONRY CEMENT SHALL NOT BE USED FOR CMU CONSTRUCTION.
8. ADMIXTURES SHALL NOT BE USED IN THE MORTAR OR GROUT. ANTI-FREEZE AND CALCIUM CHLORIDE SHALL NOT BE USED.
9. MINIMUM NET AREA COMPRESSIVE STRENGTH OF CONCRETE MASONRY UNITS SHALL BE:
NET AREA COMPRESSIVE STRENGTH OF ASTM C90 CMU, f_{cmu} = 2,000 PSI
NET AREA COMPRESSIVE STRENGTH OF CONCRETE MASONRY, f_m = 2,000 PSI

- 10. COARSE GROUT SHALL CONFORM TO ASTM C476 WITH A MAXIMUM AGGREGATE SIZE OF 3/8" AND A MINIMUM COMPRESSIVE STRENGTH OF 2,000 PSI.
11. ALL LOAD BEARING CONCRETE BLOCK WALLS SHALL BE REINFORCED VERTICALLY AS SHOWN ON PLAN, UNLESS NOTED OTHERWISE.
12. PROVIDE (1) #5 VERTICAL BAR IN FIRST CORE AT EACH CORNER, END OF WALL, AND ADJACENT TO OPENINGS AND CONTROL JOINTS.

- 13. VERTICAL REINFORCEMENT SHALL EXTEND THROUGH BOND BEAMS AND TO WITHIN 2 INCHES OF THE TOP OF WALLS.
14. REINFORCING STEEL SPLICES SHALL BE LAPPED A MINIMUM OF 48 BAR DIAMETERS BUT NO LESS THAN 12 INCHES, UNLESS NOTED OTHERWISE.
15. ANCHORAGE OF REINFORCING STEEL INTO CONCRETE SHALL BE 36 BAR DIAMETERS BUT NO LESS THAN 12 INCHES, UNLESS NOTED OTHERWISE.

- 16. HORIZONTAL JOINT REINFORCING SHALL BE, UNLESS SHOWN OTHERWISE, STANDARD 9 GAGE, LADDER TYPE CONFORMING TO ASTM A951, SPACED VERTICALLY AT 8 INCH ON CENTERS ABOVE AND BELOW OPENINGS FOR THREE CONSECUTIVE COURSES AND AT 16 INCHES ON CENTERS ELSEWHERE. EXTEND REINFORCEMENT 2 FEET BEYOND EACH SIDE OF OPENINGS BUT DO NOT EXTEND THROUGH CONTROL JOINTS. PROVIDE FACTORY FABRICATED "T" AND "L" SHAPED PIECES AT INTERSECTIONS AND CORNERS.
17. JOINT REINFORCEMENT SHALL BE SPLICED BY LAPPING THE LONGITUDINAL WIRES AT LEAST 12 INCHES; THE CROSS-WIRES WITHIN THE LAP SHALL BE REMOVED SO THAT THE LONGITUDINAL WIRES ARE SIDE BY SIDE. ALTERNATELY WHERE JOINT REINFORCING IS NOT REQUIRED IN BETWEEN EACH COURSE, SPLICES MAY BE MADE BY BUTTING THE ADJACENT SECTIONS OF JOINT REINFORCING AND CENTERING A 48 INCH LENGTH OF JOINT REINFORCING IN THE BED JOINT IMMEDIATELY ABOVE OR BELOW THE BUTT JOINT. SPLICE WITH "T" AND "L" SHAPED PIECES AT INTERSECTIONS AND CORNERS.

- 18. LINTELS SHALL BE PROVIDED OVER ALL OPENINGS AND OVER RECESSES WIDER THAN 12 INCHES IN ACCORDANCE WITH THE ACCOMPANYING LINTEL SCHEDULE, UNLESS NOTED OTHERWISE ON DRAWINGS.

- 19. FOR LINTELS ENDING AT A CONTROL JOINT, PROVIDE 15 POUND FELT BOND BREAKER UNDER LINTEL BEARING AND A HORIZONTAL DUMMY CONTROL JOINT ON EXPOSED FACES. NO MORTAR OR GROUT SHALL BE IN THE HEAD JOINT OF DUMMY CONTROL JOINTS OPPOSITE THE BLOCK SHELL. PROVIDE A POSITIVE MEANS OF PREVENTING GROUT FROM ENTERING DUMMY JOINT OPPOSITE THE BLOCK SHELL. DUMMY JOINT SHALL BE CAULKED AND MATCH COLOR OF MORTAR.

- 20. BOND BEAMS SHALL BE PROVIDED IN EACH WALL AT EACH FLOOR LEVEL, ROOF LEVEL, AND AT TOP OF WALL. FILL BOND BEAMS WITH GROUT. REINFORCE BOND BEAMS WITH (2) #5 UNLESS NOTED OTHERWISE. PROVIDE CORNER BARS WITH 2'-0" LEGS AND BAR SUPPORTS TO OBTAIN THE REQUIRED CLEARANCE.

- 21. BOND BEAMS AT THE TOP OF SLOPED WALLS SHALL FOLLOW THE SLOPE OF THE WALL. CUT OUT WEB OF BLOCKS SO THAT THE REINFORCING BARS ARE 4 INCHES CLEAR OF THE TOP OF THE WALL. A MINIMUM OF 8 INCHES VERTICALLY SHALL BE GROUT FILLED. (SEE TYPICAL SLOPED BOND BEAM DETAIL).

- 22. BOND BEAM REINFORCEMENT AND GROUT AT WALL CONTROL JOINTS SHALL BE CONTINUOUS. PROVIDE A DUMMY CONTROL JOINT IN BOTH FACES OF BOND BEAM ALIGNED WITH WALL CONTROL JOINTS. THE BLOCK FACE SHELLS AT DUMMY CONTROL JOINTS SHALL BE FREE OF MORTAR AND GROUT. THE DUMMY CONTROL JOINT IN EXPOSED FACES SHALL HAVE BACKING ROD AND CAULK SEAL AS REQUIRED FOR THE CONTROL JOINT.

- 23. VERTICAL CONTROL JOINTS IN CONCRETE MASONRY WALLS (OTHER THAN BASEMENT WALLS) SHALL BE PROVIDED WHERE SHOWN ON THE PLANS AND AS GIVEN BELOW:
a. AT 25 FEET OR LESS ON CENTERS BUT NOT MORE THAN 1 1/2 TIMES THE WALL HEIGHT
b. AT A DISTANCE NOT OVER ONE-HALF THE ABOVE SPACING FROM BONDED INTERSECTIONS OR CORNERS.
c. AT ONE END OF A LINTEL FOR WALL OPENINGS SIX FEET OR LESS IN WIDTH
d. AT BOTH ENDS OF LINTELS FOR OPENINGS MORE THAN SIX FEET WIDE
e. ALL ABRUPT CHANGES IN WALL HEIGHT.
f. AT ALL CHANGES IN WALL THICKNESS, SUCH AS THOSE AT PIPE AND DUCT CHASES AND THOSE ADJACENT TO COLUMNS OR PILASTERS.
g. ABOVE JOINTS IN FOUNDATIONS AND FLOORS.
h. BELOW JOINTS IN WALLS AND FLOORS THAT BEAR IN THE WALL.
i. WHERE SHOWN IN BRICK OR OTHER VENEER.

- 24. CONTROL JOINTS SHALL NOT OCCUR AT WALL CORNERS, INTERSECTIONS, ENDS, WITHIN 2'-0" OF CONCENTRATED POINTS OF BEARING, OR JAMBS OVER OPENINGS UNLESS SPECIFICALLY SHOWN ON THE STRUCTURAL DRAWINGS.

- 25. ALL MASONRY BELOW GRADE SHALL BE GROUTED SLID.

- 26. ANCHOR MASONRY TO STRUCTURAL MEMBERS WITH ADJUSTABLE TIES SPACED AS INDICATED, BUT NOT MORE THAN 16" OC VERTICALLY AND 24" OC HORIZONTALLY.

- 27. PROVIDE AN EXPANSION JOINT WHERE THE TOP OF BRICK ABUTS CONCRETE OR STEEL AND WHERE THE SIDE OF BRICK ABUTS CONCRETE, CONCRETE BLOCK OR STEEL.

- 28. MECHANICALLY VIBRATE GROUT IN VERTICAL SPACES IMMEDIATELY AFTER POURING AND AGAIN MINUTES LATER.

- 29. PROVIDE CLEANOUTS IF GROUT LIFT EXCEEDS 4'-0" IN BLOCK WALLS. MAXIMUM GROUT LIFT SHALL BE 8'-0".

- 30. SEE VENEER ANCHORAGE NOTES FOR ATTACHMENT OF VENEER TO BLOCK WALLS.

VENEER ANCHORAGE:

- 1. MASONRY VENEER SHALL BE LAID IN RUNNING BOND. (COORDINATE VENEER CONSTRUCTION WITH ARCHITECTURAL DRAWINGS.)
2. A MINIMUM 1-INCH AIR SPACE AND A 4-1/2 INCH MAXIMUM DISTANCE SHALL BE MAINTAINED BETWEEN THE INSIDE FACE OF THE VENEER AND THE WOOD STUD OR WOOD FRAMING, COLD-FORMED METAL FRAMING OR MASONRY BACKUP.
3. VENEER ANCHORS SHALL CONSIST OF AT LEAST A 9-GAGE GALVANIZED WIRE AND HAVE ENDS BENT TO FORM AN EXTENSION FROM THE BEND AT LEAST 2 INCHES LONG.
4. FOR CONCRETE OR CONCRETE MASONRY BACKING:
a. MASONRY VENEER SHALL BE ATTACHED TO CONCRETE OR CONCRETE MASONRY BACKUP UTILIZING WIRE ANCHORS EMBEDDED IN THE MORTAR JOINT.
b. PROVIDE AT LEAST ONE ANCHOR FOR EACH 3.5 SQUARE FEET OF WALL AREA. SPACING OF ANCHORS SHALL NOT EXCEED A MAXIMUM OF 32 INCHES HORIZONTALLY AND 18 INCHES VERTICALLY.

- 5. WIRE ANCHORS SHALL EXTEND INTO THE VENEER A MINIMUM OF 1-1/2 INCHES WITH AT LEAST 5/8-INCH MORTAR COVER TO THE OUTSIDE FACE.

- 6. FOR ADJUSTABLE ANCHORS, THE MAXIMUM CLEARANCE BETWEEN CONNECTING PARTS SHALL BE 1/16-INCH AND SHALL BE DETAILED TO PREVENT DISENGAGEMENT.

- 7. PROVIDE ADDITIONAL ANCHORS AROUND OPENINGS LARGER THAN 16-INCHES IN EITHER DIRECTION. ANCHOR SPACING AROUND PERIMETER OF OPENING SHALL BE 3-FEET MAXIMUM ON CENTER AND WITHIN 12-INCHES OF OPENING.

MISC. STEEL MASONRY LINTELS:

- 1. PROVIDE LINTELS OVER ALL MASONRY OPENINGS AND OVER RECESSES WIDER THAN 12 INCHES IN ACCORDANCE WITH THE ACCOMPANYING LINTEL SCHEDULE, UNLESS NOTED OTHERWISE ON DRAWINGS.
2. WHERE CONTROL JOINTS ARE AT ENDS OF LINTELS, PROVIDE 15 POUND FELT BOND BREAKER UNDER LINTEL BEARING AND DUMMY CONTROL JOINT ON EXPOSED FACES. NO MORTAR OR GROUT SHALL BE IN THE HEAD JOINT OF DUMMY CONTROL JOINTS OPPOSITE THE BLOCK SHELL. PROVIDE A POSITIVE MEANS OF PREVENTING GROUT FROM ENTERING DUMMY JOINT OPPOSITE THE BLOCK SHELL.
3. BELOW EACH BEARING POINT OF LINTEL, GROUT FILL CELLS FOR A MINIMUM OF 16" BEYOND EDGE OF OPENING AND A MINIMUM OF 16" BELOW LINTEL BEARING.
4. THE FABRICATOR SHALL SUPPLY LOOSE LINTEL ANGLES (DEFINED BELOW) OVER ALL MASONRY OPENING AND RECESSES UNLESS NOTED OTHERWISE. PROVIDE ONE ANGLE FOR EACH 4-INCHES OF WALL THICKNESS. FOR 10-INCH CMU PROVIDE THREE SIMILAR ANGLES BUT WITH 3-INCH HORIZONTAL LEGS.

Table with columns: MASONRY OPENING, STEEL ANGLE SIZE, BEARING END. Rows show dimensions like 4'-0" OR LESS, 4'-1" TO 6'-0", etc.

- 5. PLACE ANGLES WITH LONG LEG VERTICAL. ANGLES SUPPORTING BRICK SHALL BE PLACED WITH VERTICAL LEG TIGHT TO BACK OF INSIDE FACE OF THE BRICK.
6. ALL STEEL LINTELS FOR EXTERIOR WALLS SHALL BE HOT-DIP GALVANIZED AFTER FABRICATION IN ACCORDANCE WITH ASTM A123.
7. BOTTOM PLATES SHALL BE 1/2 INCH LESS IN WIDTH THAN THE WALL THICKNESS AND 1/2 INCH LESS IN LENGTH THAN THE WALL OPENING, UNLESS NOTED OTHERWISE.
8. BOTTOM PLATES SHALL BE WELDED TO THE LINTEL BEAM WITH A 1/4" x 1 1/2" INTERMITTENT WELD AT 12 INCHES ON CENTER ON BOTH SIDES.
9. WHERE LINTELS ARE AT THE SAME COURSE AS BOND BEAMS, WELD REINFORCING BARS TO EACH END OF THE LINTEL OF SAME SIZE AND NUMBER AS IN THE BOND BEAM. THE BARS SHALL EXTEND 48 BAR DIAMETERS INTO THE BOND BEAM. THE BARS SHALL CONFORM TO ASTM A706 AND THE WELD SHALL BE SUFFICIENT TO DEVELOP THE STRENGTH OF THE BAR.

POST-INSTALLED FASTENERS:

- 1. POST-INSTALLED ANCHORS SHALL BE USED ONLY WHERE SPECIFIED ON THE STRUCTURAL DRAWINGS.
2. ACI-CRSI ADHESIVE ANCHOR INSTALLER CERTIFICATION IS REQUIRED FOR ALL INSTALLERS OF ADHESIVE ANCHORS IN HORIZONTAL OR UPWARDLY INCLINED ORIENTATION. THIS CERTIFICATION CAN BE OBTAINED THROUGH ACI OR APPROVED EQUIVALENT.




Table with columns: NO, AS SHOWN, DATE, DESIGNED BY, DRAWN BY, CHECKED BY. Includes revision and scale information.

Table with columns: SCALE, AS SHOWN, DATE, DESIGNED BY, DRAWN BY, CHECKED BY. Includes scale and date information.

Table with columns: PROJECT NO., DRAWING NAME, SHEET OF. Includes project number 232515 and drawing name SD-01.

Table with columns: SHEET OF. Includes sheet number 11 of 17.

POST-INSTALLED FASTENERS CONT:

- FASTENERS SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S PRINTED INSTALLATION INSTRUCTIONS, AS INCLUDED IN THE ANCHOR PACKAGING IN COORDINATION WITH INFORMATION HEREIN. THE STRUCTURAL ENGINEER SHALL BE NOTIFIED IF CONFLICTS EXIST BETWEEN THE MANUFACTURER'S PRINTED INSTALLATION INSTRUCTIONS AND THE REQUIREMENTS HEREIN.
- REINFORCEMENT STEEL SHALL NOT BE CUT. PRIOR TO DRILLING THE CONCRETE, THE CONTRACTOR SHALL BE LOCATED WITH A MAGNETIC BAR LOCATOR. POST-INSTALLED BOLTS AND FASTENERS SHALL BE INSTALLED TO MISS REINFORCEMENT STEEL IN CONCRETE. EXISTING REINFORCING BARS IN THE CONCRETE STRUCTURE MAY CONFLICT WITH SPECIFIC ANCHOR LOCATIONS.
- DRILL HOLES USING ROTARY PERCUSSION DRILL WITH A DEPTH GAGE. DO NOT DRILL THROUGH FULL THICKNESS OF CONCRETE. USE OF A DIAMOND CORE BIT WITH ROUGHENING TOOL FOR ANCHOR HOLES MUST BE APPROVED BY THE STRUCTURAL ENGINEER OF RECORD PRIOR TO DRILLING. UNLESS OTHERWISE SHOWN IN THE DRAWINGS, ALL HOLES SHALL BE DRILLED PERPENDICULAR TO THE CONCRETE SURFACE. CLEAN HOLES IN ACCORDANCE WITH THE MANUFACTURER'S PRINTED INSTALLATION INSTRUCTIONS. IF CONCRETE IS DAMP, BLOW DRY HOLE WITH OIL-FREE COMPRESSED AIR. CLEAN HOLE WITH WATER ONLY IF RECOMMENDED BY MANUFACTURER. ADHESIVE ANCHORS MAY NOT BE SET IF WATER IS SEEPING INTO HOLE AND THE STRUCTURAL ENGINEER, OF RECORD SHALL BE NOTIFIED.
- ANCHOR SUBSTITUTION REQUESTS FOR ALTERNATE PRODUCTS MUST BE SUBMITTED AND APPROVED IN WRITING BY THE STRUCTURAL ENGINEER OF RECORD PRIOR TO USE. CONTRACTOR SHALL PROVIDE DOCUMENTATION DEMONSTRATING THAT THE SUBSTITUTED PRODUCT IS CAPABLE OF MEETING THE PERFORMANCE OF THE SPECIFIED PRODUCT. SUBSTITUTIONS WILL BE EVALUATED BY THEIR HAVING AN ICC ESR SHOWING COMPLIANCE WITH THE RELEVANT BUILDING CODE FOR ITS USE, LOAD RESISTANCE, INSTALLATION CATEGORY, AND AVAILABILITY OF COMPREHENSIVE INSTALLATION INSTRUCTIONS. ADHESIVE ANCHOR EVALUATION WILL ALSO CONSIDER CREEP, IN-SERVICE TEMPERATURE, INSTALLATION TEMPERATURE, MOISTURE CONDITION OF CONCRETE, AND DRILLING METHODS.
- THE CONTRACTOR SHALL ARRANGE AN ANCHOR MANUFACTURER'S REPRESENTATIVE TO PROVIDE ON-SITE INSTALLATION TRAINING FOR ALL ANCHOR PRODUCTS SPECIFIED. THE STRUCTURAL ENGINEER OF RECORD MUST RECEIVE DOCUMENTED CONFIRMATION THAT ALL PERSONNEL WHO INSTALL ANCHORS ARE TRAINED PRIOR TO THE COMMENCEMENT OF ANCHOR INSTALLATION.
- ANCHOR CAPACITY IS DEPENDENT UPON SPACING BETWEEN ADJACENT ANCHORS AND PROXIMITY OF ANCHORS TO EDGE OF CONCRETE. INSTALL ANCHORS IN ACCORDANCE WITH SPACING AND EDGE CLEARANCES INDICATED ON THE DRAWINGS. CONTRACTOR SHALL CONTACT STRUCTURAL ENGINEER SHOULD THE LAYOUT OF THE ANCHOR, EMBEDMENT, SPACING OR EDGE DISTANCES, IS MODIFIED.
- EXCEPT WHERE INDICATED ON THE DRAWINGS, POST-INSTALLED ANCHORS SHALL CONSIST OF THE FOLLOWING ANCHOR TYPES:
 - ANCHORAGE TO CONCRETE:
 - ADHESIVE ANCHORS:
 - HILTI HIT-HY 200 SAFE SET SYSTEM WITH HILTI HIT-Z ROD
 - HILTI HIT-HY 200 SAFE SET SYSTEM INSTALLED USING HILTI HOLLOW DRILL BIT AND VACUUM WITH HAS-V-36 GRADE 36 THREADED ROD
 - HILTI HIT-RE 500V3 SAFE SET SYSTEM INSTALLED USING HILTI HOLLOW DRILL BIT AND VACUUM WITH HAS THREADED ROD
 - SIMPSON SET-XP WITH ASTM A36 THREADED ROD
 - SIMPSON SET-XP INSTALLED USING SIMPSON SPEED CLEAN DXS SYSTEM WITH ASTM A36 THREADED ROD
 - APPROVED EQUAL
 - MECHANICAL ANCHORS:
 - HILTI KWIK HUS-EZ (KH-EZ), KH-EZ CRC, KH-EZ SS316, KH-EZ C, KH-EZ E, KH-EZ I, AND KH-EZ P SCREW ANCHOR SAFE SET SYSTEM INSTALLED USING HOLLOW DRILL BIT AND VACUUM
 - HILTI KWIK BOLT-1 EXPANSION ANCHOR
 - HILTI KWIK BOLT-TZ2 EXPANSION ANCHOR
 - SIMPSON TITEN HD SCREW ANCHOR
 - SIMPSON STRONG-BOLT 2 WEDGE ANCHOR
 - APPROVED EQUAL
 - REBAR DOWELING INTO CONCRETE:
 - HILTI HIT-HY 200 SAFE SET SYSTEM INSTALLED USING HILTI HOLLOW DRILL BIT AND VACUUM WITH CONTINUOUSLY DEFORMED REBAR
 - HILTI HIT-HY 500V3 SAFE SET SYSTEM INSTALLED USING HILTI HOLLOW DRILL BIT AND VACUUM WITH CONTINUOUSLY DEFORMED REBAR
 - SIMPSON SET-XP WITH CONTINUOUSLY DEFORMED REBAR
 - SIMPSON SET-XP INSTALLED USING SIMPSON SPEED CLEAN DXS SYSTEM WITH CONTINUOUSLY DEFORMED REBAR
 - APPROVED EQUAL
 - ANCHORAGE TO SOLID GROUTED MASONRY:
 - ADHESIVE ANCHORS:
 - HILTI HIT-HY 270 SAFE SET SYSTEM INSTALLED USING HILTI HOLLOW DRILL BIT AND VACUUM WITH HILTI HAS CONTINUOUSLY THREADED ROD OR DEFORMED REBAR.
 - SIMPSON SET-XP WITH ASTM A36 THREADED ROD OR CONTINUOUSLY DEFORMED REBAR
 - SIMPSON SET-XP INSTALLED USING SIMPSON SPEED CLEAN DXS SYSTEM WITH ASTM A36 THREADED ROD OR CONTINUOUSLY DEFORMED REBAR
 - APPROVED EQUAL
 - MECHANICAL ANCHORS USE:
 - HILTI KWIK BOLT-1 EXPANSION ANCHOR
 - HILTI KWIK BOLT-TZ2 EXPANSION ANCHOR
 - HILTI KH-EZ, KH-EZ CRC, KH-EZ SS316, KH-EZ C, AND KH-EZ P SCREW ANCHORS
 - SIMPSON STRONG-BOLT 2 WEDGE ANCHOR
 - SIMPSON WEDGE-ALL WEDGE ANCHOR
 - APPROVED EQUAL
 - ANCHORAGE TO HOLLOW / MULTI-WYTHE MASONRY:
 - ADHESIVE ANCHORS USE:
 - HILTI HIT-HY 270 SAFE SET SYSTEM INSTALLED USING THE APPROPRIATE SIZE SCREEN TUBE PER THE ADHESIVE MANUFACTURER'S PRINTED INSTALLATION INSTRUCTIONS AND A HILTI HOLLOW DRILL BIT AND VACUUM WITH HILTI HAS CONTINUOUSLY THREADED ROD OR DEFORMED REBAR. SIMPSON SET-XP THE APPROPRIATE SIZE SCREEN TUBE PER THE ADHESIVE MANUFACTURER'S PRINTED INSTALLATION INSTRUCTIONS WITH ASTM A36 THREADED ROD
 - SIMPSON SET-XP INSTALLED USING SIMPSON SPEED CLEAN DXS SYSTEM WITH ASTM A36 THREADED ROD
 - APPROVED EQUAL

HELICAL PILES:

- HELICAL PILES SHALL BE INSTALLED TO MEET THE MINIMUM TORQUE REQUIRED TO PROVIDE THE LOAD CAPACITIES SHOWN ON THE PLANS. THE MINIMUM TORQUE SHALL BE ENOUGH TO ACHIEVE THE REQUIRED BEARING CAPACITY, INCLUDING A SAFETY FACTOR OF 2. INSTALLATION TORQUE SHALL BE MONITORED THROUGHOUT THE INSTALLATION PROCESS.
- HELICAL PILES ARE TO BE DESIGNED AND MANUFACTURED TO RESIST THE STRESSES INDUCED BY THE INSTALLATION OF THE HELICAL PILES INTO THE SOILS AND RESULTING FROM THE APPLIED LOADS.
- HELICAL PILES ARE TO BE DESIGNED AND MANUFACTURED TO MEET THE CURRENT INTERNATIONAL BUILDING CODE (IBC) USED BY THE STATE IN WHICH THE PROJECT RESIDES. HELICAL PILES SHALL COMPLY WITH 2018 IBC SECTION 1810 AND ARE TO BE DESIGNED AND MANUFACTURED TO RESIST THE STRESSES INDUCED BY THE INSTALLATION OF THE HELICAL PILES AND RESULTING FROM THE APPLIED LOADS.
- HELICAL PILES MANUFACTURE SHALL POSSES ICC ESR REPORT SHOWING THE HELICAL PILES MEET THE REQUIREMENTS OF THE INTERNATIONAL BUILDING CODE. HELICAL PILES SHALL CONFORM TO ICC-AC308 ACCEPTANCE CRITERIA FOR HELICAL FOUNDATION SYSTEMS.
- SHOP DRAWINGS SHALL BE SUBMITTED TO THE AOR AND EOR FOR REVIEW 14 DAYS PRIOR TO INSTALLATION DATE FOR REVIEW. SHOP DRAWINGS ARE TO BE SUBMITTED WITH STAMPED AND SIGNED CALCULATIONS BY AN ENGINEER IN THE STATE OF THE PROJECT. SUBMITTAL SHALL INCLUDE, BUT IS NOT LIMITED TO, HELICAL PILE PLAN SHOWING LOCATIONS OF PILES, SHAFT SIZES, CONNECTIONS BETWEEN PILE SHAFTS, PLATE BEARING VALUES AND CAPACITIES, HELICAL PILE DESIGN LOADS (COMPRESSION, TENSION, LATERAL, BENDINGS), TYPE AND DIMENSIONS OF CENTRAL STEEL SHAFT, DIMENSIONS OF THE SHAFT, QUANTITY, SIZE, THICKNESS, AND SPACING OF THE HELICAL PLATES, MATERIAL TYPE AND STRENGTH, PROTECTION FROM CORROSION, EMBEDMENT DEPTHS, AND MINIMUM AND MAXIMUM TORQUE CAPACITIES.
- LOCATIONS OF HELICAL PILES MAY NOT BE CHANGED WITHOUT WRITTEN APPROVAL FROM THE EOR.

- ALL HELICAL PILES, PLATES AND CONNECTIONS MUST BE CORROSION PROTECTED BY HOT DIP GALVANIZATION PER ASTM A123.
- SPECIAL INSPECTIONS OF THE HELICAL PILE INSTALLATION SHALL BE PERFORMED IN ACCORDANCE WITH SECTION 1705.9 OF THE 2018 IBC UNLESS EXCEPTIONS NOTED IN SECTION 1704.2 OF IBC ARE MET. THE SPECIAL INSPECTOR SHALL RECORD THE FOLLOWING:
 - INSTALLATION DATE
 - PILE MANUFACTURER
 - ALLOWABLE AND ULTIMATE CAPACITY NOTED ON THE SHOP DRAWINGS FOR EACH PILE TYPE INSTALLATION CONTRACTOR
 - MINIMUM & MAXIMUM ALLOWABLE INSTALLATION TORQUES, AND ACTUAL TORQUE ACHIEVED DURING INSTALLATION.
 - SHAFT DIAMETER AND THE CONFIGURATION OF HELICAL PLATES ON EACH PILE.
 - ACTUAL EMBEDMENT OF EACH PILE.
- SEE BOOK SPECIFICATION FOR ADDITIONAL INFORMATION AND SPECIFICATIONS.
- GENERAL CONTRACTOR SHALL COORDINATE ALL UTILITIES, UNDERGROUND HAZARDS, AND OBSTRUCTIONS. ENGINEER/DESIGNER DOES NOT HAVE INFORMATION TO LOCATE / COORDINATE OBSTRUCTIONS AND DOES NOT TAKE RESPONSIBILITY FOR ANY UTILITY, UNDERGROUND HAZARD, OR OBSTRUCTION.
- ALLOWABLE TOLERANCES: CENTERLINE OF HELICAL PILES SHALL NOT BE MORE THAN 3 INCHES FROM INDICATED PLAN LOCATION, HELICAL PILE PLUMBNESS SHALL BE WITHIN 2 DEGREES OF DESIGN ALIGNMENT, AND THE TOP ELEVATION OF HELICAL PILE SHALL BE WITHIN +1 INCH TO -2 INCHES OF THE DESIGN VERTICAL ELEVATION.

SPECIAL INSPECTIONS:

PER THE IBC SECTION 1705, SPECIAL INSPECTIONS ARE REQUIRED FOR THE FOLLOWING ITEMS:

- DUTIES AND RESPONSIBILITIES OF THE SPECIAL INSPECTOR:
 - THE SPECIAL INSPECTOR SHALL OBSERVE THE WORK DESIGNATED TO ASSURE IT IS CONSTRUCTED IN CONFORMANCE TO THE APPROVED CONSTRUCTION DOCUMENTS.
 - THE SPECIAL INSPECTOR SHALL SUBMIT INSPECTION REPORTS AND TESTS TO THE BUILDING OFFICIAL AND REGISTERED DESIGN PROFESSIONAL IN RESPONSIBLE CHARGE.
 - DISCREPANCIES SHALL BE BROUGHT TO THE IMMEDIATE ATTENTION OF THE CONTRACTOR FOR CORRECTION. IF THE DISCREPANCIES ARE NOT CORRECTED, THE DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE BUILDING OFFICIAL AND THE REGISTERED DESIGN PROFESSIONAL IN RESPONSIBLE CHARGE PRIOR TO THE COMPLETION OF THAT PHASE OF THE WORK.
 - A FINAL REPORT DOCUMENTING REQUIRED SPECIAL INSPECTIONS AND TESTS, AND CORRECTION OF ANY DISCREPANCIES NOTED IN THE INSPECTIONS OR TESTS, SHALL BE SUBMITTED WITHIN THE AGREED UPON TIME TO THE BUILDING OFFICIAL PRIOR TO THE START ISSUANCE OF A CERTIFICATE OF OCCUPANCY.
 - PRIOR TO START OF CONSTRUCTION, THE CONTRACTOR SHALL SUBMIT A STATEMENT OF RESPONSIBILITY ACKNOWLEDGING THE AWARENESS OF THE SPECIAL INSPECTION REQUIREMENTS CONTAINED IN THE STATEMENT OF SPECIAL INSPECTIONS.
- CONCRETE:
 - INSPECT REINFORCEMENT, INCLUDING PRESTRESSING TENDONS, AND VERIFY PLACEMENT. (PERIODIC)
 - REINFORCING BAR WELDING:
 - VERIFY WELDABILITY OF REINFORCING BARS OTHER THAN ASTM A706. (PERIODIC)
 - INSPECT SINGLE-PASS FILLET WELDS, MAXIMUM 5/16" (PERIODIC)
 - INSPECT ALL OTHER WELDS (CONTINUOUS)
 - INSPECT ANCHORS CAST IN CONCRETE (PERIODIC)
 - INSPECT ANCHORS POST-INSTALLED IN HARDENED CONCRETE MEMBERS:
 - ADHESIVE ANCHORS INSTALLED IN HORIZONTALLY OR UPWARDLY INCLINED ORIENTATIONS TO RESIST SUSTAINED TENSION LOADS. (CONTINUOUS)
 - MECHANICAL ANCHORS AND ADHESIVE ANCHORS NOT DEFINED ABOVE. (PERIODIC)
 - VERIFY USE OF REQUIRED MIX DESIGN. (PERIODIC)
 - PRIOR TO CONCRETE PLACEMENT, FABRICATE SPECIMENS FOR STRENGTH TESTS, PERFORM SLUMP AND AIR CONTENT TESTS, AND DETERMINE THE TEMPERATURE OF THE CONCRETE. (CONTINUOUS)
 - INSPECT CONCRETE AND SHOTCRETE PLACEMENT FOR PROPER APPLICATION TECHNIQUES. (CONTINUOUS)
 - VERIFY MAINTENANCE OF SPECIFIED CURING TEMPERATURE AND TECHNIQUES. (PERIODIC)
 - INSPECT PRESTRESSED CONCRETE FOR:
 - APPLICATION OF PRESTRESSING FORCES. (CONTINUOUS)
 - GROUTING OF BONDED PRESTRESSING TENDONS. (CONTINUOUS)
 - INSPECT ERECTION OF PRECAST CONCRETE MEMBERS. (PERIODIC)
 - VERIFY IN-SITU CONCRETE STRENGTH, PRIOR TO STRESSING OF TENDONS IN POST-TENSIONED CONCRETE AND PRIOR TO REMOVAL OF SHORES AND FORMS FROM BEAMS AND STRUCTURAL SLABS. (PERIODIC)
 - INSPECT FORMWORK FOR SHAPE, LOCATION AND DIMENSIONS OF THE CONCRETE MEMBER BEING FORMED. (PERIODIC)
 - NO INSPECTION IS REQUIRED FOR SLABS-ON-GRADE.
- MASONRY: (LEVEL C)
 - VERIFY COMPLIANCE WITH THE APPROVED SUBMITTALS. (PERIODIC)
 - VERIFY THAT THE FOLLOWING ARE IN COMPLIANCE:
 - PROPORTIONS OF SITE-MIXED MORTAR, GROUT AND PRESTRESSING GROUT FOR BONDED TENDONS. (PERIODIC)
 - GRADE, TYPE, AND SIZE OF REINFORCEMENT AND ANCHOR BOLTS, AND PRESTRESSING TENDONS AND ANCHORAGES (PERIODIC)
 - PLACEMENT OF MASONRY UNITS AND CONSTRUCTION OF MORTAR JOINTS. (PERIODIC)
 - PLACEMENT OF REINFORCEMENT, CONNECTORS, PRESTRESSING TENDONS AND ANCHORAGES. (CONTINUOUS)
 - GROUT SPACE PRIOR TO GROUTING (CONTINUOUS)
 - PLACEMENT OF GROUT AND PRESTRESSING GROUT FOR BONDED TENDONS (CONTINUOUS)
 - SIZE AND LOCATION OF STRUCTURAL ELEMENTS (PERIODIC)
 - TYPE, SIZE AND LOCATION OF ANCHORS, INCLUDING OTHER DETAILS OF ANCHORAGE OF MASONRY TO STRUCTURAL MEMBERS, FRAMES OR OTHER CONSTRUCTION. (CONTINUOUS)
 - WELDING OF REINFORCEMENT (CONTINUOUS)
 - PREPARATION, CONSTRUCTION, AND PROTECTION OF MASONRY DURING COLD WEATHER (TEMPERATURE BELOW 40°F) OR HOT WEATHER (TEMPERATURE ABOVE 90°F). (PERIODIC)
 - APPLICATION AND MEASUREMENT OF PRESTRESSING FORCE. (CONTINUOUS)
 - PLACEMENT OF AAC MASONRY UNITS AND CONSTRUCTION OF THIN-BED MORTAR JOINTS (CONTINUOUS)
 - PROPERTIES OF THIN-BED MORTAR FOR AAC MASONRY (CONTINUOUS)
 - OBSERVE PREPARATION OF GROUT SPECIMENS, MORTAR SPECIMENS AND/OR PRISMS. (CONTINUOUS)

- SOILS:
 - VERIFY MATERIALS BELOW SHALLOW FOUNDATIONS ARE ADEQUATE TO ACHIEVE THE DESIGN BEARING CAPACITY. (PERIODIC)
 - VERIFY EXCAVATIONS ARE EXTENDED TO PROPER DEPTH AND HAVE REACHED PROPER MATERIAL. (PERIODIC)
 - PERFORM CLASSIFICATION AND TESTING OF CONTROLLED FILL MATERIALS. (PERIODIC)
 - VERIFY USE OF PROPER MATERIALS, DENSITIES AND LIFT THICKNESS DURING PLACEMENT AND COMPACTION OF COMPACTED FILL. (CONTINUOUS)
 - PRIOR TO PLACEMENT OF COMPACTED FILL, OBSERVE SUBGRADE AND VERIFY THAT THE SITE HAS BEEN PROPERLY PREPARED. (PERIODIC)
- HELICAL PILE FOUNDATIONS:
 - VERIFY INSTALLATION EQUIPMENT USED, PILE DIMENSIONS, TIP ELEVATIONS, FINAL DEPTH, FINAL INSTALLATION TORQUE (CONTINUOUS)
 - VERIFY ELEMENT MATERIALS, SIZES AND LENGTHS COMPLY WITH THE REQUIREMENTS. (CONTINUOUS)
 - DETERMINE THE CAPACITIES OF TEST ELEMENTS AND CONDUCT ADDITIONAL LOAD TESTS, AS REQUIRED. (CONTINUOUS)
 - INSPECT DRIVING OPERATIONS AND MAINTAIN COMPLETE AND ACCURATE RECORDS FOR EACH ELEMENT. (CONTINUOUS)
 - VERIFY PLACEMENT LOCATIONS AND PLUMBNESS. DETERMINE REQUIRED PENETRATIONS TO ACHIEVE DESIGN CAPACITY, RECORD TIP AND BUTT ELEVATIONS AND DOCUMENT ANY DAMAGE TO FOUNDATION ELEMENT. (CONTINUOUS)

STRUCTURAL DRAWING ABBREVIATIONS

ADDL	ADDITIONAL	SCHED	SCHEDULE
ADJ	ADJACENT	SECT	SECTION
ALT	ALTERNATE	SF	SQUARE FOOT
&	AND	SIM	SIMILAR
APPROX	APPROXIMATELY	SOG	SLAB-ON-GRADE
ARCH	ARCHITECT OR ARCHITECTURAL	SPA	SPACING
@	AT or SPACING	SPEC(S)	SPECIFICATION(S)
		SQ	SQUARE
B/	BOTTOM OF	STD	STANDARD
BL	BUILDING LINE	STL	STEEL
BLDG	BUILDING	STR	STRUCTURAL
BM	BEAM	STRUCT	STRUCTURAL
BRG	BEARING	SYM	SYMMETRICAL
BTWN	BETWEEN		
BOT	BOTTOM	T	TOP
		T/	TOP OF
CL	CENTERLINE	T&B	TOP AND BOTTOM
CLR	CLEAR	TEMP	TEMPERATURE STEEL
CTR	CENTER	THRU	THROUGH
COL	COLUMN	TRANS	TRANSVERSE
CONC	CONCRETE	TYP	TYPICAL
CONST	CONSTRUCTION		
CONT	CONTINUOUS	UN or UNO	UNLESS NOTED (OTHERWISE)
CJ	CONTROL/CONSTRUCTION JOINT		
CMU	CONCRETE MASONRY UNIT	VERT	VERTICAL
CONT	CONTINUOUS	VIF	VERIFY IN FIELD
CUFT	CUBIC FEET		
CY	CUBIC YARDS	w/	WITH
		w/o	WITHOUT
DEMO	DEMOLITION	WP	WORKPOINT
DIAG	DIAGONAL	WT	WEIGHT
DIA or ø	DIAMETER	WWF	WELDED WIRE FABRIC
DIM	DIMENSION		
DN	DOWN		
DWG	DRAWING		
DWL	DOWEL		
EA	EACH		
EJ	EACH FACE		
EF	EXPANSION JOINT		
EL	ELEVATION		
ELEC	ELECTRICAL		
EMBED	EMBEDDED, EMBEDMENT		
EQ	EQUAL		
ES	EACH SIDE		
EW	EACH WAY		
EX	EXISTING		
EXIST	EXISTING		
EXP	EXPANSION		
EXT	EXTERIOR		
FAB	FABRICATE		
FDN	FOUNDATION		
FIN	FINISH		
FLG	FLANGE		
FLR	FLOOR		
FS	FAR SIDE		
FT	FOOT, FEET		
FTG	FOOTING		
GA	GAGE		
GAL	GALLON		
GALV	GALVANIZED		
GC	GENERAL CONTRACTOR		
GEN	GENERAL		
GLB	GLUE LAMINATED BEAM		
GR	GRADE		
GYP BD	GYPSUM BOARD		
HC	HOLLOW CORE		
HORIZ	HORIZONTAL		
HT	HEIGHT		
HVY	HEAVY		
ID	INSIDE DIAMETER		
IF	INSIDE FACE		
IN	INCH		
INFO	INFORMATION		
INT	INTERIOR		
INV	INVERT		
JST	JOIST		
JT	JOINT		
K	KIPS		
KSF	KIPS PER SQUARE FOOT		
KSI	KIPS PER SQUARE INCH		
L	ANGLE		
LBS	POUNDS		
LF	LINEAL FEET		
LG	LONG		
LL	LIVE LOAD		
LLH	LONG LEG HORIZONTAL		
LLV	LONG LEG VERTICAL		
LOC	LOCATION		
LONG	LONGITUDINAL		
MAX	MAXIMUM		
MECH	MECHANICAL		
MFR	MANUFACTURER		
MIN	MINIMUM		
MISC	MISCELLANEOUS		
MK	MARK		
MO	MASONRY OPENING		
MTL	METAL		
NO or #	NUMBER		
NOM	NOMINAL		
NS	NEAR SIDE		
NTS	NOT TO SCALE		
OC	ON CENTER		
OD	OUTSIDE DIAMETER		
OF	OUTSIDE FACE		
OPNG	OPENING		
PC	PRECAST		
PERP	PERPENDICULAR		
PL	PLATE		
PLF	POUNDS PER LINEAL FOOT		
PLYWD	PLY WOOD		
PREFAB	PREFABRICATED		
PSF	POUNDS PER SQUARE FOOT		
PSI	POUNDS PER SQUARE INCH		
QTY	QUANTITY		
RAD	RADIUS		
REF	REFERENCE		
REINF	REINFORCEMENT, REINFORCING, REINFORCED		
REQD	REQUIRED		



NO	REVISION	DATE


SCALE:	AS SHOWN
DATE:	10/30/2024
DESIGNED BY:	BF
DRAWN BY:	BW
CHECKED BY:	BF

THE CITY OF PAINESVILLE
 WATER TREATMENT PLANT
 CHLORINE BUILDING
 LAKE COUNTY
 MENTOR, OHIO
 CHLORINE FEED BUILDING
 GENERAL NOTES

PROJECT NO:	232515
DRAWING NAME	SD-02
SHEET	OF
12	17

TABLE 1705.3 REQUIRED SPECIAL INSPECTIONS OF CONCRETE CONSTRUCTION					
REQUIRED	TYPE	CONTINUOUS SPECIAL INSPECTION	PERIODIC SPECIAL INSPECTION	REFERENCED STANDARD ^a	IBC REFERENCE
X	1. INSPECT REINFORCEMENT, INCLUDING PRESTRESSING TENDONS, AND VERIFY PLACEMENT.	-	X	ACI 318 CH. 20, 25.2, 25.3, 26.6.1-26.6.3	1908.4
X	2. REINFORCING BAR WELDING:				
X	a. VERIFY WELDABILITY OF REINFORCING BARS OTHER THAN ASTM A706;	-	X	AWS D1.4 ACI 318: 26.6.4	-
X	b. INSPECT SINGLE-PASS FILLET WELDS, MAXIMUM 5/16"; AND		X		
X	c. INSPECT ALL OTHER WELDS	X			
X	3. INSPECT ANCHORS CAST INTO CONCRETE.	-	X	ACI 318: 17.8.2	-
X	4. INSPECT ANCHORS POST-INSTALLED IN HARDENED CONCRETE MEMBERS: ^b				
X	a. ADHESIVE ANCHORS INSTALLED IN HORIZONTALLY OR UPWARDLY INCLINED ORIENTATIONS TO RESIST SUSTAINED TENSION LOADS.	X		ACI 318: 17.8.2.4	-
X	b. MECHANICAL ANCHORS AND ADHESIVE ANCHORS NOT DEFINED IN 4.a.		X	ACI 318: 17.8.2	
X	5. VERIFY USE OF REQUIRED DESIGN MIX.	-	X	ACI 318: CH. 19, 26.4.3, 26.4.4	1904.1, 1904.2, 1908.2, 1908.3
X	6. PRIOR TO CONCRETE PLACEMENT, FABRICATE SPECIMENS FOR STRENGTH TESTS, PERFORM SLUMP AND AIR CONTENT TESTS, AND DETERMINE THE TEMPERATURE OF THE CONCRETE	X	-	ASTM C172 ASTM C31 ACI 318: 26.4, 26.12	1908.10
X	7. INSPECT CONCRETE AND SHOTCRETE PLACEMENT FOR PROPER APPLICATION TECHNIQUES.	X	-	ACI 318: 26.5	1908.6, 1908.7, 1908.8
X	8. VERIFY MAINTENANCE OF SPECIFIED CURING TEMPERATURE AND TECHNIQUES.	-	X	ACI 318: 26.5.3-26.5.5	1908.9
X	9. INSPECT PRESTRESSED CONCRETE FOR:				
X	a. APPLICATION OF PRESTRESSING FORCES; AND	X	-	ACI 318: 26.10	-
X	b. GROUTING OF BONDED PRESTRESSING TENDONS.	X	-		
X	10. INSPECT ERECTION OF PRECAST CONCRETE MEMBERS.	-	X	ACI 318: CH. 26.8	-
X	11. VERIFY IN-SITU CONCRETE STRENGTH, PRIOR TO STRESSING OF TENDONS IN POST-TENSIONED CONCRETE AND PRIOR TO REMOVAL OF SHORES AND FORMS FROM BEAMS AND STRUCTURAL SLABS.	-	X	ACI 318: 26.11.2	-
X	12. INSPECT FORMWORK FOR SHAPE, LOCATION AND DIMENSIONS OF THE CONCRETE MEMBER BEING FORMED.	-	X	ACI 318: CH. 26.11.2(b)	-

MINIMUM TESTS					
VERIFICATION OF f_m AND f_{ACI} IN ACCORDANCE WITH SPECIFICATION ARTICLE 1.4 B PRIOR TO CONSTRUCTION AND FOR EVERY 5,000 SQ. FT (465 SQ. M) DURING CONSTRUCTION					
VERIFICATION OF PROPORTIONS OF MATERIALS IN PREMIXED OR PREBLENDED MORTAR, PRESTRESSING GROUT, AND GROUT OTHER THAN SELF-CONSOLIDATING GROUT, AS DELIVERED TO THE PROJECT SITE					
VERIFICATION OF SLUMP FLOW AND VISUAL STABILITY INDEX (VSI) AS DELIVERED TO THE PROJECT SITE IN ACCORDANCE WITH SPECIFICATION ARTICLE 1.5 B.1.b.3 FOR SELF-CONSOLIDATING GROUT					
REQUIRED	INSPECTION TASK	FREQUENCY		REFERENCE FOR CRITERIA	
		CONTINUOUS	PERIODIC	TMS 402/ ACI 530/ ASCE 5	TMS 602/ ACI 530.1/ ASCE 6
X	1. VERIFY COMPLIANCE WITH APPROVED SUBMITTAL	-	X	-	ART. 1.5
X	2. VERIFY THAT THE FOLLOWING ARE IN COMPLIANCE:				
X	a. PROPORTIONS OF SITE-MIXED MORTAR, GROUT AND PRESTRESSING GROUT FOR BONDED TENDONS	-	X	-	ART. 2.1, 2.6 A, 2.6 B, 2.6 C, 2.4 G 1.b
X	b. GRADE, TYPE, AND SIZE OF REINFORCEMENT AND ANCHOR BOLTS, AND PRESTRESSING TENDONS AND ANCHORAGES	-	X	SEC. 6.1	ART. 2.4, 3.4
X	c. PLACEMENT OF MASONRY UNITS AND CONSTRUCTION OF MORTAR JOINTS	-	X	-	ART. 3.3 B
X	d. PLACEMENT OF REINFORCEMENT, CONNECTORS, AND PRESTRESSING TENDONS AND ANCHORAGES	X	-	SEC. 6.1, 6.2.1, 6.2.6, 6.2.7	ART. 3.2 E, 3.4, 3.6 A
X	e. GROUT SPACE PRIOR TO GROUTING	X	-	-	ART. 3.2 D, 3.2 F
X	f. PLACEMENT OF GROUT AND PRESTRESSING GROUT FOR BONDED TENDONS	X	-	-	ART. 3.5, 3.6 C
X	g. SIZE AND LOCATION OF STRUCTURAL ELEMENTS	-	X	-	ART. 3.3 F
X	h. TYPE, SIZE, AND LOCATION OF ANCHORS INCLUDING OTHER DETAILS OF ANCHORAGE OF MASONRY TO STRUCTURAL MEMBERS, FRAMES, OR OTHER CONSTRUCTION	X	-	SEC. 1.2.1(e), 6.1.4.3, 6.2.1	-
X	i. WELDING OF REINFORCEMENT	X	-	SEC. 8.1.6.7.2, 9.3.3.4 (c), 11.3.3.4(b)	-
X	j. PREPARATION, CONSTRUCTION, AND PROTECTION OF MASONRY DURING COLD WEATHER (TEMPERATURE BELOW 40 DEG F (4.4 DEG C)) OR HOT WEATHER (TEMPERATURE ABOVE 90 DEG F (32.2 DEG C))	-	X	-	ART. 1.8 C, 1.8 D
X	k. APPLICATION AND MEASUREMENT OF PRESTRESSING FORCE	X	-	-	ART. 3.6 B
X	l. PLACEMENT OF AAC MASONRY UNITS AND CONSTRUCTION OF THIN-BED MORTAR JOINTS	X	-	-	ART. 3.3 B.9, 3.3 F.1.b
X	m. PROPERTIES OF THIN-BED MORTAR FOR AAC MASONRY	X	-	-	ART. 2.1 C.1
X	3. OBSERVE PREPARATION OF GROUT SPECIMENS, MORTAR SPECIMENS, AND/OR PRISMS	X	-	-	ART. 1.4 B.2.a.3, 1.4 B.2.b.3, 1.4 B.2.c.3, 1.4 B.3, 1.4 B.4



- NOTES:
- VALUES LISTED IN THE ABOVE TABLE ARE BASED UPON AN ENCLOSED BUILDING USING THE SPECIFIED WIND LOADING AS INDICATED IN THE 'DESIGN LOADS' SECTION OF THE GENERAL NOTES.
 - PRESSURE (POSITIVE) AND SUCTION (NEGATIVE) VALUES SIGNIFY LOADING ACTING TOWARDS AND AWAY FROM THE BUILDING SURFACES, RESPECTIVELY (FULL HEIGHT, UNLESS NOTED.)
 - VALUES LISTED IN THE ABOVE TABLE ARE ULTIMATE WIND PRESSURES. TO OBTAIN ALLOWABLE STRESS DESIGN WIND VALUES, MULTIPLY THE VALUES SHOWN IN THE ABOVE TABLE BY 0.6.
 - EFFECTIVE WIND AREAS, UNLESS NOTED OTHERWISE:
 $a^* = 0.6h$
 $b^* = 0.2h$
 $c^* = 0.4h$ (3'-0" MIN)
 - SUCTION VALUES LISTED IN ROOF ZONES 1, 1', 2 & 3 INDICATE GROSS UPLIFT PRESSURES.







NO	REVISION	DATE

SCALE: AS SHOWN	DATE: 10/30/2024	DESIGNED BY: BF	DRAWN BY: BW	CHECKED BY: BF
-----------------	------------------	-----------------	--------------	----------------

THE CITY OF PAINESVILLE
WATER TREATMENT PLANT
CHLORINE BUILDING
LAKE COUNTY MENTOR, OHIO
CHLORINE FEED BUILDING
GENERAL NOTES

PROJECT NO:	232515
DRAWING NAME:	SD-03
SHEET	OF
13	17

DIM	"T" WALL THICKNESS				
	6"	8"	10"	12"	18"
a	1"	1 1/4"	1 1/2"	1 3/4"	2 1/2"
b	1/2"	1/2"	1/2"	1/2"	1/2"
c	3/4"	3/4"	3/4"	3/4"	3/4"






TYPICAL VERTICAL CONTRACTION AND CONSTRUCTION JOINTS IN CONCRETE WALL DETAIL
3/4" = 1'-0"

TYPICAL FLOOR SLAB REINF AT RE-ENTRANT CORNERS DETAIL
1/2" = 1'-0"




HOUSE KEEPING PAD ON SOG
3/4" = 1'-0"

TYPICAL REINFORCING AT OPENINGS IN CONCRETE WALL DETAIL
1/2" = 1'-0"



TYPICAL STEPPED FOOTING DETAIL
3/4" = 1'-0"

TYPICAL FLOOR DRAIN DETAIL
3/4" = 1'-0"




TYPICAL PIPE PENETRATION DETAIL (MULTIPLE)
3/4" = 1'-0"

LAP TABLE (f _c = 4,000 PSI)					
BAR SIZE	LAP CLASS	UNCOATED BARS			
		TOP BARS		OTHER BARS	
		CASE 1	CASE 2	CASE 1	CASE 2
#3	A	19	28	15	22
	B	24	36	19	28
#4	A	25	37	19	29
	B	32	48	25	37
#5	A	31	47	24	36
	B	40	60	31	47
#6	A	37	56	29	43
	B	48	72	37	56
#7	A	54	81	42	63
	B	70	106	54	81
#8	A	62	93	48	71
	B	80	121	62	93



LAP TABLE (f _c = 4,500 PSI)					
BAR SIZE	LAP CLASS	UNCOATED BARS			
		TOP BARS		OTHER BARS	
		CASE 1	CASE 2	CASE 1	CASE 2
#3	A	18	26	14	20
	B	23	34	18	26
#4	A	23	35	18	27
	B	30	45	23	35
#5	A	29	44	23	34
	B	38	56	29	44
#6	A	35	53	27	40
	B	45	68	35	53
#7	A	51	87	39	59
	B	66	100	51	77
#8	A	58	88	45	67
	B	76	114	58	88

NOTES:
1. TABULATED VALUES ARE BASED ON A MINIMUM YIELD STRENGTH OF 60,000 PSI. LENGTHS ARE IN INCHES.
2. CASES 1 AND 2, WHICH DEPEND ON THE TYPE OF STRUCTURAL MEMBER, CONCRETE COVER, AND OC SPACING OF THE BARS ARE DEFINED AS:
BEAMS AND COLUMNS
• CASE 1: CONCRETE COVER AT LEAST 1.0d_b AND OC SPACING AT LEAST 2.0 d_b
• CASE 2: CONCRETE COVER LESS THAN 1.0d_b OR OC SPACING AT LESS THAN 2.0 d_b
OTHER BARS
• CASE 1: CONCRETE COVER AT LEAST 1.0d_b AND OC SPACING AT LEAST 3.0 d_b
• CASE 2: CONCRETE COVER LESS THAN 1.0d_b OR OC SPACING AT LESS THAN 3.0 d_b
3. TOP BARS ARE HORIZONTAL BARS WITH MORE THAN 12 INCHES OF CONCRETE CAST BELOW THE BARS.

NOTES:
1. TABULATED VALUES ARE BASED ON A MINIMUM YIELD STRENGTH OF 60,000 PSI. LENGTHS ARE IN INCHES.
2. CASES 1 AND 2, WHICH DEPEND ON THE TYPE OF STRUCTURAL MEMBER, CONCRETE COVER, AND OC SPACING OF THE BARS ARE DEFINED AS:
BEAMS AND COLUMNS
• CASE 1: CONCRETE COVER AT LEAST 1.0d_b AND OC SPACING AT LEAST 2.0 d_b
• CASE 2: CONCRETE COVER LESS THAN 1.0d_b OR OC SPACING AT LESS THAN 2.0 d_b
OTHER BARS
• CASE 1: CONCRETE COVER AT LEAST 1.0d_b AND OC SPACING AT LEAST 3.0 d_b
• CASE 2: CONCRETE COVER LESS THAN 1.0d_b OR OC SPACING AT LESS THAN 3.0 d_b
3. TOP BARS ARE HORIZONTAL BARS WITH MORE THAN 12 INCHES OF CONCRETE CAST BELOW THE BARS.



WHERE MULTIPLE LAYERS ARE SPECIFIED (TOP OR BOT REIN) PROVIDE 1" MIN CLR AND PLACE UPPER LEVEL BARS DIRECTLY OVER LOWER LEVEL AS SHOWN UNO (PROVIDE #8 SPACER)



TYPICAL GRADE BEAM SECTION

TYPICAL GRADE BEAM ELEVATION


NO	REVISION	DATE

SCALE: AS SHOWN
DATE: 10/30/2024
DESIGNED BY: BF
DRAWN BY: BW
CHECKED BY: BF

THE CITY OF PAINESVILLE
WATER TREATMENT PLANT
CHLORINE BUILDING
LAKE COUNTY
MENTOR, OHIO


STANDARD DETAILS
SECTIONS AND TYPICAL DETAILS

PROJECT NO:	232515
DRAWING NAME:	SD-04
SHEET OF:	14 OF 17




TYPICAL MASONRY OPENING DETAIL

1/2" = 1'-0"




TYPICAL WALL CORNER DETAILS

3/4" = 1'-0"




TYPICAL MASONRY CONTROL JOINT DETAIL

1 1/2" = 1'-0"




TYPICAL CMU REINF POSITIONERS DETAIL

1" = 1'-0"




TYPICAL SLOPED WALL BOND BEAM DETAIL

1/2" = 1'-0"



TYPICAL VERTICAL CMU CONSTRUCTION JOINT DETAIL

1" = 1'-0"




NO	REVISION	DATE

SCALE:	AS SHOWN
DATE:	10/30/2024
DESIGNED BY:	BF
DRAWN BY:	BW
CHECKED BY:	BF


THE CITY OF PAINESVILLE
 WATER TREATMENT PLANT
 CHLORINE BUILDING
 LAKE COUNTY MENTOR, OHIO

STANDARD DETAILS
 SECTIONS AND TYPICAL DETAILS


PROJECT NO:	232515
DRAWING NAME	SD-05
SHEET	15
OF	17




1 SECTION
S3.01 3/4" = 1'-0"




2 SECTION
S3.01 3/4" = 1'-0"



3 SECTION
S3.01 3/4" = 1'-0"



4 SECTION
S3.01 3/4" = 1'-0"



5 TYPICAL THICKENED SLAB AT STAIR DETAIL
S3.01 3/4" = 1'-0"



NO.	DATE	REVISION

SCALE:	AS SHOWN
DATE:	10/30/2024
DESIGNED BY:	BF
DRAWN BY:	BW
CHECKED BY:	BF

THE CITY OF PAINESVILLE
 WATER TREATMENT PLANT
 CHLORINE BUILDING
 LAKE COUNTY MENTOR, OHIO

STANDARD DETAILS
 SECTIONS AND TYPICAL DETAILS

PROJECT NO:	232515
DRAWING NAME	SD-06
SHEET	16
OF	17

