

## ADDENDUM #2

**Job #:** 240070      **Project Title** Forest Park 2024 Street Program

**Client:** City of Forest Park

**Issue** April 22, 2024  
**Date:**

**Bid Date:** May 2, 2024

THIS IS TO CERTIFY THAT YOU ARE IN RECEIPT OF ADDENDUM #2 FOR THE ABOVE-MENTIONED PROJECT.

PLEASE SIGN AND RETURN VIA EMAIL TO: [pbellew@ctconsultants.com](mailto:pbellew@ctconsultants.com).

\_\_\_\_\_  
Name / Title:

\_\_\_\_\_  
Company:

\_\_\_\_\_  
Date:

The bid proposal form is attached.



**2024 CITY FOREST PARK STREET PROGRAM**  
**HAVENSPORT DRIVE, RAPHAEL DRIVE, AND CARILLON BOULEVARD**  
**CITY OF FOREST PARK, HAMILTON COUNTY, OHIO**

DATE: 4/18/24  
 PROJECT: 240070

Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure	Unit Cost Total	Item Cost
<b>HAVENSPORT DRIVE</b>						
1	253	* PAVEMENT REPAIR, AS PER PLAN	141	SY	\$100.00	
2	254	PAVEMENT PLANING, ASPHALT CONCRETE (1-1/2" FULL WIDTH)	5650	SY	\$4.00	
3	407	TRACKLESS TACK COAT, AS PER PLAN	565	GAL	\$7.00	
4	441	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, (448) (1")	173	CY	\$250.00	
5	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG64-22, (448) (1-1/2")	254	CY	\$260.00	
6	441	ASPHALT CONCRETE MISC.: 1/2" STRESS ABSORBING MEMBRANE INTERLAYER, (SAMI), TYPE 1	5650	SY	\$5.00	
7	441	ASPHALT CONCRETE MISC.: ASPHALT REJUVENATING AGENT	5650	SY	\$1.50	
8	614	MAINTAINING TRAFFIC	1	LS	\$2,500.00	
9	608	ADA CURB RAMP, AS PER PLAN, INCLUDING REMOVAL OF UNCLASSIFIED MATERIAL AND CURB REPLACEMENT, (SEPARATE PAY ITEM FOR TRUNCATED DOMES )	450	SF	\$24.00	
10	608	ADA CURB RAMP, INSTALLING TRUNCATED DOMES	40	SF	\$40.00	
11	608	SPOT CURB AND GUTTER REMOVE AND REPLACE	200	LF	\$48.00	
12	611	STORM MANHOLE ADJUSTED TO GRADE	2	EA	\$1,000.00	
13	611	DOWNSPOUT CONDUIT, MISC : PVC SCHEDULE 40 PIPE - 3"	1	LF	\$50.00	
14	SPL	SANITARY MANHOLE ADJUSTED TO GRADE	6	LF	\$1,000.00	
15	644	STOP LINE, 24" WHITE THERMOPLASTIC	24	LF	\$9.00	
16	611	FURNISH NEW CURB PLATE, S.G.I. AS PER PLAN	4	EA	\$700.00	
17	611	CATCH BASIN - DOUBLE GRATE INLET - REBUILD TOP 18" USING PRECAST TOP	1	EA	\$2,200.00	
18	611	FURNISH NEW CURB PLATE, D.G.I. AS PER PLAN	6	EA	\$800.00	
19	611	FURNISH NEW GRATE, AS PER PLAN	16	EA	\$800.00	
20	653	* TOPSOIL FURNINSHED AND PLACED	1	CY	\$50.00	
21	659	* REPAIR SEEDING AND MULCHING	1	SY	\$1.00	
22	659	* WATER	1	M/GAL	\$10.00	
<b>TOTAL - HAVENSPORT DRIVE</b>						
<b>RAPHAEL DRIVE</b>						
23	253	* PAVEMENT REPAIR, AS PER PLAN	174	SY	\$100.00	
24	254	PAVEMENT PLANING, ASPHALT CONCRETE (2-1/2" FULL WIDTH)	6960	SY	\$4.00	
25	407	TRACKLESS TACK COAT, AS PER PLAN	696	GAL	\$7.00	
26	441	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, (448) (1")	90	CY	\$250.00	

\*DENOTES CONTINGENCY ITEM - USE ONLY AT THE DIRECTION OF THE ENGINEER



**2024 CITY FOREST PARK STREET PROGRAM**  
**HAVENSPORT DRIVE, RAPHAEL DRIVE, AND CARILLON BOULEVARD**  
**CITY OF FOREST PARK, HAMILTON COUNTY, OHIO**

DATE: 4/18/24  
 PROJECT: 240070

27	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG64-22, (448) (1-1/2")	313	CY	\$260.00	
28	441	ASPHALT CONCRETE MISC.: 1/2" STRESS ABSORBING MEMBRANE INTERLAYER, (SAMI), TYPE 1	6960	SY	\$5.00	
29	441	ASPHALT CONCRETE MISC.: ASPHALT REJUVENATING AGENT	6960	SY	\$1.50	
30	SPL	SANITARY MANHOLE ADJUSTED TO GRADE	1	EA	\$1,000.00	
31	611	STORM MANHOLE ADJUSTED TO GRADE	1	EA	\$1,000.00	
32	611	*DOWNSPOUT CONDUIT, MISC : PVC SCHEDULE 40 PIPE, 3"	1	LF	\$10.00	
33	608	ADA CURB RAMP, AS PER PLAN, INCLUDING REMOVAL OF UNCLASSIFIED MATERIAL AND CURB REPLACEMENT, (SEPARATE PAY ITEM FOR TRUNCATED DOMES )	1100	SF	\$24.00	
34	608	* CURB AND GUTTER REMOVE AND REPLACE	2570	LF	\$42.50	
35	608	ADA CURB RAMP, INSTALLING TRUNCATED DOMES	60	SF	\$40.00	
36	614	MAINTAINING TRAFFIC	1	LS	\$2,500.00	
37	644	STOP LINE, 24" WHITE THERMOPLASTIC	24	LF	\$9.00	
38	611	FURNISH NEW CURB PLATE, S.G.I. AS PER PLAN	7	EA	\$700.00	
39	611	CATCH BASIN - SINGLE GRATE INLET - REBUILD TOP 18" USING PRECAST TOP	3	EA	\$2,500.00	
40	611	FURNISH NEW CURB PLATE, D.G.I. AS PER PLAN	6	EA	\$800.00	
41	611	* FURNISH NEW GRATE, AS PER PLAN	19	EA	\$800.00	
42	653	* TOPSOIL FURNISHED AND PLACED	95	CY	\$50.00	
43	659	* REPAIR SEEDING AND MULCHING	1	SY	\$1.00	
44	659	* WATER	1	M/GAL	\$10.00	
<b>TOTAL RAPHAEL DRIVE</b>						
<b>CARILLON BOULEVARD</b>						
45	253	* PAVEMENT REPAIR, AS PER PLAN	151	SY	\$100.00	
46	254	PAVEMENT PLANING, ASPHALT CONCRETE (2-1/2" FULL WIDTH)	6050	SY	\$4.00	
47	407	TRACKLESS TACK COAT, AS PER PLAN	605	GAL	\$7.00	
48	441	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, (448) (1")	185	CY	\$250.00	
49	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG64-22, (448) (1-1/2")	277	CY	\$260.00	
50	441	ASPHALT CONCRETE MISC.: 1/2" STRESS ABSORBING MEMBRANE INTERLAYER, (SAMI), TYPE 1	6050	SY	\$5.00	
51	441	ASPHALT CONCRETE MISC.: ASPHALT REJUVENATING AGENT	6050	SY	\$1.50	
52	614	MAINTAINING TRAFFIC	1	LS	\$10,000.00	
53	644	CENTER LINE, 4" SOLID DOUBLE YELLOW	1570	LF	\$1.00	
54	644	CHANNELIZING LINE, 8" SOLID WHITE THERMOPLASTIC	200	LF	\$2.50	



**2024 CITY FOREST PARK STREET PROGRAM**  
**HAVENSPORT DRIVE, RAPHAEL DRIVE, AND CARILLON BOULEVARD**  
**CITY OF FOREST PARK, HAMILTON COUNTY, OHIO**

DATE: 4/18/24  
 PROJECT: 240070

55	644	STOP LINE, 24" THERMOPLASTIC	50	LF	\$7.50	
56	644	DIAGONAL CROSS HATCH MARKING, 24" YELLOW THERMOPLASTIC	210	LF	\$7.50	
57	644	LANE ARROW, 96" WHITE	4	EA	\$125.00	
58	644	WORD ON PAVEMENT, 96" WHITE	2	EA	\$125.00	
59	809	STOP-LINE RADAR DETECTION	1	EA	\$10,000.00	
60	611	FURNISH NEW CURB PLATE, D.G.I. AS PER PLAN	10	EA	\$800.00	
61	611	* FURNISH NEW GRATE, AS PER PLAN	20	EA	\$800.00	
62	653	* TOPSOIL FURNISHED AND PLACED	1	CY	\$50.00	
63	659	* REPAIR SEEDING AND MULCHING	1	SY	\$1.00	
64	659	* WATER	1	M/GAL	\$10.00	
<b>TOTAL CARILLON BLVD</b>						
<b>TOTAL BID (HAVENSPORT + RAPHAEL + CARILLON)</b>						

\*DENOTES CONTINGENCY ITEM - USE ONLY AT THE DIRECTION OF THE ENGINEER