

ADDENDUM #3

Job #: 240070 **Project Title** Forest Park 2024 Street Program

Client: City of Forest Park

Issue April 23, 2024
Date:

Bid Date: May 2, 2024

THIS IS TO CERTIFY THAT YOU ARE IN RECEIPT OF ADDENDUM #3 FOR THE ABOVE-MENTIONED PROJECT.

PLEASE SIGN AND RETURN VIA EMAIL TO: pbellew@ctconsultants.com.

Name / Title:

Company:

Date:

The blank bid proposal form is attached.



**2024 CITY FOREST PARK STREET PROGRAM
HAVENSPORT DRIVE, RAPHAEL DRIVE, AND CARILLON BOULEVARD
CITY OF FOREST PARK, HAMILTON COUNTY, OHIO**

DATE: 4/18/24
PROJECT: 240070

Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure	Unit Cost Total	Item Cost
HAVENSPORT DRIVE						
1	253	* PAVEMENT REPAIR, AS PER PLAN	141	SY		
2	254	PAVEMENT PLANING, ASPHALT CONCRETE (1-1/2" FULL WIDTH)	5650	SY		
3	407	TRACKLESS TACK COAT, AS PER PLAN	565	GAL		
4	441	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, (448) (1")	173	CY		
5	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG64-22, (448) (1-1/2")	254	CY		
6	441	ASPHALT CONCRETE MISC.: 1/2" STRESS ABSORBING MEMBRANE INTERLAYER, (SAMI), TYPE 1	5650	SY		
7	441	ASPHALT CONCRETE MISC.: ASPHALT REJUVENATING AGENT	5650	SY		
8	614	MAINTAINING TRAFFIC	1	LS		
9	608	ADA CURB RAMP, AS PER PLAN, INCLUDING REMOVAL OF UNCLASSIFIED MATERIAL AND CURB REPLACEMENT, (SEPARATE PAY ITEM FOR TRUNCATED DOMES)	450	SF		
10	608	ADA CURB RAMP, INSTALLING TRUNCATED DOMES	40	SF		
11	608	SPOT CURB AND GUTTER REMOVE AND REPLACE	200	LF		
12	611	STORM MANHOLE ADJUSTED TO GRADE	2	EA		
13	611	DOWNSPOUT CONDUIT, MISC : PVC SCHEDULE 40 PIPE - 3"	1	LF		

*DENOTES CONTINGENCY ITEM - USE ONLY AT THE DIRECTION OF THE ENGINEER



**2024 CITY FOREST PARK STREET PROGRAM
HAVENSPORT DRIVE, RAPHAEL DRIVE, AND CARILLON BOULEVARD
CITY OF FOREST PARK, HAMILTON COUNTY, OHIO**

DATE: 4/18/24
PROJECT: 240070

14	SPL	SANITARY MANHOLE ADJUSTED TO GRADE	6	LF		
15	644	STOP LINE, 24" WHITE THERMOPLASTIC	24	LF		
16	611	FURNISH NEW CURB PLATE, S.G.I. AS PER PLAN	4	EA		
17	611	CATCH BASIN - DOUBLE GRATE INLET - REBUILD TOP 18" USING PRECAST TOP	1	EA		
18	611	FURNISH NEW CURB PLATE, D.G.I. AS PER PLAN	6	EA		
19	611	FURNISH NEW GRATE, AS PER PLAN	16	EA		
20	653	* TOPSOIL FURNINSHED AND PLACED	1	CY		
21	659	* REPAIR SEEDING AND MULCHING	1	SY		
22	659	* WATER	1	M/GAL		

TOTAL - HAVENSPORT DRIVE

RAPHAEL DRIVE

23	253	* PAVEMENT REPAIR, AS PER PLAN	174	SY		
24	254	PAVEMENT PLANING, ASPHALT CONCRETE (2-1/2" FULL WIDTH)	6960	SY		
25	407	TRACKLESS TACK COAT, AS PER PLAN	696	GAL		
26	441	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, (448) (1")	90	CY		
27	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG64-22, (448) (1-1/2")	313	CY		
28	441	ASPHALT CONCRETE MISC.: 1/2" STRESS ABSORBING MEMBRANE INTERLAYER, (SAMI), TYPE 1	6960	SY		

*DENOTES CONTINGENCY ITEM - USE ONLY AT THE DIRECTION OF THE ENGINEER



**2024 CITY FOREST PARK STREET PROGRAM
HAVENSPORT DRIVE, RAPHAEL DRIVE, AND CARILLON BOULEVARD
CITY OF FOREST PARK, HAMILTON COUNTY, OHIO**

DATE: 4/18/24
PROJECT: 240070

29	441	ASPHALT CONCRETE MISC.: ASPHALT REJUVENATING AGENT	6960	SY		
30	SPL	SANITARY MANHOLE ADJUSTED TO GRADE	1	EA		
31	611	STORM MANHOLE ADJUSTED TO GRADE	1	EA		
32	611	*DOWNSPOUT CONDUIT, MISC : PVC SCHEDULE 40 PIPE, 3"	1	LF		
33	608	ADA CURB RAMP, AS PER PLAN, INCLUDING REMOVAL OF UNCLASSIFIED MATERIAL AND CURB REPLACEMENT, (SEPARATE PAY ITEM FOR TRUNCATED DOMES)	1100	SF		
34	608	* CURB AND GUTTER REMOVE AND REPLACE	2570	LF		
35	608	ADA CURB RAMP, INSTALLING TRUNCATED DOMES	60	SF		
36	614	MAINTAINING TRAFFIC	1	LS		
37	644	STOP LINE, 24" WHITE THERMOPLASTIC	24	LF		
38	611	FURNISH NEW CURB PLATE, S.G.I. AS PER PLAN	7	EA		
39	611	CATCH BASIN - SINGLE GRATE INLET - REBUILD TOP 18" USING PRECAST TOP	3	EA		
40	611	FURNISH NEW CURB PLATE, D.G.I. AS PER PLAN	6	EA		
41	611	* FURNISH NEW GRATE, AS PER PLAN	19	EA		
42	653	* TOPSOIL FURNISHED AND PLACED	95	CY		
43	659	* REPAIR SEEDING AND MULCHING	1	SY		
44	659	* WATER	1	M/GAL		

*DENOTES CONTINGENCY ITEM - USE ONLY AT THE DIRECTION OF THE ENGINEER



**2024 CITY FOREST PARK STREET PROGRAM
HAVENSPORT DRIVE, RAPHAEL DRIVE, AND CARILLON BOULEVARD
CITY OF FOREST PARK, HAMILTON COUNTY, OHIO**

DATE: 4/18/24
PROJECT: 240070

TOTAL RAPHAEL DRIVE					
CARILLON BOULEVARD					
45	253	* PAVEMENT REPAIR, AS PER PLAN	151	SY	
46	254	PAVEMENT PLANING, ASPHALT CONCRETE (2-1/2" FULL WIDTH)	6050	SY	
47	407	TRACKLESS TACK COAT, AS PER PLAN	605	GAL	
48	441	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, (448) (1")	185	CY	
49	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG64-22, (448) (1-1/2")	277	CY	
50	441	ASPHALT CONCRETE MISC.: 1/2" STRESS ABSORBING MEMBRANE INTERLAYER, (SAMI), TYPE 1	6050	SY	
51	441	ASPHALT CONCRETE MISC.: ASPHALT REJUVENATING AGENT	6050	SY	
52	614	MAINTAINING TRAFFIC	1	LS	
53	644	CENTER LINE, 4" SOLID DOUBLE YELLOW	1570	LF	
54	644	CHANNELIZING LINE, 8" SOLID WHITE THERMOPLASTIC	200	LF	
55	644	STOP LINE, 24" THERMOPLASTIC	50	LF	
56	644	DIAGONAL CROSS HATCH MARKING, 24" YELLOW THERMOPLASTIC	210	LF	
57	644	LANE ARROW, 96" WHITE	4	EA	
58	644	WORD ON PAVEMENT, 96" WHITE	2	EA	

*DENOTES CONTINGENCY ITEM - USE ONLY AT THE DIRECTION OF THE ENGINEER



**2024 CITY FOREST PARK STREET PROGRAM
 HAVENSPORT DRIVE, RAPHAEL DRIVE, AND CARILLON BOULEVARD
 CITY OF FOREST PARK, HAMILTON COUNTY, OHIO**

DATE: 4/18/24
 PROJECT: 240070

59	809	STOP-LINE RADAR DETECTION	1	EA		
60	611	FURNISH NEW CURB PLATE, D.G.I. AS PER PLAN	10	EA		
61	611	* FURNISH NEW GRATE, AS PER PLAN	20	EA		
62	653	* TOPSOIL FURNISHED AND PLACED	1	CY		
63	659	* REPAIR SEEDING AND MULCHING	1	SY		
64	659	* WATER	1	M/GAL		
TOTAL CARILLON BLVD						
TOTAL BID (HAVENSPORT + RAPHAEL + CARILLON)						

*DENOTES CONTINGENCY ITEM - USE ONLY AT THE DIRECTION OF THE ENGINEER