

Proposal Items List - Not a Bid Form



2024 CITY FOREST PARK STREET PROGRAM
HAVENSPORT DRIVE, RAPHAEL DRIVE,
& CARILLON BOULEVARD
CITY OF FOREST PARK, HAMILTON COUNTY, OHIO

DATE: **4/18/24**
 PROJECT: **240070**

Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure
HAVENSPORT DRIVE				
1	253	* PAVEMENT REPAIR, AS PER PLAN	141	SY
2	254	PAVEMENT PLANING, ASPHALT CONCRETE (1-1/2" FULL WIDTH)	5650	SY
3	407	TRACKLESS TACK COAT, AS PER PLAN	565	GAL
4	441	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, (448) (1")	173	CY
5	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG64-22, (448) (1-1/2")	254	CY
6	441	ASPHALT CONCRETE MISC.: 1/2" STRESS ABSORBING MEMBRANE INTERLAYER, (SAMI), TYPE 1	5650	SY
7	441	ASPHALT CONCRETE MISC.: ASPHALT REJUVENATING AGENT	5650	SY
8	614	MAINTAINING TRAFFIC	1	LS
9	608	ADA CURB RAMP, AS PER PLAN, INCLUDING REMOVAL OF UNCLASSIFIED MATERIAL AND CURB REPLACEMENT, (SEPARATE PAY ITEM FOR TRUNCATED DOMES)	450	SF
10	608	ADA CURB RAMP, INSTALLING TRUNCATED DOMES	40	SF
11	608	SPOT CURB AND GUTTER REMOVE AND REPLACE	200	LF
12	611	STORM MANHOLE ADJUSTED TO GRADE	2	EA
13	611	DOWNSPOUT CONDUIT, MISC : PVC SCHEDULE 40 PIPE - 3"	1	LF
14	SPL	SANITARY MANHOLE ADJUSTED TO GRADE	6	LF
15	644	STOP LINE, 24" WHITE THERMOPLASTIC	24	LF
16	611	FURNISH NEW CURB PLATE, S.G.I. AS PER PLAN	4	EA
17	611	CATCH BASIN - DOUBLE GRATE INLET - REBUILD TOP 18" USING PRECAST TOP	1	EA
18	611	FURNISH NEW CURB PLATE, D.G.I. AS PER PLAN	6	EA
19	611	FURNISH NEW GRATE, AS PER PLAN	16	EA
20	653	* TOPSOIL FURNISHED AND PLACED	1	CY

*DENOTES CONTINGENCY ITEM - USE ONLY AT THE DIRECTION OF THE ENGINEER



**2024 CITY FOREST PARK STREET PROGRAM
HAVENSPORT DRIVE, RAPHAEL DRIVE,
& CARILLON BOULEVARD
CITY OF FOREST PARK, HAMILTON COUNTY, OHIO**

DATE: 4/18/24
PROJECT: 240070

21	659	* REPAIR SEEDING AND MULCHING	1	SY
22	659	* WATER	1	M/GAL
RAPHAEL DRIVE				
23	253	* PAVEMENT REPAIR, AS PER PLAN	174	SY
24	254	PAVEMENT PLANING, ASPHALT CONCRETE (2-1/2" FULL WIDTH)	6960	SY
25	407	TRACKLESS TACK COAT, AS PER PLAN	696	GAL
26	441	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, (448) (1")	90	CY
27	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG64-22, (448) (1-1/2")	313	CY
28	441	ASPHALT CONCRETE MISC.: 1/2" STRESS ABSORBING MEMBRANE INTERLAYER, (SAMI), TYPE 1	6960	SY
29	441	ASPHALT CONCRETE MISC.: ASPHALT REJUVENATING AGENT	6960	SY
30	SPL	SANITARY MANHOLE ADJUSTED TO GRADE	1	EA
31	611	STORM MANHOLE ADJUSTED TO GRADE	1	EA
32	611	*DOWSNPOUT CONDUIT, MISC : PVC SCHEDULE 40 PIPE, 3"	1	LF
33	608	ADA CURB RAMP, AS PER PLAN, INCLUDING REMOVAL OF UNCLASSIFIED MATERIAL AND CURB REPLACEMENT, (SEPARATE PAY ITEM FOR TRUNCATED DOMES)	1100	SF
34	608	* CURB AND GUTTER REMOVE AND REPLACE	2570	LF
35	608	ADA CURB RAMP, INSTALLING TRUNCATED DOMES	60	SF
36	614	MAINTAINING TRAFFIC	1	LS
37	644	STOP LINE, 24" WHITE THERMOPLASTIC	24	LF
38	611	FURNISH NEW CURB PLATE, S.G.I. AS PER PLAN	7	EA
39	611	CATCH BASIN - SINGLE GRATE INLET - REBUILD TOP 18" USING PRECAST TOP	3	EA
40	611	FURNISH NEW CURB PLATE, D.G.I. AS PER PLAN	6	EA

*DENOTES CONTINGENCY ITEM - USE ONLY AT THE DIRECTION OF THE ENGINEER



**2024 CITY FOREST PARK STREET PROGRAM
HAVENSPORT DRIVE, RAPHAEL DRIVE,
& CARILLON BOULEVARD
CITY OF FOREST PARK, HAMILTON COUNTY, OHIO**

DATE: 4/18/24
PROJECT: 240070

41	611	* FURNISH NEW GRATE, AS PER PLAN	19	EA
42	653	* TOPSOIL FURNISHED AND PLACED	95	CY
43	659	* REPAIR SEEDING AND MULCHING	1	SY
44	659	* WATER	1	M/GAL

CARILLON BOULEVARD

45	253	* PAVEMENT REPAIR, AS PER PLAN	151	SY
46	254	PAVEMENT PLANING, ASPHALT CONCRETE (2-1/2" FULL WIDTH)	6050	SY
47	407	TRACKLESS TACK COAT, AS PER PLAN	605	GAL
48	441	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, (448) (1")	185	CY
49	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG64-22, (448) (1-1/2")	277	CY
50	441	ASPHALT CONCRETE MISC.: 1/2" STRESS ABSORBING MEMBRANE INTERLAYER, (SAMI), TYPE 1	6050	SY
51	441	ASPHALT CONCRETE MISC.: ASPHALT REJUVENATING AGENT	6050	SY
52	614	MAINTAINING TRAFFIC	1	LS
53	644	CENTER LINE, 4" SOLID DOUBLE YELLOW	1570	LF
54	644	CHANNELIZING LINE, 8" SOLID WHITE THERMOPLASTIC	200	LF
55	644	STOP LINE, 24" THERMOPLASTIC	50	LF
56	644	DIAGONAL CROSS HATCH MARKING, 24" YELLOW THERMOPLASTIC	210	LF
57	644	LANE ARROW, 96" WHITE	4	EA
58	644	WORD ON PAVEMENT, 96" WHITE	2	EA
59	809	STOP-LINE RADAR DETECTION	1	EA
60	611	FURNISH NEW CURB PLATE, D.G.I. AS PER PLAN	10	EA
61	611	* FURNISH NEW GRATE, AS PER PLAN	20	EA
62	653	* TOPSOIL FURNISHED AND PLACED	1	CY



2024 CITY FOREST PARK STREET PROGRAM
HAVENSPORT DRIVE, RAPHAEL DRIVE,
& CARILLON BOULEVARD
CITY OF FOREST PARK, HAMILTON COUNTY, OHIO

DATE: **4/18/24**
 PROJECT: **240070**

63	659	* REPAIR SEEDING AND MULCHING	1	SY
64	659	* WATER	1	M/GAL