

CITY OF FOREST PARK W. SHARON ROAD IMPROVEMENTS

DATE: 4/18/24 PROJECT: **241095** CITY OF FOREST PARK, HAMILTON COUNTY, OHIO

Item	Spec.	Item	Estimated	Unit of				
No.	No.		Quantity	Measure				
W. SHARON ROAD								
1	251	* PARTIAL DEPTH PAVEMENT REPAIR	390	SY				
2	253	* FULL DEPTH PAVEMENT REPAIR	700	SY				
3	254	PAVEMENT PLANING, ASPHALT CONCRETE (2-1/2" FULL WIDTH)	21800	SY				
4	407	TRACKLESS TACK COAT, 0.06 GAL/SY	1308	GAL				
5	441	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, (448) (1")	670	CY				
6	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG64-22, (448) (1-1/2")	1000	CY				
7	441	ASPHALT CONCRETE MISC.: STRESS ABSORBING MEMBRANE INTERLAYER, (SAMI), TYPE 1	21800	SY				
8	441	ASPHALT CONCRETE MISC.: ASPHALT REJUVENATING AGENT	21800	SY				
9	614	MAINTAINING TRAFFIC	1	LS				
10	630	* REMOVAL OF GROUND MOUNTED SIGN AND SUPPORT AND REERECTION	6	EA				
11	SPL	* ADJUST SANITARY MH TO GRADE	1	EA				
12	SPL	* ADJUST TELEPHONE MH TO GRADE	1	EA				
13	SPL	* ADJUST ELECTRIC MH TO GRADE	6	EA				
14	644	EDGE LINE, 4" WHITE	12800	LF				



CITY OF FOREST PARK W. SHARON ROAD IMPROVEMENTS

W. SHARON ROAD IMPROVEMENTS DATE: 4/18/24
CITY OF FOREST PARK, HAMILTON COUNTY, OHIO PROJECT: 241095

Item	Spec.	Item	Estimated	Unit of
No.	No.		Quantity	Measure
15	644	CENTERLINE, 4" DOUBLE YELLOW	12350	LF
16	644	CHANNELIZING LINE, 8" WHITE THERMOPLASTIC	232	LF
17	644	STOP LINE, 24" WHITE THERMOPLASTIC	54	LF
18	632	POWERHEAD DETECTOR LOOP	2	EA
19	632	LOOP DETECTOR TIE IN	2	EA
20	644	CROSSWALK LINE, 12" WHITE THERMOPLASTIC	124	LF
20	044	CNOSSWALK LINE, 12 WHITE THEKINOPLASTIC	124	LF
21	621	RAISED PAVEMENT MARKERS	93	EA
22	644	ARROWS ON PAVEMENT, INCLUDES COMBO ARROWS	8	EA