

Proposal Items List - Not a Bid Form



PROJECT: HANOVER PLACE RECONSTRUCTION

CITY OF FORT THOMAS, KY

PROJECT #241381

ADVERTISEMENT DATE: 04/18/2024

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
		BASE BID (HANOVER PLACE)		
1	110	MOBILIZATION	1	LS
2	112	MAINTENANCE OF TRAFFIC	1	LS
3	202	CLEARING AND GRUBBING (INCLUDES THE REMOVAL AND REINSTALLATION OF SIGNS, MAILBOXES, AND FENCING)	1	LS
4	203	REMOVE EXISTING ROADWAY INCLUDING EXISTING CURB	2,300	SY
5	203	REMOVE EXISTING STORM STRUCTURE	2	EA
6	204	EXCAVATION FOR GRANULAR BASE	2,300	SY
7	207	SUBGRADE RESHAPING AND COMPACTING	2,300	SY
8	212/213	EROSION CONTROL AND WATER POLLUTION CONTROL	1	LS
9	SPL	YARD RESTORATION (4" TOPSOIL, SEED & MULCH)	350	SY
10	214	WOVEN GEOTEXTILE FABRIC, MIRAFI 600X OR EQUIVALENT	2,300	SY
11	SPL*	GEOGRID (TENSAR BX 1200 OR EQUIVALENT) REINFORCEMENT FOR SUBGRADE REPAIR *	250	SY
12	302/SPL*	CRUSHED STONE BASE (LESS THAN 3% FINES) FOR SUBGRADE REPAIR (INCLUDES EXCAVATION AND DISPOSAL OF UNSUITABLE MATERIAL) *	100	CY
13	302	4" CRUSHED STONE AGGREGATE BASE	2,300	SY



PROJECT: HANOVER PLACE RECONSTRUCTION

CITY OF FORT THOMAS, KY

PROJECT #241381

ADVERTISEMENT DATE: 04/18/2024

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
14	505	8" CONCRETE PAVEMENT WITH INTEGRAL ROLLED CURB	2,300	SY
15	505	CONCRETE DRIVE APRON REPLACEMENT (6")	1,575	SF
16	505	ADA CURB RAMP (INCLUDES REMOVAL OF EXISTING CONCRETE, NEW CONCRETE, AND DETECTABLE WARNING)	3	EA
17	701	INSTALL 12" DIAMETER STORM SEWER (N-12)	25	LF
18	701	INSTALL 18" DIAMETER STORM SEWER (N-12)	10	LF
19	704	4" RIGID PVC UNDERDRAIN, AS PER PLAN	1,350	LF
20	710	INSTALL NEW STANDARD DOUBLE GRATE CURB INLET	1	EA
21	710	INSTALL NEW DOUBLE GRATE INLET WITH MOUNTABLE GRATE	1	EA
22	SPL	ADJUST WATER VALVE TO GRADE	1	EA