



REV.	DESCRIPTION	DATE

PERRY JOINT ECONOMIC DEVELOPMENT DISTRICT
MIDWEST MATERIALS SANITARY
SEWAGE IMPROVEMENT
 PERRY, OHIO
 LAKE COUNTY
 PLAN VIEW
 F.M. PLAN STA 11+00 TO STA 16+54

PROJECT NO.	170415
DISCIPLINE	CIVIL
SHEET NAME	PLAN
SHEET	06
OF	22



- NOTES:
1. TONE AND FIELD LOCATE THE EXISTING 2" WATERLINE PRIOR TO STAKING THE NEW 2" HDPE FORCE MAIN. MAINTAIN A MINIMUM OF 10' HORIZONTAL SEPARATION BETWEEN THE EXISTING 2" WATERLINE AND NEW 2" FORCE MAIN.
 2. CONTRACTOR TO EXTEND CLEARING TO A MINIMUM OF 5' BEYOND FORCE MAIN.
 3. THE NUMBER AND LOCATION OF SERVICE LATERALS EXISTING IN THE BAR BUILDING HAS NOT BEEN DETERMINED. THE CONTRACTOR SHALL BE RESPONSIBLE FOR DETERMINING THE LOCATION WHERE THE EXISTING SERVICE LATERAL(S) EXIT THE BAR BUILDING. NEW SERVICE LATERALS SHALL BE INSTALLED TO THE BUILDINGS IN ACCORDANCE WITH LCDU R & R.