2020 NEIGHBORHOOD INVESTMENT PROGRAM
CITY OF HERMITAGE
PROJECT NO.: 18030206

Ref No.	PennDOT Pub 408 Section	Description	Total Quan.	Unit
1		BONDS AND INSURANCES	1	LS
2	201	CLEARING AND GRUBBING	1	LS
3	206	EMBANKMENT, AS PER PLAN	20	CY
4	212	GEOTEXTILE FABRIC, CL IV, TYPE A	395	SY
5	350	NO. 2A LIMESTONE SUBBASE MATERIAL, COMPACTED, 100% STANDARD PROCTOR, 12" DEPTH	445	SY
6	350	NO. 2A LIMESTONE AGGREGATE, 4" DEPTH	102	SY
7	409 (HMA) 411 (WMA)	SUPERPAVE ASPHALT MIXTURE DESIGN, HMA OR WMA WEARING COURSE, PG 64-22, 0.3 TO <3 MILLION ESALS, 9.5 mm MIX, SRL-H, 1-1/2" DEPTH, AS PER PLAN	3932	SY
8	409 (HMA) 411 (WMA)	SUPERPAVE ASPHALT MIXTURE DESIGN (MAX 15% RAP), HMA OR WMA BINDER COURSE, PG 64-22, 0.3 TO <3 MILLION ESALS, 19 mm MIX, 3-1/2" DEPTH, AS PER PLAN	370	SY
9	409 (HMA) 411 (WMA)	SUPERPAVE ASPHALT MIXTURE DESIGN (MAX 15% RAP), HMA OR WMA BINDER COURSE, PG 64-22, 0.3 TO <3 MILLION ESALS, 19 mm MIX, 2-1/2" DEPTH, AS PER PLAN	3466	SY
10	409 (HMA) 411 (WMA)	DRIVEWAY REPLACEMENT, ASPHALT, AS PER PLAN	489	SY
11	491	PAVEMENT PLANING, BITUMINOUS PAVEMENT SURFACE, 3" AVG. DEPTH, MILLED MATERIAL RETAINED BY CITY (DELIVERED TO STOCKPILE), AS PER PLAN	3274	SY
12		FULL-DEPTH PAVEMENT REPAIR, AS PER PLAN	100	SY
13		DRIVEWAY REPLACEMENT, PLAIN CEMENT CONCRETE, 5" DEPTH, AS PER PLAN	152	SY

2020 NEIGHBORHOOD INVESTMENT PROGRAM
CITY OF HERMITAGE
PROJECT NO.: 18030206

Ref No.	PennDOT Pub 408 Section	Description	Total Quan.	Unit
14	601	12" DIAMETER HDPE STORM SEWER, AS PER PLAN	1975	LF
15	601	15" DIAMETER HDPE STORM SEWER, AS PER PLAN	415	LF
16	601	18" DIAMETER HDPE STORM SEWER, AS PER PLAN	245	LF
17	605	2' x 4' TYPE C INLET, AS PER PLAN	8	EA
18	605	2' x 2' TYPE M INLET, AS PER PLAN	23	EA
19	606	ADJUST VALVE BOXES TO GRADE	1	EA
20	606	ADJUST MANHOLES TO GRADE	5	EA
21	608	MOBILIZATION, AS PER PLAN	1	LS
22	630	PLAIN CEMENT CONCRETE CURB, 6" REVEAL, AS PER PLAN	1555	LF
23	676	CEMENT CONCRETE SIDEWALKS, 4" THICK	100	SY
24	695	CURB RAMP WITH DETECTABLE WARNING SURFACE	1	EA
25	800	EROSION AND SEDIMENTATION CONTROL, AS PER PLAN	1	LS
26	802	TOPSOIL FURNISHED AND PLACED	280	CY

2020 NEIGHBORHOOD INVESTMENT PROGRAM
CITY OF HERMITAGE
PROJECT NO.: 18030206

Ref No.	PennDOT Pub 408 Section	Description	Total Quan.	Unit
27	804	SEEDING, FORMULA B	2440	SY
28	805	MULCHING SEEDED AREAS	2440	SY
29	901 PUB 213	MAINTENANCE AND PROTECTION OF TRAFFIC DURING CONSTRUCTION, PER PENNDOT PUB 213	1	LS
30	931	POST MOUNTED SIGNS, TYPE B, AS PER PLAN	1	LS