

---

***SECTION 7***  
***SPECIFIC PROJECT REQUIREMENTS***

---

## SPECIFIC PROJECT REQUIREMENTS

### 1 - CONTACT DURING BIDDING

- 1.1 All questions during bidding should be addressed to Jeffrey S. Smith, P.E., P.L.S., who can be reached at CT Consultants, Inc., 3735 East State Street, Hermitage, Pennsylvania 16148 at 724.734.2306.

### 2 - INSURANCE

- 2.1 Section SC-5.04(D) of the Supplementary Conditions shall be deleted and no "all risk builders risk" or "installation floater" insurance need be purchased by the Contractor.

### 3 - WORKING HOURS

- 3.1 No work shall be performed between the hours of 7:30 PM and 7:30 AM nor on Saturday, Sunday, or legal Holidays, without written permission of the Owner.

### 4 - PROJECT COMPLETION

- 4.1 All work including restoration and clean-up shall be completed no later than the contract completion date. Failure to complete all work within the allotted time will result in assessment of liquidated damages. Upon completion of all work and written notification of same by the Contractor, the Engineer and Owner will compile a punch list. The punch list will be sent to the Contractor. All punch list work shall be completed to the satisfaction of the Engineer and the Owner within 14 days after receipt of the punch list. Failure to complete the punch list work within the allotted time will result in assessment of liquidated damages.

### 5 - ASPHALT GRINDINGS

- 5.1 All grindings shall remain the property of the City.

### 6 - SEQUENCE OF CONSTRUCTION

- 6.1 To coordinate the completion of the work and properly assess the interrelation of unit processes, the General Contractor shall prepare a proposed staging plan for all demolition and construction on the project. The Staging Plan shall be submitted for review by Engineer and Owner prior to the commencement of construction operations at these facilities.
- 6.2 This outline is for reference only and the requirements of staffing, means and methods of demolition and construction, and all coordination with specific trades or disciplines is the sole responsibility of the General Contractor.

- a. Install standard filter fabric fence and/or compost filter sock and trap in accordance with the standard details. Soil stockpile areas shall also be protected with silt fence and/or compost filter sock.
- b. Perform clearing, grubbing, and stripping of top soil, and demo to the extent necessary to complete the individual task.
- c. Remove existing storm sewer at the locations specified in the plans and perform installation of new storm sewer.
- d. Remove existing curb and perform installation of new curb at locations specified in the plans.
- e. Seed all disturbed areas which will not be paved as soon as the finished grade has been established. Seed and mulch in accordance with the drawings and project manual.
- f. Perform the driveway adjustments.
- g. Perform the pavement reconstruction and resurfacing.
- h. Install topsoil on all disturbed surfaces which will not be paved with permanent paving material. In paved areas, temporarily stabilize with crushed stone.
- i. Install new pavement markings as shown in the plans.

## 7 - TRAFFIC CONTROL

- 7.1 Before any work may begin in the right-of-way, a Traffic Control Plan must be submitted and approved by the owner. Required traffic control devices must be erected and maintained by the contractor and will comply to the State of Pennsylvania Control for Construction and Maintenance Regulations. Temporary barricades, barrels, lights, and all detour traffic control shall be implemented per PennDOT Publication 213 and the Federal Highway Administration Manual on Uniform Traffic Control Devices (MUTCD).