## SECTION 011100 - SUMMARY OF WORK

## PART 1 - GENERAL

#### 1.1 SECTION INCLUDES

- A. Project Scope and Location
- B. Owner Supplied Products
- C. Contractor Use of Site
- D. Existing Services, Structures and Underground Facilities
- E. Protection of Work and Improvements
- F. Schedules and Work Sequence
- G. Owner Occupancy

# 1.2 PROJECT SCOPE AND LOCATION

- A. The project generally consists of the installation of a 300kW emergency standby diesel generator, a 600A service entrance rated automatic transfer switch and related appurtenances.
- B. The project site is located at 1092 John Glenn Highway (US40), New Concord, Muskingum County, Ohio.
- C. Contractor shall provide all items, articles, materials, operations or methods mentioned or scheduled on the Drawings or herein specified: including all labor, supervision, equipment, incidentals, taxes and permits necessary to complete the Work as described within the Contract Documents. Contractor shall install all items provided by Owner as mentioned or scheduled on the Drawings or herein specified.

### 1.3 OWNER SUPPLIED PRODUCTS

A. None

### 1.4 CONTRACTOR USE OF SITE

- A. Access to Site: Limited to Contractor.
- B. Construction Operations: Easements were not obtained for this project. Contractor shall contain operations to within the rights-of-way or lands upon which the work is to be performed.

#### 1.5 EXISTING SERVICES, STRUCTURES AND UNDERGROUND FACILITIES

- A. Should unchartered or incorrectly charted piping or other utilities be encountered during installation, notify Owner and consult with utility owner immediately for directions.
- B. Cooperate with Owner and utility companies in keeping respective services and facilities in operation and repair any damaged utilities to the satisfaction of the utility owner.
- C. Contractor shall not interrupt existing utilities serving facilities occupied and used by the Owner or others, except when permitted in writing by the Owner.
- D. Any accidental interruption of services shall be repaired immediately, including provision of temporary facilities until permanent repairs can be made.
- E. Existing underground facilities may consist of gas lines, water lines, storm sewers, and buried telephone and electric cables. The utilities shown on the Drawings are based on data furnished by the utility companies listed in the Drawings and on field observations and are believed to be reasonably accurate.
- F. Contractor shall notify the Ohio Utilities Protection Service (OUPS), (1-800-362-2764), the Oil and Gas Producer's Underground Protection Service (OGPUPS), ( (1-800-925-0988), and any other non-OUPS/non-OGPUPS utility a minimum of 48 hours prior to commencing work on the project to coordinate the marking of utilities in the field. Based on information made available by the various utility companies, the companies shown in the Drawings have facilities in the area.
- G. Contractor shall proceed with caution in the excavation and preparation of the Site so the exact location of structures and Underground Facilities can be determined. Contractor shall include in Contract Price any costs for temporary or permanent relocations of such structures and Underground Facilities required to complete the Work unless specifically indicated otherwise in the Specifications.
- H. Contractor shall keep an accurate and complete record of all such structures and Underground Facilities encountered and shall provide the Owner a copy of this record. The record shall include a description of the item encountered, opinion as to condition, and adequate measurements and depths so that the item can be located in the future.
- I. Contractor shall inspect all structures and Underground Facilities for condition and soundness. Unsound conditions shall be reported to the structure or facility owner immediately after exposing. Contractor shall not proceed with the work until the structure or facility owner has been notified. Owner shall then be given time to inspect and correct, if required, the structure or Underground Facility. Contractor shall make claim under the provisions of Articles 11 and 12 of the General Conditions should the Contractor feel a price or time adjustment is justified.

- J. Any additional costs incurred because of the failure of the Contractor to report the condition of any and all existing structure or Underground Facility encountered shall be paid by the Contractor.
- K. Whenever the Engineer feels it is necessary to explore and excavate to determine the location of existing structures and Underground Facilities, the Contractor shall make explorations and excavations for such purposes. If Contractor is required to perform additional work in making the explorations and excavations, extra compensation will be allowed as provided for in the General Conditions.

### 1.6 PROTECTION OF WORK AND IMPROVEMENTS

- A. Contractor shall protect the property of the Owner, existing improvements, and the Work installed by the Contractor and others from abuse, damage, dust, debris, and other objectionable materials resulting from construction activities.
- B. Contractor shall provide suitable covers, partitions, or other dust and fume containment devices to suit construction operations.
- C. Contractor shall keep property, existing improvements and the Work, including structures, mains, fittings and accessories free from dirt and foreign matter at all times.
- D. Contractor shall provide temporary plugging of openings, holes and pipe ends that are existing or that the Contractor has installed.
- E. Property, improvements and Work damaged by Contractor shall be repaired or replaced by Contractor to the satisfaction of the Owner.

### 1.7 SCHEDULES AND WORK SEQUENCE

A. Contractor shall provide schedules for performance of the Work in accordance with the provision set forth within the General Conditions. The schedule(s) shall detail all phases of construction to completion with milestones and associated dates. The schedule(s) shall be presented in a format acceptable to the Owner and Engineer.

## 1.8 OWNER OCCUPANCY

A. Owner shall have access to site throughout the term of the project.

### PART 2 - PRODUCTS

Not Applicable.

### PART 3 - EXECUTION

Not Applicable.

# END OF SECTION 011100