CONTRACT A:
ALL SITE WORK INCLUDING CONCRETE AND ASPHALT PAVEMENT, WATER MAIN RELOCATION, WATER & FIRE SERVICE LINES, SANITARY SEWERS, STORM SEWERS, GRADING, SIDEWALKS, CURBS, CURB RAMPS, SIGNAGE, PAVEMENT MARKINGS, LANDSCAPING, IRRIGATION, ETC.

CONTRACT B:
BUILDING AND SURROUNDING CONCRETE, INCLUDING CURB RAMPS TO BACK OF CURB.

CONTRACT B:
6" BOLLARD (SEE DETAIL)

CONTRACT B:
BUILDING AND SURROUNDING CONC. TO BACK OF CURB

FF: 769.84

CURB RADII ARE BACK OF CURB (TYP.)

PAINT EX. LOT

MODIFIED ODOT TYPE 8 CURB (SEE DETAIL & GRADING)

PR. CONC. WALK CONTINUES EAST ALONG EX. LOT END AT CROSSWALK LOCATION. PROVIDE DETECTABLE WARNING DOMES 6' x 2' IN LINE WITH EXISTING DOMES ACROSS DRIVE.

SEE ABOVE

END OF PROPOSED WALK

SEE DETAIL BELOW

PR. JERSEY BARRIERS

CATV BOX
SEE ELECTRICAL FOR RELOCATION

PAVEMENT MARKINGS AS SHOWN (TYP.)

BUS ONLY

EX. SAN MH
RIM: 774.00
8" INV N&S: 763.50
6" INV W: 763.80

WILLOUGHBY AND KIRTLAND

BAR SCALE
20' 10' 0' 20'
SCALE: 1"= 20'

LEGEND:

- 01 9" CONCRETE PAVEMENT - CONTRACT A (*SEE DETAIL*)
- 02 HEAVY DUTY ASPHALT - CONTRACT A (*SEE DETAIL*)
- 03 CONTRACT B: BUILDING AND SURROUNDING CONCRETE
- 04 TYPE 2A - 6 INCH CURB (*SEE DETAIL*)
- 05 TYPE 6 - 6 INCH VERTICAL CURB (*SEE DETAIL*)
- 07 6" CONCRETE WALK WITH INTEGRATED CURB. (*SEE DETAIL*)
- 08 6" CONCRETE WALK (*SEE DETAIL*)
- 09 CURB RAMP
- 10 CROSSWALK
- 11 STOP BAR
- 12 PAINTED ISLAND
- 13 SAWCUT FULL DEPTH
- A DO NOT ENTER SIGN - [R5-1]
- B STOP SIGN - [R1-1]
- C CROSSWALK SIGN - [W11-2]
- D ONE WAY SIGN - [R6-2L]
- E BUS LANE SIGN - [R3-5gP]
- F AUTHORIZED VEHICLE ONLY - [R5-11]

STATE OF OHIO
LENE C. HILL
66017
REGISTERED PROFESSIONAL ENGINEER

your trusted advisor
consultants
engineers
architects
planners

NO	REVISION	DATE
1	REBID REVISION	8/05/2019

ISSUED FOR: CD
ISSUE DATE: 8/5/2019
SCALE: AS SHOWN
DESIGNED BY: LCH / GMS
DRAWN BY: GMS
CHECKED BY: LCH

LAKELAND TRANSFER CENTER
LAKELAND COMMUNITY COLLEGE
7601 CLOCKTOWER DR., KIRTLAND, OH 44094

SITE LAYOUT

PROJECT NO. 18050002
DISCIPLINE CIVIL
SHEET NAME C_03
SHEET 8 OF 55

H:\2018\18050002\DWG\SHEETS\C_18050002 - SITE LAYOUT.DWG - C_03 - 8/5/2019 1:18:37 PM - GEORGE STEVENS