

POINT TABLE				
POINT #	T/C ELEVATION	NORTHING	EASTING	DESCRIPTION
1	771.60	295017.72	1678836.89	MH 1
2	769.20	295417.54	1678825.11	MH 2
3	767.85	295817.20	1678821.32	MH 3
4	765.64	296174.02	1678824.60	MH 4
5	767.10	296181.95	1678637.95	MH 5
6	778.40	296194.77	1678336.25	MH 6
7	780.15	296237.88	1678242.41	MH 7
8	780.90	296478.13	1678020.48	MH 8
9	785.00	296631.57	1677880.02	MH 9
10	787.30	296895.93	1677644.38	MH 10
11	774.70	297089.82	1677876.52	MH 11
12	775.60	297104.06	1677961.80	MH 12
13	780.76	296958.16	1678178.18	MH 13
14	781.70	296679.11	1678241.96	MH 14
15	777.85	296816.70	1678393.93	MH 15
16	765.53	296386.61	1678649.74	MH 16
17	764.50	296627.91	1678663.65	MH 17
18	768.45	296729.94	1678524.34	MH 18
19	780.00	294818.15	1678634.96	CRACKEL LLS
20	799.20	294469.09	1678609.30	AIR RELEASE VALVE
21	814.50	293735.41	1678536.88	AIR RELEASE W/ C/O
22	0.00	291290.99	1678054.00	FM VAULT
23	855.75	291353.52	1677733.66	EX MH

SANITARY SERVICE SCHEDULE TABLE									
LOT	FGE	INVERT AT END OF SERVICE	SERVICE LENGTH	SLOPE	SERVICE INVERT AT MAIN	ALIGNMENT	WYE STATION	MAIN INVERT AT WYE	RISER HEIGHT
115 MARY LN.	783.63	780.00	180	0.0208	776.25	1	0+28.00	767.72	8.53
110 MARY LN.	776.00	773.00	78	0.0208	771.38	1	0+41.12	769.59	1.78
85 MARY LN.	783.94	780.00	114	0.0208	777.63	1	1+33.92	768.66	8.97
70 MARY LN.	776.50	772.50	96	0.0208	770.50	1	2+23.03	767.77	2.73
43 MARY LN.	779.12	775.00	84	0.0208	773.25	1	2+27.25	767.73	5.52
50 MARY LN.	775.00	771.00	108	0.0208	768.75	1	3+33.22	766.99	1.76
30 MARY LN.	778.37	776.00	63	0.0208	774.69	1	4+35.37	766.49	8.20
60 PAGE SCHOOL RD.	780.89	776.00	87	0.0208	774.19	1	4+85.70	766.29	7.90
10 MARY LN.	780.33	776.00	95	0.0208	774.02	1	4+98.28	766.24	7.78
100 PAGE SCHOOL RD.	787.59	783.00	148	0.0208	779.92	1	8+91.25	765.05	14.87
23 MICHAEL LN.	783.89	779.00	148	0.0208	775.92	1	11+11.48	764.52	11.40
242 PAGE SCHOOL RD.	776.14	772.00	158	0.0208	768.71	1	17+63.39	761.94	6.77
140 MARY LN.	775.00	771.00	131	0.0208	768.27	2	0+0.00	768.00	0.27
135 MARY LN.	784.29	780.00	51	0.0208	778.94	2	1+51.76	767.70	11.24
40 MICHAEL LN.	777.65	773.00	159	0.0208	769.69	2	1+95.63	767.61	2.08
188 PAGE SCHOOL RD.	777.60	773.00	138	0.0208	770.13	2	3+45.80	767.21	2.91
175 MARY LN.	773.45	769.00	110	0.0208	766.71	3	0+0.00	757.97	8.74
180 MARY LN.	766.50	762.00	138	0.0208	759.13	3	0+45.20	756.81	2.32
210 MARY LN.	762.75	761.00	161	0.0208	757.65	3	0+64.74	756.77	0.88
203 MARY LN.	770.58	764.00	87	0.0208	762.19	3	2+64.57	756.27	5.92
250 MARY LN.	775.00	770.00	101	0.0208	767.90	3	3+13.27	756.17	11.73
272 PAGE SCHOOL RD.	770.61	764.00	101	0.0208	761.90	3	4+74.37	755.75	6.15
270 MARY LN.	766.23	762.00	119	0.0208	759.52	3	5+13.17	755.67	3.85

SANITARY NOTES:

- ALL SANITARY LATERALS SHALL BE AT 2.08% MINIMUM SLOPE UNLESS OTHERWISE NOTED.
- A MINIMUM OF 1.5' (VERTICALLY) AND 10' (HORIZONTALLY) SHALL SEPARATE THE SANITARY SERVICES FROM THE STORM LINES AND WATER MAINS.
- NO UTILITY SHALL BE CLOSER THAN 10 FEET ON EITHER SIDE OF THE SANITARY SEWER MAIN.
- WYES INSTALLED AT MORE THAN 45 DEGREES FROM HORIZONTAL SHALL BE CONCRETE ENCASED.
- REFER TO SANITARY SERVICE SCHEDULE TABLE, THIS SHEET FOR LATERAL INFORMATION.
- EX. UTILITY ELEVATIONS ARE APPROXIMATE. CONTRACTOR TO FIELD VERIFY PRIOR TO CONSTRUCTION.



ISSUED FOR:	EPA REVIEW	NO	DATE	
ISSUE DATE:	1/17/20			
SCALE:	AS SHOWN			
DESIGNED BY:	ISC			
DRAWN BY:	ISC			
CHECKED BY:	KB			

**CRACKEL SUBDIVISION
SANITARY SEWER - PHASE 3
- WEST UNION, OHIO -**

LATERAL AND MH TABLES

PROJECT NO.	190123
DISCIPLINE	CIVIL
SHEET NAME	FM-PNP6
SHEET	OF
18B	25