

**Proposal to Village of West Union
For Crackel Subdivision Sanitary Sewer - Phase 3
Base Bid
Project No. 190123**

REF. NO.	DESCRIPTION	QTY.	MEASURE UNITS	UNIT PRICE LABOR	UNIT PRICE MATERIAL	TOTAL UNIT PRICE	ITEM TOTAL
1	(202) SEPTIC SYSTEM ABANDONED, AS PER PLAN	23.00	EACH	\$ _____	\$ _____	\$ _____	\$ _____
2	(253) PAVEMENT RESTORATION ALLOWANCE	1.00	LS	\$ ----	\$ ----	\$ ----	\$ 100,000.00
3	(SPC) ASPHALT DRIVE REPLACEMENT, AS PER PLAN	375.00	SY	\$ _____	\$ _____	\$ _____	\$ _____
4	(SPC) STONE DRIVE REPLACEMENT, AS PER PLAN	150.00	SY	\$ _____	\$ _____	\$ _____	\$ _____
5	(SPC) ACCESS ROAD, AS PER PLAN	1,200.00	SY	\$ _____	\$ _____	\$ _____	\$ _____
6	(441) ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22, AS PER PLAN	200.00	CY	\$ _____	\$ _____	\$ _____	\$ _____
7	(441) ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, (448), AS PER PLAN	325.00	CY	\$ _____	\$ _____	\$ _____	\$ _____
8	(603) 8 INCH SANITARY SEWER, PVC, AS PER PLAN	650.00	FT	\$ _____	\$ _____	\$ _____	\$ _____
9	(603) 12 INCH SANITARY SEWER, PVC, AS PER PLAN	3,767.00	FT	\$ _____	\$ _____	\$ _____	\$ _____
10	(604) MANHOLE, AS PER PLAN	17.00	EACH	\$ _____	\$ _____	\$ _____	\$ _____
11	(611) 6 INCH SANITARY SEWER LATERAL, AS PER PLAN	3,300.00	FT	\$ _____	\$ _____	\$ _____	\$ _____
12	(611) 6 INCH SANITARY SEWER LATERAL RECONNECTIONS, AS PER PLAN	23.00	EACH	\$ _____	\$ _____	\$ _____	\$ _____
13	(SPC) 12 INCH CONDUIT, HORIZONTAL DIRECTIONAL DRILLING WITHOUT CASING, HDPE, AS PER PLAN	120.00	FT	\$ _____	\$ _____	\$ _____	\$ _____
14	(611) UTILITY VAULT, PRECAST CONCRETE	1.00	EACH	\$ _____	\$ _____	\$ _____	\$ _____
15	(614) MAINTAINING TRAFFIC, AS PER PLAN	1.00	LS	\$ _____	\$ _____	\$ _____	\$ _____
16	(623) CONSTRUCTION LAYOUT STAKES AND SURVEYING	1.00	LS	\$ _____	\$ _____	\$ _____	\$ _____
17	(624) MOBILIZATION	1.00	LS	\$ _____	\$ _____	\$ _____	\$ _____
18	(625) POWER SERVICE ALLOWANCE, AS PER PLAN	1.00	LS	\$ ----	\$ ----	\$ ----	\$ 50,000.00
19	(659) SEEDING AND MULCHING	4,658.00	SY	\$ _____	\$ _____	\$ _____	\$ _____
20	(680) SPECIAL - LIFT STATION REHABILITATION	1.00	EACH	\$ _____	\$ _____	\$ _____	\$ _____
21	(680) PUMP STATION NO. 1, AS PER PLAN	1.00	LS	\$ _____	\$ _____	\$ _____	\$ _____
22	(680) PUMP STATION NO. 2, AS PER PLAN	1.00	LS	\$ _____	\$ _____	\$ _____	\$ _____

BF.8B

**Proposal to Village of West Union
For Crackel Subdivision Sanitary Sewer - Phase 3
Base Bid
Project No. 190123**

REF. NO.	DESCRIPTION	QTY.	MEASURE UNITS	UNIT PRICE LABOR	UNIT PRICE MATERIAL	TOTAL UNIT PRICE	ITEM TOTAL
23	(680) FORCE MAIN CONNECTION TO SANITARY MANHOLE, AS PER PLAN	2.00	EACH	\$ _____	\$ _____	\$ _____	\$ _____
24	(680) 6 INCH FORCE MAIN, AS PER PLAN	4,453.00	FT	\$ _____	\$ _____	\$ _____	\$ _____
25	(680) AIR RELEASE VALVE AND VAULT, AS PER PLAN	1.00	EACH	\$ _____	\$ _____	\$ _____	\$ _____
26	(680) AIR RELEASE VALVE AND VAULT WITH CLEANOUTS, AS PER PLAN	1.00	EACH	\$ _____	\$ _____	\$ _____	\$ _____
27	(832) STORM WATER POLLUTION PREVENTION PLAN, AS PER PLAN	1.00	LS	\$ _____	\$ _____	\$ _____	\$ _____
28	(832) EROSION CONTROL, AS PER PLAN	30,000.00	EACH	\$ ----	\$ ----	\$1.00	\$ 30,000.00
				INFORMAL TOTAL BID \$ _____			

BF.9B