

NOT A BID FORM



CITY OF SOUTHGATE 2019 STREET PROGRAM


PROJECT No. 190505

BID TAB


BID DATE: 8/1/2019

ITEM NO.	SPEC. NO.		Estimated Quantity	Unit of Measure
		FORT BEECH DRIVE / WINTER VIEW LANE		
1	110	MOBILIZATION	1	LS
2	112	MAINTENANCE OF TRAFFIC	1	LS
3	202	CLEARING & GRUBBING (See note on Plan Sheet No. 1)	1	LS
4	203	REMOVE EXISTING PAVEMENT	685	SY
5	203	REMOVE CONCRETE WALK	170	SF
6	204	EXCAVATION FOR GRANULAR BASE	270	CY
7	207	SUBGRADE RESHAPING & COMPACTING	685	SY
8	212/213	EROSION & WATER POLLUTION CONTROL	1	LS
9	214	WOVEN GEOTEXTILE, MIRAFI 600X OR EQUIVALENT	685	SY
10	SPL	GEOGRID (TENSAR BX-1200 OR APPROVED EQUIV)	685	SY
11	302/SPL*	CRUSHED STONE BASE (LESS THAN 7% FINES) FOR SUBGRADE REPAIR (INCLUDES EXCAVATION & DISPOSAL OF UNSUITABLE MATERIAL)*	50	CY


NOT A BID FORM

 CITY OF SOUTHGATE 2019 STREET PROGRAM					PROJECT No. 190505
BID TAB					BID DATE: 8/1/2019
12	302	14" CRUSHED STONE BASE (LESS THAN 7% FINES)	270	CY	
13	402/403	ASPHALT PAVEMENT BASE COURSE (5")	95	CY	
14	402/403	ASPHALT PAVEMENT LEVELING COURSE (1" AVG. DEPTH)	35	CY	
15	402/403	ASPHALT PAVEMENT SURFACE COURSE (1-1/2") w/ ARAMID FIBER REINFORCEMENT - ACE FIBER OR EQUIVALENT)	50	CY	
16	406	TACK COAT	100	GAL	
17	408	PAVEMENT MILLING (2.5" TYP.)	500	SY	
18	505	CONCRETE WALK	170	SF	
19	505	INSTALL ADA CURB RAMP	2	EA	
20	506	CONCRETE ROLLED CURB REPLACEMENT	50	LF	
21	SPL *	FULL DEPTH PAVEMENT REPAIR AS PER PLAN - CONTINGENCY	200	SY	
22	704	4" RIGID PVC UNDERDRAIN - INCLUDES TRANSVERSE DRAINS	620	LF	
23	704	6" RIGID PVC OUTLET COLLECTOR LINE	18	LF	
24	SPL	CONNECT EXISTING SUMP PUMP OUTLET PIPE TO PROPOSED COLLECTOR LINE	1	EA	

NOT A BID FORM

 CITY OF SOUTHGATE 2019 STREET PROGRAM					PROJECT No. 190505
BID TAB					BID DATE: 8/1/2019
25	SPL	SANITARY SEWER MANHOLE ADJUSTED TO GRADE PER SD1 REGULATIONS	1	EA	
26	SPL	STORM SEWER MANHOLE ADJUSTED TO GRADE PER SD1 REGULATIONS	1	EA	
27	713	24" STOP BAR, PAINT	33	LF	
NORTH STREET					
28	110	MOBILIZATION	1	LS	
29	112	MAINTENANCE OF TRAFFIC	1	LS	
30	202	CLEARING & GRUBBING (includes area for Channel Lining and see Note on Plan Sheet No. 1))	1	LS	
31	203	REMOVE EXISTING PAVEMENT (includes concrete portion)	300	SY	
32	203	REMOVE CONCRETE WALK	320	SF	
33	204	EXCAVATION FOR GRANULAR BASE	90	CY	
34	207	SUBGRADE RESHAPING & COMPACTING	300	SY	

NOT A BID FORM

		CITY OF SOUTHGATE 2019 STREET PROGRAM	PROJECT No. 190505	
BID TAB			BID DATE: 8/1/2019	
35	212/213	EROSION & WATER POLLUTION CONTROL	1	LS
36	214	WOVEN GEOTEXTILE, MIRAFI 600X OR EQUIVALENT	300	SY
37	SPL	GEOGRID (TENSAR BX-1200 OR APPROVED EQUIV)	300	SY
38	302/SPL*	CRUSHED STONE BASE (LESS THAN 7% FINES) FOR SUBGRADE REPAIR (INCLUDES EXCAVATION & DISPOSAL OF UNSUITABLE MATERIAL)*	20	CY
39	302	4" CRUSHED STONE BASE (LESS THAN 7% FINES)	35	CY
40	302	6" GRAVEL BASE, CLEAN No. 2 STONE	50	CY
41	402/403	ASPHALT PAVEMENT BASE COURSE (5")	45	CY
42	402/403	ASPHALT PAVEMENT LEVELING COURSE (1" AVG. DEPTH)	25	CY
43	402/403	ASPHALT PAVEMENT SURFACE COURSE (1-1/2") w/ ARAMID FIBER REINFORCEMENT - ACE FIBER OR EQUIVALENT)	35	CY
44	406	TACK COAT	50	GAL
45	408	PAVEMENT MILLING (2.5" TYP.)	500	SY
46	505	CONCRETE WALK	260	SF
47	505	CONCRETE DRIVE APRON REPLACEMENT	55	SF

NOT A BID FORM



CITY OF SOUTHGATE 2019 STREET PROGRAM

PROJECT No. 190505

BID TAB

BID DATE: 8/1/2019

48	506	CONCRETE ROLLED CURB REPLACEMENT	18	LF
49	506	CONCRETE VERTICAL CURB (INCLUDES CONSTRUCTING 24" WIDE OPENING FOR DRAINAGE)	173	LF
50	SPL *	FULL DEPTH PAVEMENT REPAIR AS PER PLAN - CONTINGENCY	100	SY
51	703	CLASS III CHANNEL LINING (INCLUDES GEOTEXTILE FABRIC PER DETAIL)	20	TON
52	704	4" RIGID PVC UNDERDRAIN - INCLUDES OUTLET	75	LF
53	SPL	SANITARY SEWER MANHOLE ADJUSTED TO GRADE PER SD1 REGULATIONS	1	EA
54	SPL	WATER VALVE / MANHOLE ADJUSTED TO GRADE PER NKWD REGULATIONS	3	EA
55	SPL	GAS VALVE ADJUSTED TO GRADE PER DUKE ENERGY REGULATIONS	2	EA

NOT A BID FORM



CITY OF SOUTHGATE 2019 STREET PROGRAM

PROJECT No. 190505

BID TAB

BID DATE: 8/1/2019

SHALER STREET				
56	110	MOBILIZATION	1	LS
57	112	MAINTENANCE OF TRAFFIC	1	LS
58	402/403	ASPHALT PAVEMENT LEVELING COURSE (1" AVG. DEPTH)	8	CY
59	402/403	ASPHALT PAVEMENT SURFACE COURSE (1-1/2") w/ ARAMID FIBER REINFORCEMENT - ACE FIBER OR EQUIVALENT)	12	CY
60	406	TACK COAT	29	GAL
61	408	PAVEMENT MILLING (2.5" TYP.)	300	SY