

NOT A BID FORM



PROJECT: EAST FOSTER-MAINEVILLE RD / MULBERRY ST REHABILITATION
 OWNER: VILLAGE OF MAINEVILLE, OH
 PROJECT #:190595



ADDENDUM #1 BID DATE & TIME: OCTOBER 18, 2019 AT 10:00 AM

Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure
EAST FOSTER-MAINEVILLE ROAD				
1	251	* PARTIAL DEPTH PAVEMENT REPAIR, AS PER PLAN	202	SY
2	253	* PAVEMENT REPAIR, AS PER PLAN	101	SY
3	254	PAVEMENT PLANING, ASPHALT CONCRETE, (2-1/2")	4,043	SY
4	407	SPECIAL, TACK COAT, TRACKLESS TACK, AS PER PLAN @ 0.075 GAL/SY	304	GAL
5	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1 (448), PG64-22 (1-1/2")	169	CY
6	441	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1 (448) (1")	112	CY
7	441	ASPHALT CONCRETE, MISC.: 1/2" STRESS ABSORBING MEMBRANE INTERLAYER (SAMI) TYPE 1	4,043	SY
8	608	* WALKWAY, MISC.: 5" CONCRETE WALK, INC LUDING REMOVAL OF UNCLASSIFIED MATERIAL	724	SF
9	608	* WALKWAY, MISC.: 7" CONCRETE WALK, INC LUDING REMOVAL OF UNCLASSIFIED MATERIAL	316	SF
10	611	CATCH BASIN NO. 2-2B, INCLUDING THE REMOVAL OF EXISTING CATCH BASIN AND TIE-INS	2	EACH
11	SPL	* MANHOLE ADJUSTED TO GRADE, SANITARY SEWER MANHOLE ADJUSTED TO GRADE; AS PER PLAN; LABOR AND MATERIAL	5	EACH
12	SPL	* MANHOLE REPAIRED AND ADJUSTED TO GRADE, SANITARY MANHOLE. AS PER PLAN; LABOR AND MATERIAL	5	EACH

*DENOTES CONTINGENCY ITEM - USE ONLY AT THE DIRECTION OF THE ENGINEER

NOT A BID FORM



PROJECT: EAST FOSTER-MAINEVILLE RD / MULBERRY ST REHABILITATION
 OWNER: VILLAGE OF MAINEVILLE, OH
 PROJECT #:190595



ADDENDUM #1

BID DATE & TIME: OCTOBER 18, 2019 AT 10:00 AM

Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure
13	SPL	* BRICK MASONRY MANHOLE REPAIR, SANITARY SEWER MANHOLE, AS PER PLAN; LABOR AND MATERIAL	5	EACH
14	614	MAINTAINING TRAFFIC	1	LS
15	644	EDGE LINE, 4"	0.53	MILE
16	644	CENTER LINE, 4"	0.30	MILE
17	644	STOP LINE, 24"	11	FT
18	644	CROSSWALK LINE, 12"	93	FT
19	644	TRANSVERSE / DIAGONAL LINE, 24"	60	FT
20	644	TRANSVERSE / DIAGONAL LINE, 6"	20	FT
21	644	SCHOOL SYMBOL MARKING, 96"	1	EACH
22	644	PARKING LOT STALL MARKING	50	FT
MULBERRY STREET				
23	251	* PARTIAL DEPTH PAVEMENT REPAIR, AS PER PLAN	116	SY
24	253	* PAVEMENT REPAIR, AS PER PLAN	16	SY
25	254	PAVEMENT PLANING, ASPHALT CONCRETE, (2-1/2")	2,596	SY

*DENOTES CONTINGENCY ITEM - USE ONLY AT THE DIRECTION OF THE ENGINEER

NOT A BID FORM

 <p>VILLAGE OF MAINEVILLE EST. 1815</p>	<p>PROJECT: EAST FOSTER-MAINEVILLE RD / MULBERRY ST REHABILITATION OWNER: VILLAGE OF MAINEVILLE, OH PROJECT #:190595</p> <p>ADDENDUM #1 BID DATE & TIME: OCTOBER 18, 2019 AT 10:00 AM</p>	 <p>GT consultants engineers architects planners</p>
---	---	---

Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure
26	407	SPECIAL, TACK COAT, TRACKLESS TACK, AS PER PLAN @ 0.075 GAL/SY (ADDENDUM #1)	195	GAL
27	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1 (448), PG64-22 (1-1/2")	109	CY
28	441	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1 (448) (1")	72	CY
29	441	ASPHALT CONCRETE, MISC.: 1/2" STRESS ABSORBING MEMBRANE INTERLAYER (SAMI) TYPE 1	2,596	SY
30	609	CURB MISC.: ROLLED CONCRETE CURB, INCLUDING PLAIN PORTLAND CEMENT CONCRETE FILL (CLASS QC1) AND SPOT REMOVAL AND REPLACEMENT, AS PER DETAIL	146	FT
31	SPL	* MANHOLE ADJUSTED TO GRADE, SANITARY SEWER MANHOLE ADJUSTED TO GRADE; AS PER PLAN; LABOR AND MATERIAL	1	EACH
32	SPL	* MANHOLE REPAIRED AND ADJUSTED TO GRADE, SANITARY MANHOLE. AS PER PLAN; LABOR AND MATERIAL	1	EACH
33	SPL	* BRICK MASONRY MANHOLE REPAIR, SANITARY SEWER MANHOLE, AS PER PLAN; LABOR AND MATERIAL	1	EACH
34	614	MAINTAINING TRAFFIC	1	LS
35	644	STOP LINE	11	FT

*DENOTES CONTINGENCY ITEM - USE ONLY AT THE DIRECTION OF THE ENGINEER