

## ADDENDUM #1

**Job #:** 190595      **Project Title:** EAST FOSTER-MAINEVILLE RD / MULBERRY ST REHABILITATION

**Client:** VILLAGE OF MAINEVILLE

**Issue Date:** TUESDAY, OCTOBER 15, 2019

**Bid Date:** FRIDAY, OCTOBER 18, 2019 (UNCHANGED)

THIS IS TO CERTIFY THAT YOU ARE IN RECEIPT OF ADDENDUM #1 FOR THE ABOVE-MENTIONED PROJECT.

PLEASE SIGN AND RETURN BY FAX ( 513.791.1936 ) TO THE ATTENTION OF RHONDA FOMBY OR YOU MAY RESPOND VIA EMAIL TO: rfomby@ctconsultants.com.

\_\_\_\_\_  
Name / Title:

\_\_\_\_\_  
Company:

\_\_\_\_\_  
Date:

### ADDITIONS/CHANGE:

On the Bid Quantities Sheet, Line Item 26, SPECIAL TACK COAT, TRACKLESS TACK, AS PER PLAN @ 0.075 GAL/SY, 195 SY;

Should read: SPECIAL TACK COAT, TRACKLESS TACK, AS PER PLAN @ 0.075 GAL/SY, **195 GAL**

Please change out Page 3 of the Bid Quantities with the attached corrected sheet.

**END OF ADDENDUM #**



**PROJECT: EAST FOSTER-MAINEVILLE RD / MULBERRY ST REHABILITATION**  
**OWNER: VILLAGE OF MAINEVILLE, OH**  
**PROJECT #:190595**



**ADDENDUM #1**      **BID DATE & TIME: OCTOBER 18, 2019 AT 10:00 AM**

Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure	Unit Cost Total	Item Cost
<b>EAST FOSTER-MAINEVILLE ROAD</b>						
1	251	* PARTIAL DEPTH PAVEMENT REPAIR, AS PER PLAN	202	SY		
2	253	* PAVEMENT REPAIR, AS PER PLAN	101	SY		
3	254	PAVEMENT PLANING, ASPHALT CONCRETE, (2-1/2")	4,043	SY		
4	407	SPECIAL, TACK COAT, TRACKLESS TACK, AS PER PLAN @ 0.075 GAL/SY	304	GAL		
5	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1 (448), PG64-22 (1-1/2")	169	CY		
6	441	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1 (448) (1")	112	CY		
7	441	ASPHALT CONCRETE, MISC.: 1/2" STRESS ABSORBING MEMBRANE INTERLAYER (SAMI) TYPE 1	4,043	SY		
8	608	* WALKWAY, MISC.: 5" CONCRETE WALK, INC LUDING REMOVAL OF UNCLASSIFIED MATERIAL	724	SF		
9	608	* WALKWAY, MISC.: 7" CONCRETE WALK, INC LUDING REMOVAL OF UNCLASSIFIED MATERIAL	316	SF		
10	611	CATCH BASIN NO. 2-2B, INCLUDING THE REMOVAL OF EXISTING CATCH BASIN AND TIE-INS	2	EACH		
11	SPL	* MANHOLE ADJUSTED TO GRADE, SANITARY SEWER MANHOLE ADJUSTED TO GRADE; AS PER PLAN; LABOR AND MATERIAL	5	EACH		
12	SPL	* MANHOLE REPAIRED AND ADJUSTED TO GRADE, SANITARY MANHOLE. AS PER PLAN; LABOR AND MATERIAL	5	EACH		

\*DENOTES CONTINGENCY ITEM - USE ONLY AT THE DIRECTION OF THE ENGINEER



**PROJECT: EAST FOSTER-MAINEVILLE RD / MULBERRY ST REHABILITATION**  
**OWNER: VILLAGE OF MAINEVILLE, OH**  
**PROJECT #:190595**



**ADDENDUM #1**      **BID DATE & TIME: OCTOBER 18, 2019 AT 10:00 AM**

Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure	Unit Cost Total	Item Cost
13	SPL	* BRICK MASONRY MANHOLE REPAIR, SANITARY SEWER MANHOLE, AS PER PLAN; LABOR AND MATERIAL	5	EACH		
14	614	MAINTAINING TRAFFIC	1	LS		
15	644	EDGE LINE, 4"	0.53	MILE		
16	644	CENTER LINE, 4"	0.30	MILE		
17	644	STOP LINE, 24"	11	FT		
18	644	CROSSWALK LINE, 12"	93	FT		
19	644	TRANSVERSE / DIAGONAL LINE, 24"	60	FT		
20	644	TRANSVERSE / DIAGONAL LINE, 6"	20	FT		
21	644	SCHOOL SYMBOL MARKING, 96"	1	EACH		
22	644	PARKING LOT STALL MARKING	50	FT		
<b>SUB - TOTAL EAST FOSTER-MAINEVILLE ROAD</b>						
<b>MULBERRY STREET</b>						
23	251	* PARTIAL DEPTH PAVEMENT REPAIR, AS PER PLAN	116	SY		
24	253	* PAVEMENT REPAIR, AS PER PLAN	16	SY		
25	254	PAVEMENT PLANING, ASPHALT CONCRETE, (2-1/2")	2,596	SY		

\*DENOTES CONTINGENCY ITEM - USE ONLY AT THE DIRECTION OF THE ENGINEER



**PROJECT: EAST FOSTER-MAINEVILLE RD / MULBERRY ST REHABILITATION**  
**OWNER: VILLAGE OF MAINEVILLE, OH**  
**PROJECT #:190595**

**ADDENDUM #1**      **BID DATE & TIME: OCTOBER 18, 2019 AT 10:00 AM**



Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure	Unit Cost Total	Item Cost
26	407	SPECIAL, TACK COAT, TRACKLESS TACK, AS PER PLAN @ 0.075 GAL/SY <b>(ADDENDUM #1)</b>	195	GAL		
27	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1 (448), PG64-22 (1-1/2")	109	CY		
28	441	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1 (448) (1")	72	CY		
29	441	ASPHALT CONCRETE, MISC.: 1/2" STRESS ABSORBING MEMBRANE INTERLAYER (SAMI) TYPE 1	2,596	SY		
30	609	CURB MISC.: ROLLED CONCRETE CURB, INCLUDING PLAIN PORTLAND CEMENT CONCRETE FILL (CLASS QC1) AND SPOT REMOVAL AND REPLACEMENT, AS PER DETAIL	146	FT		
31	SPL	* MANHOLE ADJUSTED TO GRADE, SANITARY SEWER MANHOLE ADJUSTED TO GRADE; AS PER PLAN; LABOR AND MATERIAL	1	EACH		
32	SPL	* MANHOLE REPAIRED AND ADJUSTED TO GRADE, SANITARY MANHOLE. AS PER PLAN; LABOR AND MATERIAL	1	EACH		
33	SPL	* BRICK MASONRY MANHOLE REPAIR, SANITARY SEWER MANHOLE, AS PER PLAN; LABOR AND MATERIAL	1	EACH		
34	614	MAINTAINING TRAFFIC	1	LS		
35	644	STOP LINE	11	FT		
<b>SUB - TOTAL MULBERRY STREET</b>						
<b>PROJECT TOTAL COST</b>						

\*DENOTES CONTINGENCY ITEM - USE ONLY AT THE DIRECTION OF THE ENGINEER