

# NOT A BID FORM

**CT Consultants, Inc.**

Project: **LAKESIDE PARK 2020 STREET PROGRAM**  
**LAKESIDE PARK, KENTUCKY**

Date: **03/19/20**  
 Project No.: **191020**

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
<b>PART A - GEISEN AVE</b>				
1	110	MOBILIZATION	1	LS
2	112	MAINTENANCE OF TRAFFIC	1	LS
3	202	CLEARING AND GRUBBING , (INCLUDES REMOVAL AND REINSTALLATION OF SIGNS AND MAILBOXES)	1	LS
4	203	REMOVE EXISTING CATCH BASIN	4	EA
5	204	REMOVE EXISTING ROADWAY INCLUDING EXISTING CURB	1,600	SY
6	204	EXCAVATION FOR GRANULAR BASE	1,600	SY
7	207	SUBGRADE RESHAPING AND COMPACTING	1,600	SY
8	SPL	YARD RESTORATION (4" TOPSOIL, SEED AND MULCH)	600	SY
9	SPL	EROSION & WATER POLLUTION CONTROL	1	LS
10	214	MIRAFI 600X OR EQUIVALENT WOVEN GEOTEXTILE	1,500	SY
11	302	4" CRUSHED STONE BASE	1,600	SY

\* CONTINGENCY ITEM - TO BE USED AT THE ENGINEER'S DIRECTION

# NOT A BID FORM

CT Consultants, Inc.

Project: LAKESIDE PARK 2020 STREET PROGRAM  
LAKESIDE PARK, KENTUCKY

Date: 03/19/20  
Project No.: 191020

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
12	320/SPL*	CRUSHED STONE BASE, (LESS THAN 7% FINES) FOR SUBGRADE REPAIR (INCLUDES EXCAVATION AND DISPOSAL OF UNSUITABLE MATERIAL)	55	CY
13	SPL*	GEOGRID REINFORCEMENT FOR SUBGRADE REPAIR (TENSAR BX 1200 OR EQUIVALENT)	160	SY
14	SPL	8" PCC PAVEMENT WITH INTEGRAL 3" ROLLED CURB	1,300	SY
15	SPL	8" PCC PAVEMENT WITH INTEGRAL 3" ROLLED CURB - 3 DAY	300	SY
16	SPL	6" CONCRETE APRON/DRIVEWAY REPLACEMENT	1,200	SF
17	SPL	4" CONCRETE SIDEWALK REPLACEMENT	450	SF
18	SPL	ADA CURB RAMP	5	EA
19	704	4" RIGID PERFORATED PVC UNDERDRAIN SYSTEM (INCLUDES TRANSVERSE UNDERDRAINS)	1,050	LF
20	704	6" SOLID WALL PVC DOWNSPOUT COLLECTOR LINE (IN COMMON TRENCH WITH UNDERDRAIN SYSTEM)	150	LF
21	SPL	DOWNSPOUT CONNECTION TO DOWNSPOUT COLLECTOR LINE (INCLUDES PVC PIPE, COUPLINGS, CLEANOUT AND REMOVAL OF EXISTING DOWNSPOUT PIPE)	2	EA
22	SPL	DOUBLE GRATE CURB INLET	4	EA

# NOT A BID FORM

**CT Consultants, Inc.**

Project: **LAKESIDE PARK 2020 STREET PROGRAM  
LAKESIDE PARK, KENTUCKY**

Date: **03/19/20**  
Project No.: **191020**

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
23	SPL	ADJUST SANITARY MANHOLE TO GRADE	1	EA
24	SPL	ADJUST GAS VALVE TO GRADE	4	EA
25	SPL	ADJUST WATER METER TO GRADE	4	EA
<b>PART A - TOTAL</b>				

# NOT A BID FORM

CT Consultants, Inc.

Project: LAKESIDE PARK 2020 STREET PROGRAM  
LAKESIDE PARK, KENTUCKY

Date: 03/19/20  
Project No.: 191020

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
<b>PART B - PENWOOD ROAD/LOCUST AVE</b>				
1	110	MOBILIZATION	1	LS
2	112	MAINTENANCE OF TRAFFIC	1	LS
3	202	CLEARING AND GRUBBING , (INCLUDES REMOVAL AND REINSTALLATION OF SIGNS AND MAILBOXES)	1	LS
4	204	REMOVE EXISTING ROADWAY INCLUDING EXISTING CURB	800	SY
5	204	EXCAVATION FOR GRANULAR BASE	800	SY
6	207	SUBGRADE RESHAPING AND COMPACTING	800	SY
7	SPL	YARD RESTORATION (4" TOPSOIL, SEED AND MULCH)	215	SY
8	SPL	EROSION & WATER POLLUTION CONTROL	1	LS
9	214	MIRAFI 600X OR EQUIVALENT WOVEN GEOTEXTILE	740	SY
10	302	4" CRUSHED STONE BASE	800	SY
11	320/SPL*	CRUSHED STONE BASE, (LESS THAN 7% FINES) FOR SUBGRADE REPAIR (INCLUDES EXCAVATION AND DISPOSAL OF UNSUITABLE MATERIAL)	30	CY

# NOT A BID FORM

CT Consultants, Inc.

Project: LAKESIDE PARK 2020 STREET PROGRAM  
LAKESIDE PARK, KENTUCKY

Date: 03/19/20  
Project No.: 191020

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
12	SPL*	GEOGRID REINFORCEMENT FOR SUBGRADE REPAIR (TENSAR BX 1200 OR EQUIVALENT)	80	SY
13	SPL	8" PCC PAVEMENT WITH INTEGRAL 4" ROLLED CURB	800	SY
14	SPL	6" CONCRETE APRON/DRIVEWAY REPLACEMENT	200	SF
15	704	4" RIGID PERFORATED PVC UNDERDRAIN SYSTEM (INCLUDES TRANSVERSE UNDERDRAINS)	570	LF
16	SPL	DOWNSPOUT EXTENSTION THROUGH CURB	3	EA
17	SPL	ADJUST SANITARY MANHOLE TO GRADE	1	EA
18	SPL	EDGE DRAIN - EXCAVATION, NO. 57 STONE BACKFILL, & NON WOVEN GEOTEXTILE (MIRAFI 140N OR EQUIVALENT)	1	LS
<b>PART B - TOTAL</b>				

# NOT A BID FORM

<b>CT Consultants, Inc.</b> <b>LAKESIDE PARK 2020 STREET PROGRAM</b> <b>LAKESIDE PARK, KENTUCKY</b> <b>PRELIMINARY OPINION OF CONSTRUCTION COST</b>				
Project:				Date: 03/16/20
				Project No.: 191020
ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
<b>PART C - MARLO WAY</b>				
1	110	MOBILIZATION	1	LS
2	112	MAINTENANCE OF TRAFFIC	1	LS
3	202	CLEARING AND GRUBBING , (INCLUDES REMOVAL AND REINSTALLATION OF SIGNS AND MAILBOXES)	1	LS
4	204	REMOVE EXISTING ROADWAY INCLUDING EXISTING CURB	150	SY
5	SPL	YARD RESTORATION (4" TOPSOIL, SEED AND MULCH)	25	SY
6	SPL	EROSION & WATER POLLUTION CONTROL	1	LS
7	SPL	8" PCC PAVEMENT WITH INTEGRAL 4" ROLLED CURB	150	SY
<b>PART C - TOTAL</b>				

# NOT A BID FORM

CT Consultants, Inc.				
Project:		LAKESIDE PARK 2020 STREET PROGRAM LAKESIDE PARK, KENTUCKY	Date:	03/19/20
			Project No.:	191020
ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
<b>PART D - N ASHBROOK CUL-DE-SAC</b>				
1	110	MOBILIZATION	1	LS
2	112	MAINTENANCE OF TRAFFIC	1	LS
3	202	CLEARING AND GRUBBING , (INCLUDES REMOVAL AND REINSTALLATION OF SIGNS AND MAILBOXES)	1	LS
4	204	REMOVE EXISTING ROADWAY INCLUDING EXISTING CURB	375	SY
5	204	EXCAVATION FOR GRANULAR BASE	375	SY
6	207	SUBGRADE RESHAPING AND COMPACTING	375	SY
7	SPL	YARD RESTORATION (4" TOPSOIL, SEED AND MULCH)	50	SY
8	SPL	EROSION & WATER POLLUTION CONTROL	1	LS
9	214	MIRAFI 600X OR EQUIVALENT WOVEN GEOTEXTILE	350	SY
10	302	4" CRUSHED STONE BASE	375	SY
11	320/SPL*	CRUSHED STONE BASE, (LESS THAN 7% FINES) FOR SUBGRADE REPAIR (INCLUDES EXCAVATION AND DISPOSAL OF UNSUITABLE MATERIAL)	15	CY
12	SPL*	GEOGRID REINFORCEMENT FOR SUBGRADE REPAIR (TENSAR BX 1200 OR EQUIVALENT)	38	SY

# NOT A BID FORM

CT Consultants, Inc.

Project: LAKESIDE PARK 2020 STREET PROGRAM  
LAKESIDE PARK, KENTUCKY

Date: 03/19/20  
Project No.: 191020

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
13	SPL	8" PCC PAVEMENT WITH INTEGRAL 4" ROLLED CURB	375	SY
14	SPL	6" CONCRETE APRON/DRIVEWAY REPLACEMENT	70	SF
15	704	4" RIGID PERFORATED PVC UNDERDRAIN SYSTEM (INCLUDES TRANSVERSE UNDERDRAINS)	200	LF
16	704	6" SOLID WALL PVC DOWNSPOUT COLLECTOR LINE (IN COMMON TRENCH WITH UNDERDRAIN SYSTEM)	90	LF
17	SPL	DOWNSPOUT CONNECTION TO DOWNSPOUT COLLECTOR LINE (INCLUDES PVC PIPE, COUPLINGS, CLEANOUT AND REMOVAL OF EXISTING DOWNSPOUT PIPE)	1	EA
18	SPL	REMOVE/REPLACE EXIST. CURB INLET TOP SECTION AND CASTING/GRATE W/ DOUBLE VANE GRATE.	1	EA
PART D - TOTAL				



# NOT A BID FORM

CT Consultants, Inc.				
Project:		LAKESIDE PARK 2020 STREET PROGRAM LAKESIDE PARK, KENTUCKY	Date:	03/19/20
			Project No.:	191020
ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
<b>PART E - APPLEWOOD DR</b>				
1	110	MOBILIZATION	1	LS
2	112	MAINTENANCE OF TRAFFIC	1	LS
3	204	REMOVE EXISTING ROADWAY INCLUDING EXISTING CURB	25	SY
4	SPL	EROSION & WATER POLLUTION CONTROL	1	LS
5	SPL	8" PCC PAVEMENT WITH INTEGRAL 4" ROLLED CURB	15	SY
6	713	DOUBLE YELLOW - PAINT	35	LF
7	713	6" WHITE CROSSWALK - PAINT	140	LF
8	713	24" WHITE STOP BAR - PAINT	20	LF
9	713	DIAGONAL HATCHING - YELLOW PAINT (4" WIDE @ 2' SPACING)	1	LS
10	SPL	12" TOPSOIL	10	SY
<b>PART E - TOTAL</b>				
<b>TOTAL BID - PART A+B+C+D+E</b>				