



## ADDENDUM #1

**Job #:** 200167      **Project Title** Fort Wright 2020 Concrete Street Program

**Client:** City of Fort Wright

**Issue Date:** May 11, 2020

**Bid Date:** May 14, 2020

THIS IS TO CERTIFY THAT YOU ARE IN RECEIPT OF ADDENDUM #1 FOR THE ABOVE-MENTIONED PROJECT. PLEASE SIGN AND RETURN TO: [pbellew@ctconsultants.com](mailto:pbellew@ctconsultants.com).

\_\_\_\_\_  
Name / Title:

\_\_\_\_\_  
Company:

\_\_\_\_\_  
Date:

Please note the updated quantities on Line 10 on Part B – Ridgemont Avenue –

302 – 4” CRUSHED STONE BASE – 1100 SY

AN UPDATED BID TAB IS ATTACHED.

**ADDENDUM #1 - May 11, 2020**

**CT Consultants, Inc.**  
**FORT WRIGHT 2020 CONCRETE STREET PROGRAM**  
**FORT WRIGHT, KENTUCKY**

Date: 04/30/20  
 Project No.: 200167

Project:

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure	Unit Cost Total	Total Amount Bid
<b>PART A - HELEN RUTH DRIVE</b>						
1	110	MOBILIZATION	1	LS		
2	112	MAINTENANCE OF TRAFFIC	1	LS		
3	202	CLEARING AND GRUBBING , (INCLUDES REMOVAL AND REINSTALLATION OF SIGNS AND MAILBOXES)	1	LS		
4	203	REMOVE EXISTING CATCH BASIN	2	EA		
5	204	REMOVE EXISTING ROADWAY INCLUDING EXISTING CURB	2,400	SY		
6	205	EMBANKMENT	125	CY		
7	204	EXCAVATION	150	CY		
8	207	SUBGRADE RESHAPING AND COMPACTING	2,400	SY		
9	SPL	YARD RESTORATION (4" TOPSOIL, SEED AND MULCH)	1,800	SY		
10	SPL	EROSION & WATER POLLUTION CONTROL	1	LS		
11	214	MIRAFI 600X OR EQUIVALENT WOVEN GEOTEXTILE	2,250	SY		
12	302	4" CRUSHED STONE BASE	2,400	SY		

**ADDENDUM #1 - May 11, 2020**

**CT Consultants, Inc.  
FORT WRIGHT 2020 CONCRETE STREET PROGRAM  
FORT WRIGHT, KENTUCKY**

Date: 04/30/20  
Project No.: 200167

Project:

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure	Unit Cost Total	Total Amount Bid
13	320/SPL*	CRUSHED STONE BASE, (LESS THAN 7% FINES) FOR SUBGRADE REPAIR (INCLUDES EXCAVATION AND DISPOSAL OF UNSUITABLE MATERIAL)	80	CY		
14	SPL*	GEOGRID REINFORCEMENT FOR SUBGRADE REPAIR (TENSAR BX 1200 OR EQUIVALENT)	240	SY		
15	SPL	10" PCC PAVEMENT WITH INTEGRAL 3" ROLLED CURB	2,400	SY		
16	SPL	8" CONCRETE APRON/DRIVEWAY REPLACEMENT (INCLUDES CURB WHERE INDICATED)	2,000	SF		
17	SPL	8" CONCRETE APRON/DRIVEWAY REPLACEMENT WITH GRAVEL BASE (INCLUDES CURB WHERE INDICATED)	600	SF		
18	704	4" RIGID PERFORATED PVC UNDERDRAIN SYSTEM (INCLUDES TRANSVERSE UNDERDRAINS)	1,615	LF		
19	SPL	DOUBLE GRATE CURB INLET	2	EA		
20	SPL	ADJUST SANITARY MANHOLE TO GRADE	1	EA		
21	SPL	ADJUST CURB INLET TO GRADE	3	EA		
		<b>PART A -TOTAL</b>				

**ADDENDUM #1 - MAY 11, 2020**

**CT Consultants, Inc.**  
**FORT WRIGHT 2020 CONCRETE STREET PROGRAM**  
**FORT WRIGHT, KENTUCKY**

Date: 04/30/20  
 Project No.: 200167

Project:

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure	Unit Cost Total	Total Amount Bid
		<b>PART B - RIDGEMONT AVE</b>				
1	110	MOBILIZATION	1	LS		
2	112	MAINTENANCE OF TRAFFIC	1	LS		
3	202	CLEARING AND GRUBBING , (INCLUDES REMOVAL AND REINSTALLATION OF SIGNS AND MAILBOXES)	1	LS		
4	204	REMOVE EXISTING ROADWAY INCLUDING EXISTING CURB	1,000	SY		
5	204	EXCAVATION FOR GRANULAR BASE	1,100	SY		
6	207	SUBGRADE RESHAPING AND COMPACTING	1,100	SY		
7	SPL	YARD RESTORATION (4" TOPSOIL, SEED AND MULCH)	600	SY		
8	SPL	EROSION & WATER POLLUTION CONTROL	1	LS		
9	214	MIRAFI 600X OR EQUIVALENT WOVEN GEOTEXTILE	1,000	SY		
10	302	4" CRUSHED STONE BASE	1,100	SY		
11	320/SPL*	CRUSHED STONE BASE, (LESS THAN 7% FINES) FOR SUBGRADE REPAIR (INCLUDES EXCAVATION AND DISPOSAL OF UNSUITABLE MATERIAL)	33	CY		

**ADDENDUM #1 - MAY 11, 2020**

**CT Consultants, Inc.  
FORT WRIGHT 2020 CONCRETE STREET PROGRAM  
FORT WRIGHT, KENTUCKY**

Project:

Date: 04/30/20  
Project No.: 200167

ITEM NO.	SPEC NO.	ITEM	Estimated Quantity	Unit of Measure	Unit Cost Total	Total Amount Bid
12	SPL*	GEOGRID REINFORCEMENT FOR SUBGRADE REPAIR (TENSAR BX 1200 OR EQUIVALENT)	100	SY		
13	SPL	8" PCC PAVEMENT WITH INTEGRAL 3" ROLLED CURB	1,100	SY		
14	SPL	ASPHALT DRIVEWAY REPLACEMENT (INCLUDES CURB)	100	SF		
15	SPL	6" CONCRETE APRON/DRIVEWAY REPLACEMENT	1,200	SF		
16	SPL	4" CONCRETE SIDEWALK REPLACEMENT	600	SF		
17	704	4" RIGID PERFORATED PVC UNDERDRAIN SYSTEM (INCLUDES TRANSVERSE UNDERDRAINS)	1,000	LF		
18	704	UNDERDRAIN OUTLET (4" SOLID PVC PIPE)	50	LF		
19	SPL	ADJUST SANITARY MANHOLE TO GRADE	1	EA		
		<b>PART B - TOTAL</b>				
		<b>PART A + B - TOTAL</b>				