

# NOT A BID FORM

CT Consultants, Inc.				
Project:		<b>FORT WRIGHT 2020 CONCRETE STREET PROGRAM FORT WRIGHT, KENTUCKY</b>		Date: 04/30/20 Project No.: 200167
ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
<b>PART A - HELEN RUTH DRIVE</b>				
1	110	MOBILIZATION	1	LS
2	112	MAINTENANCE OF TRAFFIC	1	LS
3	202	CLEARING AND GRUBBING , (INCLUDES REMOVAL AND REINSTALLATION OF SIGNS AND MAILBOXES)	1	LS
4	203	REMOVE EXISTING CATCH BASIN	2	EA
5	204	REMOVE EXISTING ROADWAY INCLUDING EXISTING CURB	2,400	SY
6	205	EMBANKMENT	125	CY
7	204	EXCAVATION	150	CY
8	207	SUBGRADE RESHAPING AND COMPACTING	2,400	SY
9	SPL	YARD RESTORATION (4" TOPSOIL, SEED AND MULCH)	1,800	SY
10	SPL	EROSION & WATER POLLUTION CONTROL	1	LS
11	214	MIRAFI 600X OR EQUIVALENT WOVEN GEOTEXTILE	2,250	SY
12	302	4" CRUSHED STONE BASE	2,400	SY

# NOT A BID FORM

CT Consultants, Inc.				
Project:		<b>FORT WRIGHT 2020 CONCRETE STREET PROGRAM FORT WRIGHT, KENTUCKY</b>		Date: 04/30/20 Project No.: 200167
ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
13	320/SPL*	CRUSHED STONE BASE, (LESS THAN 7% FINES) FOR SUBGRADE REPAIR (INCLUDES EXCAVATION AND DISPOSAL OF UNSUITABLE MATERIAL)	80	CY
14	SPL*	GEOGRID REINFORCEMENT FOR SUBGRADE REPAIR (TENSAR BX 1200 OR EQUIVALENT)	240	SY
15	SPL	10" PCC PAVEMENT WITH INTEGRAL 3" ROLLED CURB	2,400	SY
16	SPL	8" CONCRETE APRON/DRIVEWAY REPLACEMENT (INCLUDES CURB WHERE INDICATED)	2,000	SF
17	SPL	8" CONCRETE APRON/DRIVEWAY REPLACEMENT WITH GRAVEL BASE (INCLUDES CURB WHERE INDICATED)	600	SF
18	704	4" RIGID PERFORATED PVC UNDERDRAIN SYSTEM (INCLUDES TRANSVERSE UNDERDRAINS)	1,615	LF
19	SPL	DOUBLE GRATE CURB INLET	2	EA
20	SPL	ADJUST SANITARY MANHOLE TO GRADE	1	EA
21	SPL	ADJUST CURB INLET TO GRADE	3	EA
<b>PART A -TOTAL</b>				

# NOT A BID FORM

CT Consultants, Inc.				
Project:		<b>FORT WRIGHT 2020 CONCRETE STREET PROGRAM FORT WRIGHT, KENTUCKY</b>		Date: 04/30/20 Project No.: 200167
ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
<b>PART B - RIDGEMONT AVE</b>				
1	110	MOBILIZATION	1	LS
2	112	MAINTENANCE OF TRAFFIC	1	LS
3	202	CLEARING AND GRUBBING , (INCLUDES REMOVAL AND REINSTALLATION OF SIGNS AND MAILBOXES)	1	LS
4	204	REMOVE EXISTING ROADWAY INCLUDING EXISTING CURB	1,000	SY
5	204	EXCAVATION FOR GRANULAR BASE	1,100	SY
6	207	SUBGRADE RESHAPING AND COMPACTING	1,100	SY
7	SPL	YARD RESTORATION (4" TOPSOIL, SEED AND MULCH)	600	SY
8	SPL	EROSION & WATER POLLUTION CONTROL	1	LS
9	214	MIRAFI 600X OR EQUIVALENT WOVEN GEOTEXTILE	1,000	SY
10	302	4" CRUSHED STONE BASE	1,000	SY
11	320/SPL*	CRUSHED STONE BASE, (LESS THAN 7% FINES) FOR SUBGRADE REPAIR (INCLUDES EXCAVATION AND DISPOSAL OF UNSUITABLE MATERIAL)	33	CY

# NOT A BID FORM

	<b>CT Consultants, Inc.</b>			
Project:	<b>FORT WRIGHT 2020 CONCRETE STREET PROGRAM FORT WRIGHT, KENTUCKY</b>	Date:	04/30/20	
		Project No.:	200167	

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
12	SPL*	GEOGRID REINFORCEMENT FOR SUBGRADE REPAIR (TENSAR BX 1200 OR EQUIVALENT)	100	SY
13	SPL	8" PCC PAVEMENT WITH INTEGRAL 3" ROLLED CURB	1,100	SY
14	SPL	ASPHALT DRIVEWAY REPLACEMENT (INCLUDES CURB)	100	SF
15	SPL	6" CONCRETE APRON/DRIVEWAY REPLACEMENT	1,200	SF
16	SPL	4" CONCRETE SIDEWALK REPLACEMENT	600	SF
17	704	4" RIGID PERFORATED PVC UNDERDRAIN SYSTEM (INCLUDES TRANSVERSE UNDERDRAINS)	1,000	LF
18	704	UNDERDRAIN OUTLET (4" SOLID PVC PIPE)	50	LF
19	SPL	ADJUST SANITARY MANHOLE TO GRADE	1	EA
		<b>PART B - TOTAL</b>		
		<b>PART A +B - TOTAL</b>		